



Contractor Select™  
**WPX LED**  
Wall packs

The WPX LED wall packs are energy efficient, cost effective, and aesthetically appealing. Full cut-off solution for both new construction and HSI wall pack replacement/renewal opportunities. Reliable IP66 construction and excellent LED lumen maintenance ensure a long service life.

**FEATURES:**

- Architectural design at very economical prices
- Energy efficient - payback in less than two years
- Wide range of configuration options available

Note: WPX3 lumen package and all the WPX configuration options are not included in the Contractor Select program. For more information, please visit [WPL LED](#).




**D-Series Size 2**  
LED Area Luminaire



**Specifications**

EPA: 1.06 ft<sup>2</sup>  
20 fpm  
Length: 40.59"  
1031 mm  
Width: 16.76"  
425 mm  
Height H1: 8.11"  
206 mm  
Height H2: 3.95"  
100 mm  
Weight: 46 lbs  
20 kg



Provide light fixtures as shown on Fixture Schedule. Substitutions shall have prior approval by the Project Engineer before bid date. Being listed as an acceptable Manufacturer in no way relieves the Contractors obligation to provide all equipment and features in accordance with these specifications.

**LIGHT FIXTURE SCHEDULE**

| TYPE | STYLE                              | MANUFACTURER/MODEL NUMBER                                    | LAMPS          | REMARKS                      |
|------|------------------------------------|--------------------------------------------------------------|----------------|------------------------------|
| Z    | DSX2 SINGLE-FACE FORWARD THROW LED | LITHONIA #DSX2-P240K-70CRI-T2M-WVOLT-SPA-PIR-HS-DBLXD_1      | 179W LED       | MOUNT 24" AFG ON SQUARE POLE |
| Z1   | DSX2 DOUBLE-FACE FORWARD THROW LED | LITHONIA #DSX2-PS-40K-70CRI-T2M-WVOLT-SPA-WPA-PIR-HS-DBLXD_1 | 179W LED       | MOUNT 24" AFG ON SQUARE POLE |
| ZW   | WPX1 EXTERIOR WALL PACK            | GARCO #106L-16L-530-NW-G1-2-UNV-DD-BK                        | 2900LM 24W LED | INSTALL 10' AFG              |
| ZW1  | WPX1 EXTERIOR WALL PACK            | GARCO #106L-16L-530-NW-G1-4-UNV-DD-BK                        | 2900LM 24W LED | INSTALL 14' AFG              |
| ZW2  | WPX1 EXTERIOR WALL PACK            | GARCO #106L-32L-1000-NW-G1-4-UNV-DD-BK                       | 2900LM 24W LED | INSTALL 16' AFG              |

ISG

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DATE: \_\_\_\_\_ LIC. NO. \_\_\_\_\_

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

DATE: \_\_\_\_\_ LIC. NO. \_\_\_\_\_

**SHEET NOT VALID UNLESS THIS TEXT IS COLOR.**

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.  
© 2024 I & S GROUP, INC.

PROJECT

**THE STATION**

MANKATO MINNESOTA

| REVISION SCHEDULE |             |    |
|-------------------|-------------|----|
| DATE              | DESCRIPTION | BY |
|                   |             |    |
|                   |             |    |
|                   |             |    |
|                   |             |    |
|                   |             |    |
|                   |             |    |
|                   |             |    |

|                     |                     |
|---------------------|---------------------|
| PROJECT NO.         | 25-32735            |
| FILE NAME           | 32735-EX-ELECTRICAL |
| DRAWN BY            | AAQ                 |
| DESIGNED BY         | AAQ/NJH             |
| REVIEWED BY         | NJH                 |
| ORIGINAL ISSUE DATE | 10/1/24             |
| CLIENT PROJECT NO.  | -                   |

TITLE  
**SITE  
PHOTOMETRICS  
PLAN**

SHEET  
**E2-00**

