

Bid Proposal

NO.	ITEM	UNIT	QTY	PRICE	EXTENSION
1	MOBILIZATION	LS	1		
2	REMOVE CONCRETE CURB AND GUTTER	LF	1,150		
3	REMOVE 12 - 18 INCH RCP	LF	146		
4	REMOVE CONCRETE CROSS GUTTER	SQ YD	30		
5	REMOVE 2 X 3 CATCHBASIN	EACH	2		
6	REMOVE 48" STORM MANHOLE	EACH	3		
7	SAWING BITUMINOUS PAVEMENT	LIN FT	264		
8	SELECT TOPSOIL BORROW (6" DEPTH)	CY	65		
9	SALVAGE AGGREGATE AND EXPORT FROM SITE	CY	1,000		
10	4" AGGREGATE BASE, CLASS 5	TON	280		
11	MILL BITUMINOUS SURFACE FULL DEPTH, FULL WIDTH	SQ YD	17,600		
12	BITUMINOUS MATERIAL FOR TACK COAT	GAL	881		
13	1.5" WEARING COURSE SPWEA340B	TON	1,599		
14	2" NON-WEARING COURSE SPNWB330B	TON	2,132		
15	CONSTRUCT RC PIPE APRON 15 INCH	EACH	1		
16	CONSTRUCT RC PIPE APRON 18 INCH	EACH	2		
17	15" RC PIPE SEWER, DESIGN 3006	LIN FT	238		
18	18" RC PIPE SEWER, DESIGN 3006	LIN FT	1,200		
19	CONSTRUCT 2' x 3' STORM CATCH BASIN	EACH	4		
20	CONSTRUCT DRAINAGE STRUCTURE DESIGN 48-4020	EACH	11		
21	F&I CASTING ASSEMBLY (STORM)	EACH	15		
22	CONCRETE CURB & GUTTER DESIGN B618	LIN FT	1,150		
23	6" CONCRETE CROSS GUTTER	SQ YD	30		
24	TRAFFIC CONTROL	LS	1		
25	SILT FENCE, HEAVY DUTY	LF	500		
26	INLET PROTECTION	EACH	5		
27	SEEDING	SY	350		
28	SEED, TYPE 270	LBS	14		
29	MULCH MATERIAL, TYPE 1	TON	0		
30	DISK ANCHORING	ACRE	0		
31	EROSION CONTROL BLANKET, CATEGORY 2	SY	500		
32	FERTILIZER, TYPE 20-0-10	LBS	21		
33	4" DOUBLE YELLOW LINE - EPOXY	LIN FT	6,165		
34	4" SOLID LINE WHITE - EPOXY	LIN FT	12,340		
35	24" SOLID LINE WHITE STOP BARS - EPOXY	LIN FT	26		
36	CROSS WALK - EPOXY	SY FT	120		
Total 1-36					

Written Amount