

1 COURTYARD PLAN
M-2 SCALE: 1/4" = 1'-0"




NOTES

1. AIR COOLED CHILLERS CH-1,2 AND DRYCOOLER DC-1 ARE PRE-PURCHASED EQUIPMENT. M.C. SHALL PROVIDE LABOR AND CRANE AS NECESSARY TO ACCEPT AND INSTALL THIS EQUIPMENT AT THE SITE.
2. LOCATIONS AND SIZES OF CONCRETE EQUIPMENT PADS ARE SHOWN ON ARCHITECTURAL PLANS.
3. NEW GLYCOL SYSTEM SHALL BE FULLY INSULATED INCLUDING ALL FITTINGS, VESSELS AND COMPONENTS. GLYCOL SYSTEM OUTSIDE SHALL BE INSULATED AND FULLY JACKETED.
4. M.C. SHALL PROVIDE SHEET METAL ENCLOSURE AROUND GLYCOL PUMPS GLP-1,2. ENCLOSURE TO HAVE REMOVABLE TOP FOR SERVICE ACCESS.
5. NEW GLYCOL PIPES SHALL RISE UP THE EXTERIOR OF THE BUILDING AND PENETRATE INTO THE SUBFLOOR PLENUM. PROVIDE CORE DRILLING AND SLEEVE FOR PENETRATION INTO THE BUILDING.
6. CONTROLLER DDC-1 SHALL BE FIELD INSTALLED INSIDE DRYCOOLER CONTROLS SECTION.
7. M.C. SHALL PROVIDE WEATHERPROOF ENCLOSURE FOR CONTROL VALVE CV-1.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Registered Professional Engineer under the laws of the State of Minnesota.

Nathan O. Clyde
42063
Registration No.
10/26/12
Date

PARALLEL TECHNOLOGIES
7667 EQUITABLE DRIVE
EDEN PRAIRIE, MN 55344
952-920-7485
www.ptinet.com



REVISION NO.	DATE	REVISION NO.	DATE	REVISION NO.	DATE	REVISION NO.	DATE

ISSUE DATE: 10/19/2012

EXTERIOR EQUIP. LAYOUT
DATA CENTER PROJECT
NAU COUNTRY INSURANCE
7333 SUNWOOD DRIVE NW
RAMSEY, MN 55303

PROJECT # 436
DRAWN BY: JJ
CHECKED BY: NOC
SCALE: 1/8" = 1'-0"

DRAWING NUMBER:
M-2