

**WWGOETSCH**  
ASSOCIATES, INC.  
800-831-7914

5250 WEST 74<sup>TH</sup> STREET  
MINNEAPOLIS, MN 55439-2226  
952-831-4340/FAX: 952-831-2357

7674 COLLEGE ROAD SUITE 105  
BAXTER, MN 56425-7865  
218-829-6890/FAX: 218-829-6972

---

MARCH 18, 2020

CITY OF RAMSEY, MN  
ATTN: JOHN NELSON

SUBJECT: LIFT STATION #6 RENOVATION

WE RESPECTFULLY SUBMIT OUR QUOTATION FOR THE FOLLOWING EQUIPMENT AND SERVICES. WE PROPOSE TO REMOVE EXISTING 4" BASE DISCHARGE ELBOWS, RAIL SYSTEM AND PIPING, INSTALL NEW 4"BASE ELBOWS, NEW RAIL SYSTEM, STAINLESS STEEL GUIDE PIPE, AND 4" DISCHARGE PIPING UP TO THE 90 DEGREE ELBOW IN THE WETWELL, REMOVE EXISTING KSB 10 HP PUMPS AND INSTALL NEW HYDROMATIC 10 HP CHOPPER PUMPS DESIGNED TO HANDLE RAGS .

**PROPOSAL TO INCLUDE;**

- 2 - PENTAIR HYDROMATIC MODEL C4SXP SUBMERSIBLE CHOPPER PUMPS WITH 10 HP, 1750 RPM, 460/60/3 VOLT MOTORS, 75' POWER CORDS
- 2 - 4" DISCHARGE ELBOWS AND SEALING FLANGE ASSEMBLIES
- 2 - 4" DUCTILE IRON DISCHARGE PIPING, FITTINGS AS REQUIRED
- 4 - 2" STAINLESS STEEL GUIDE PIPE
- 2 - STAINLESS STEEL CABLE BRACKETS TO REROUTE PUMP POWER CORDS
- 1 - LOT OF GASKETS, STAINLESS STEEL HARDWARE, STAINLESS STEEL ANCHOR BOLTS
- 1 - LOT OF LABOR TO INSTALL ABOVE NOTED EQUIPMENT

TOTAL INSTALLED PRICE ..... \$39,612.00

ADD TO ABOVE FOR RENTAL OF 6" DIESEL DRIVEN, TRAILER MOUNTED SELF-PRIMING PUMP, SUCTION & DISCHARGE HOSE, FLANGED FITTING TO MOUNT IN VALVE VAULT FOR BY-PASSING THE INLET TO THE LIFT STATION...\$2843.

\*WE HAVE NOT INCLUDED ANY ITEMS OR MATERIALS NOT MENTIONED ABOVE.

WE HAVE NOT INCLUDED ANY APPLICABLE TAXES.

PRICES ARE FIRM FOR 60 DAYS.

TERMS ARE NET 30 DAYS AFTER SHIPMENT.

INSTALLATION OF NEW BASE ELBOWS, PIPING, GUIDE PIPE PIPING AND PUMPS CAN PROCED IN APPROXIAMTELY 8 -10 WEEKS AFTER RECEIPT OF YOUR ORDER.

THANK YOU FOR THE OPPORTUNITY TO OFFER OUR EQUIPMENT AND SERVICES FOR YOUR CONSIDERATION.

SINCERELY,

BRYAN GOEHRING