

IP 21-03 Business Park 95 Street Reconstructions

Street Segment Summary

Street Description				Street History				Pavement Coring Results				GPR Summary		
Street	Segment Description	Length (feet)	Curb	2020 PASER	Year Built	Maint. 1	Maint. 2	Core No.	HMA Depth (inches)	Agg. Depth (inches)	WSB Recommended Maintenance	Avg HMA (inches)	Avg Agg. Base (inches)	Avg Section (inches)
140th Avenue	Radium Street / Unity Street	981	concrete	4	1998	SC 2003	SC 2015	3	5	5.5	Full Depth Reclamation, Full Bituminous Removal and Replacement or Reconstruction	4.1	n/a	n/a*
McKinley Street	Unity Street / Sunfish Lake Boulevard	1,067	concrete	4	1995	SC 2003	SC 2015	5	6.5	6.5	2 Inch Mill and Overlay	6.0	n/a	n/a*
McKinley Street	Unity Street / End	1,320	concrete	4	1996	SC 2003	SC 2015	6	6	9.5	Full Depth Reclamation, Full Bituminous Removal and Replacement or Reconstruction	5.3	n/a	n/a*
								7	4.75	9	Full Depth Reclamation, Full Bituminous Removal and Replacement or Reconstruction			
Radium Street	McKinley Street / 140th Avenue	1,250	concrete	4	1998	SC 2003	SC 2015	8	4	5	Full Depth Reclamation, Full Bituminous Removal and Replacement or Reconstruction	4.0	n/a	n/a*
Unity Street	CR 116 / McKinley Street	1,696	concrete	4	1995	SC 2003	SC 2015	1	6	6	2 Inch Mill and Overlay	6.3	n/a	n/a*
								2	7	8	2.5 Inch Mill and Overlay			
								4	8	5.5	Full Depth Reclamation, Full Bituminous Removal and Replacement or Reconstruction			
Total Length		6,314	1.2 mi.											

* GPR was unable to determine agg. base thickness