

Wetland 114P Outlet Improvements

Notes	Item No.	MnDOT No.	Item	Unit	Estimated Quantity
	1	2021.501	Mobilization	LS	1
2	2	2105.507	Common Excavation (EV)	CY	20
	3	2506.502	Construct 60" Outlet Structure	EA	1
	4	2506.502	Adjust Sanitary Casting	EA	6
	5	2506.502	Furnish and Install Haala PS60-72 Grate	EA	1
	6	2573.503	Silt Fence	LF	40
3	7	2574.507	Topsoil (LV)	CY	20
	8	2575.504	Hydroseed disturbed areas	SY	314
	9		Replace Boardwalk	SF	2,450

PAY ITEM NOTES:

1. REMOVAL LIMITS SHALL BE MARKED IN THE FIELD BY CITY STAFF.
2. EV TO CV CONVERSION FACTOR = 1.25.
3. LV TO CV CONVERSION FACTOR = 1.30.


DATE	REVISION

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota

DRAFT
Engineer

Date X/XX/XX Lic. No. XXXXX

DESIGNED BY: LLL	DATE: 8/10/22
DRAWN BY: LLL	FILE No. 19-07
CHECKED BY: LLL	



CITY OF RAMSEY
7550 SUNWOOD DRIVE
RAMSEY, MN 55303
(763) 427-1410 FAX (763) 433-9898

STATEMENT OF ESTIMATED QUANTITIES

WETLAND 114P OUTLET MODIFICATIONS
CITY PROJECT NO. 19-07
CITY OF RAMSEY, MINNESOTA