



To: Arely Peek
Purchasing Agent

January 9, 2025

Re: Recommendation of Award
Urgent repair of 20" water main leak on W. Bland near Willow Dr.
RFP-25-001 – On-Call Utility Repair Services

The City of Roswell has a significant water leak of a 20" diameter water line on W. Bland in the vicinity of Willow Dr. The leak is located in the roadway and is considered deep trenching with a depth of 8' to the top of pipe. Work will require removal of existing 20" CCP, tee and other fittings. Replace with 40 foot of 20" diameter PVC C-905, 20" butterfly valve, mega-lug connections, trenching to meet OSHA, flow fill, backfill trench and other associated work.

Upon review, I hereby recommend award of the work to White Cloud Pipeline, who is already mobilized doing other current water line repairs. Award amount to be \$104,554.27 (includes GRT), issue PO as soon as possible, proceed through Infrastructure & Finance Committees and February 2025 City Council for ratification. Quote is attached.

Engineering has obtained a State Wage Decision to comply with New Mexico Department of Work Force Solutions.

If you have any questions, please contact me.

Sincerely,

A handwritten signature in black ink, appearing to read 'Louis Najar', is written over the printed name and title.

Louis Najar, P.E.
City Engineer



QUOTATION

PO Box 2184
Roswell, NM 88202
575-622-5995 Fax 575-622-3167

NM License # 34206 Exp. 4/30/27
PW # 002269020110621 Exp. 6/21/26
EIN # 85-0398058

To: City of Roswell
Attn: Louis Najar / Andrew Valadez
Re: Bland 20" RCP Water Main Emergency Repair

Date: 1/9/25

Acknowledged: 2025 Type A Wages

20" RCP Water Main at W Bland St & Willow Dr

Pothole and excavate 20" RCP to determine source of leak – 6" valve at cross leaking
Verify pipe depth, size, composition, and concrete thickness – 7.5' to top of 20" RCP pipe
Pothole to verify and locate existing utilities within repair zone
Remove concrete sidewalk and curb & gutter in conflict with necessary excavation
Remove, temporarily relocate, and restore appx 120' of property owner fence
Excavate repair zone to below existing 20" RCP waterline and tie in locations
Remove existing 20" cross and 6" valves
Install appx 40' of 20" C900 pipe
Install 20" flanged butterfly valve, megaflanges and valve box with riser
Remove concrete from existing RCP at tie back locations
Install .25" thick steel reinforcement bands to RCP steel liner at tie back locations
Install 20" HYMAX couplings to tie new C900 pipe to existing RCP
Hand chlorination of pipe, fittings, and tie ins
Flowfill to 1' over pipe and at valve and connection locations – ½ sack flowfill
Backfill excavation zone to original grade at 90% density
Haul off of spoil dirt and concrete
Concrete sidewalk and curb & gutter to be replaced by Abraham's under existing City contract
2 ea 20" High Range HYMAX couplings to be borrowed from City and replaced to City inventory

By City:

40' 20" C900 Pipe
6" Water pump and maintain pump as necessary
Traffic Control
Construction Water

Exclusions:

Bonds (avail @ 1.75%)
Excess or special insurance
Permits / Survey / SWPPP
Density Testing / Pressure Testing / Bact Testing

*L. Najar
City Eng
1-9-2025*

Bland 20" RCP Water Main Emergency Repair

Lump Sum

\$ 96,903.00 + NMGR

GRT

7.8958%

7651.29

Proudly Serving NM Since 1992

104,554.27