



Armorock, LLC
PO Box 60006
Boulder City, NV 89006
702-824-9702
www.armorock.com

Quote Date: 5/8/2017

To:

Ref: San Luis Quote 5.4.17
San Luis, AZ

Q U O T A T I O N

Notes:

1. Quote is subject to our standard terms, conditions, and shipping polices.
2. Quote is good for 60 days from the issue date.

From:



Armorock, LLC
PO Box 60006
Boulder City, NV 89006
702-824-9702
www.armorock.com

For:
Ref: San Luis Quote 5.4.17
San Luis, AZ

Quote Date: 5/8/2017

Structure	Description	Height	Weight	Price
MH 1	60"-30" Polymer Manhole	12.28'	8,871	\$6,998
1	A-1700 30" FRAME AND COVER	1	PR30X4FL	30 IN X 4 IN FLAT PRO-RING
1	50530-C	1	50572-S	60 IN X 6 FT POLYMER MH SECTION
1	70536-B75	2		S106-12WS NPC BOOT
4	JM1.25			1.25 IN X 14 FT JOINT MASTIC ROLL
MH 2	60"-30" Polymer Manhole	14.75'	12,994	\$8,173
1	A-1700 30" FRAME AND COVER	1	PR30X4FL	30 IN X 4 IN FLAT PRO-RING
1	PR30X6FL	1	50530-C	60 IN X 3 FT ECC POLYMER CONE 30 IN
1	50572-S	1	70560-B75	60 IN X 5 FT POLYMER PRECAST BASE (3/4 DEPTH TROUGHING)
1	22M PSX-2	1		28A PSX-2:DD
1	18M PSX-2:DD	1		S106-12WS NPC BOOT
4	JM1.25			1.25 IN X 14 FT JOINT MASTIC ROLL
MH 3	60"-30" Polymer Manhole	13.00'	9,844	\$7,499
1	A-1700 30" FRAME AND COVER	1	PR30X6FL	30 IN X 6 IN FLAT PRO-RING
1	50530-C	1	70572-S1C	60 IN X 6 FT POLYMER MH SECTION
1	18M PSX-2:DD	1	70542-B75	60 IN X 3 FT 6 IN POLYMER PRECAST BASE (3/4 DEPTH TROUGHING)
2	18M PSX-2:DD	4	JM1.25	1.25 IN X 14 FT JOINT MASTIC ROLL
MH 4	60"-30" Polymer Manhole	6.65'	6,859	\$5,209
1	A-1700 30" FRAME AND COVER	1	PR30X2FL	30 IN X 2 IN FLAT PRO-RING
1	PR30X6FL	1	50530-C	60 IN X 3 FT ECC POLYMER CONE 30 IN
1	70536-B75	2		18M PSX-2:DD
2	JM1.25			1.25 IN X 14 FT JOINT MASTIC ROLL
MH 5	60"-30" Polymer Manhole	19.59'	12,670	\$9,748
1	A-1700 30" FRAME AND COVER	1	PR30X2FL	30 IN X 2 IN FLAT PRO-RING
1	50530-C	1	50524-S	60 IN X 2 FT POLYMER MH SECTION
2	50572-S	1	70530-B75	60 IN X 2 FT 6 IN POLYMER PRECAST BASE (3/4 DEPTH TROUGHING)
2	14M PSX:DD	8	JM1.25	1.25 IN X 14 FT JOINT MASTIC ROLL
MH 6	48"-36" Polymer Manhole	6.87'	5,259	\$4,766
1	A-1700 30" FRAME AND COVER	1	PR30X1FL	30 IN X 1 IN FLAT PRO-RING
1	PR30X4FL	1	70330-TL	36 IN POLYMER TRANSITION LID 30 IN
1	50436-C	1	70436-B75	48 IN X 3 FT POLYMER PRECAST BASE (3/4 DEPTH TROUGHING)
2	18M PSX-2:DD	1	JM1.25	1.25 IN X 14 FT JOINT MASTIC ROLL
Sub-Total				\$42,392
Tax (10.71%)				\$4,540
Freight/Delivery				\$2,400
Total Price for San Luis Quote 5.4.17				\$49,333