



City of San Luis

www.sanluisaz.gov

Oscar Barnett
 Project Manager
 City of San Luis
OBarnett@sanluisaz.gov
 928-341-8577

August 26, 2025

Re: Quote Request/Change Order for additional work - City of San Luis Co 22nd St and 4th Ave Intersection Improvements Project.

Note: City of San Luis Adopted Construction Standards. See Exhibit A and B for reference.

Item	Description	Unit	Quantity	Unit Price	AMOUNT
1	Remove and replace vertical curb and gutter	LF	90	By COSL	\$ By COSL
2	Remove and replace sidewalk (5' wide)	SF	1,225		\$
3	Remove and replace Sidewalk ADA Ramps (modified to roll curb)	SF	675		\$
4	Remove and replace Aprons	SF	620		\$
5	Remove and replace cross gutter	SF	171		\$
6	Saw cut and remove existing pavement	SY	5,823	By COSL	\$ By COSL
7	New 4" AC pavement/Regrade existing ABC	SY	5,343	29.00	\$154,947.00
8	Install 4" AC pavement	SY	427	33.00	\$14,091.00
9	Over-excavate, prepare subgrade, and 18" ABC subbase	SY	427	68.00	\$ 29,036.00
10	New 3" AC pavement/Regrade existing ABC	SY	53	By COSL	\$ By COSL
11	Additional Traffic Control	LS	1		\$
12	Additional Material Testing	LS	1		\$
13	Additional SWPPP	LS	1		\$
14	Additional Construction Staking	LS	1	By COSL	\$ By COSL
				Subtotal	\$198,074.00
	5% Contingency	LS	1	By COSL	\$ By COSL
				Total	\$
				Quote	198,074.00

DPE Construction, Inc. Esteban Hernandez VP / Operations Manager 08/28/2025
CONTRACTOR **SIGNATURE AND TITLE** **DATE**

Digitally signed by Esteban Hernandez
 DN: cn=Esteban Hernandez, o=DPE Construction, Inc.,
 email=Esteban.Hernandez@peyuma.com, c=US, ou=San Luis, AZ
 Reason: I am approving this document
 Content-type: text/plain
 Date: 2025.08.28 09:13:51-0700

EXHIBIT A

Co 22nd and 4th Ave

Quote Request



Quote Request

Concrete Notes

1. Curb and Gutter City of San Luis Standard (Red): (A) 50', (A.2) 40'
2. Sidewalk 5' City of San Luis Standard (Blue): (B) 191', (B.2) 30', (B.3) 10', (B.4) 14',
3. Sidewalk ADA/Ramps City of San Luis Standard modified to roll curb: (C) 35', (C.2) 35', (C.3) 44', (C.4) 21'
4. Cross Gutter Aprons City of San Luis Standard (Yellow): (D.2) 36', (D) 44', (D.3) 49'
5. Cross Gutter City of San Luis Standard (Light Blue) (O) 28'6" x 6'

EXHIBIT B

Co 22nd and 4th Ave

Quote Request



Quote Request

Asphalt Notes

- (A,B, C) Remove existing pavement 5,823 Square Yards
- (A) New 4" AC pavement/regrade existing ABC: 5,343 Square Yards
- (B) Install 4" AC pavement: 427 Square Yards
- (B) Subbase 18" ABC: 427 Square Yards
- (C) Asphalt 3" AC Pavement/Regrade ABC: 53 Square Yards