

Sylvia Diaz
Webb County
1110 Washington Street, Ste. 101 Laredo, Texas 78040

11/1/24
Quote GSS2024280
Golf Range Netting System

Scope of Work

- **Grand Slam Safety Golf Range Netting System**
 - Quantity of one in-line system 1550 Linear Feet of 30' Tall Netting – Steel Support Poles
 - Dimensions/Layout: Per provided sketch
 - Proposed netting system shall be supported with new 10" diameter steel poles, sized to meet the required loading demands per applicable local codes
 - 32 ea. – 10" diameter steel support poles.
 - All poles shall be spaced 50' on center and shall be directly embedded into ground 10' within an augured hole. All poles shall be backfilled 3000 psi concrete
 - New horizontal and vertical cables shall be installed upon support poles to frame and support new netting panels
 - #930 Polyester knotless golf netting, including all perimeter and interior solid cored rope borders.
 - All netting panels shall be customized fabricated to fit between each pole span
 - Galvanized strand steel cable (5/16")
 - Galvanized pre-formed cable grips.
 - Galvanized bolts, washers, nuts and double spring lock washers.
 - Double helical anchors with twin eyes, including required extensions.
 - 9/32" galvanized carabiner attachment snaps.
 - All other supporting hardware shall be hot dipped galvanized and shall conform to one or more of the following: ANSI, IEEE, NEMA, ASTM
 - Netting is permanent in nature (not hoistable)
 - Two year installation warranty

Total Cost: \$260,000

*Site visit would be required to determine equipment access, drilling conditions, and any other unknown circumstances before providing final pricing.

Above plans are unstamped and if a stamp is required, can be provided for an additional cost of \$3,500

Grand Slam Safety OMNIA® Partners (OMNIA):

Athletic Court and Field Containment Solutions
Grand Slam Safety, LLC.
Contract #08-39

Please see page two for project notes.

Project Notes:

- **Cost Includes:** Product as listed above, plans and drawings for approval prior to fabrication, estimated freight, mobilization to site, equipment rentals, and installation (standing poles & hanging netting) of the system.
- **Cost does not include:** Permit/bond/license/union fees, prevailing wage, ground protection, receiving or unloading potential shipments, ground protection, any landscaping or any ground related work from heavy equipment use, removal of spoils from site, or anything not clearly listed above.
- **GSS** shall not be responsible for determining height of netting.
 - Customer is solely responsible for choosing heights of netting. GSS does not guarantee that proposed netting will stop all errant golf balls.
- **Cost Assumes:** One trip install for full scope of work, safe & suitable working conditions, no time lost working around other trades, sufficient clear & free access for equipment, final field check provided to confirm net dimensions and accurate layout, and pre installation checklist sign off prior to mobilization.
 - Cost also assumes that the subsoil conditions are suitable. Any and all additional expenses as a result of rock drilling, boring, blasting, steel casings, de-watering, soil stabilization or anything of the ilk will result in additional charges.
- **Other requirements:** Owner is responsible for identifying and clearly marking all private utilities prior to excavation. Grand Slam Safety is not responsible for any underground private utilities.
- **Lead time:** TBD based upon the final scope of work chosen.
- **Payment terms:** TBD based upon the final scope of work chosen.
- Budget range is good for 30 days.
- This document serves as an initial overview only and is not a formal quote.

Thank you for the opportunity!

Dan Myers

Sports Facility Consultant & Sales Representative , Grand Slam Safety, LLC.

dan@grandslamsafety.com (315) 955-9936