



Customer

Quantcorp Construction, LLC
6548 Springfield Ave, Suite 101
Laredo, TX
78041, US
(956) 568-2846

Prepared By:
Christian Fragoso
(956) 568-2846
christianz@quantumbuilding.net

Webb County Engineering
1620 Santa Ursula Ave Ste 2-
Laredo, TX
78040, US

Mario Santos
(956) 523-4186
msantos@webbcountytx.gov

Project: **Webb County Fire Station**

Scope of Work

ADDITIONS AS PER ASI - REV 2

ASI #01

	Quantity	Unit Cost	Total Cost
Lighting Fixtures	1 ea	\$0.00	\$0.00
Description: Lighting Fixtures changed in Wash Room, from 2'x4' to strip lights. Addition of lighting under cabinet			
	--	\$0.00	\$0.00

ASI #02

	Quantity	Unit Cost	Total Cost
AT&T Pedestal Relocation	1 ea	\$1,466.29	\$1,466.29
Description: Relocation			
	--	\$1,466.29	\$1,466.29

ASI #03

	Quantity	Unit Cost	Total Cost
Lighting Fixtures at Bay Area	1 ea	\$0.00	\$0.00
Description: Modification of Lighting Fixtures (installed at no cost)			
	--	\$0.00	\$0.00



Change Order: 2024046 - 1 / Date: 4/4/2025
Project Number: QC2024-16

ASI #04

	Quantity	Unit Cost	Total Cost
Concrete Flume Description: 3000 PSI, #4 Rebar, (5) Energy Dissipator, 4' Erosion Control Blanket	1 ea	\$5,228.28	\$5,228.28
Labor for Concrete Flume Description: Labor for pouring concrete, rebar, etc.	1 ea	\$4,227.12	\$4,227.12
Concrete Toe-Down Description: (8"x18") Concrete toe-down, 3000 PSI, Rebar, Labor	188 ft	\$11.96	\$2,248.16
Labor for Concrete Toe-Down Description: Labor for pouring concrete and rebar.	188 ft	\$43.38	\$8,156.12
	--	\$19,859.68	\$19,859.68

ASI # 07 & ASI#08

	Quantity	Unit Cost	Total Cost
Fire Line Extension and Connections - Material Description: Added/revise 2", 4" & 6" water lines. Location added for the 4" tanker truck intake connections and like towards the fire tank connection. Bollard and splash block added. Connection to Fire Tank	1 ea	\$18,085.77	\$18,085.77
Labor to Install Description: Fire Line Extension and Connections	1 ea	\$16,398.63	\$16,398.63
	--	\$34,484.40	\$34,484.40

ASI # 11

	Quantity	Unit Cost	Total Cost
4' Height Chain Link Fence including gate Description: 4' high chain link fence as per ASI#11	343 ft	\$38.48	\$13,199.95
Installation of Chain Link Fence Description: Labor	343 ft	\$11.55	\$3,959.99
	--	\$17,159.94	\$17,159.94

Notes



Change Order: 2024046 - 1 / Date: 4/4/2025
Project Number: QC2024-16

Summary

Subtotal	\$72,970.30
----------	-------------

\$72,970.30

Accepted By

Date

.....

.....



CHANGE OF ORDER

WEBB COUNTY SOUTHERN FIRE STATION - 2045 MANGANA-HEIN RD.

Waterworks Services of Laredo, LLC
1214 Willow St
Laredo, Texas 78040
United States

Bill to

Webb County Southern Fire Station
Quantum Building Services - Juan Vazquez
6548 Springfield Ave.
Laredo, Texas 78041
United States

(956) 949-0854
juanjose@quantumbuilding.net

Estimate Number: PW190-2
Customer Ref: PO#238521
Estimate Date: February 26, 2025
Valid Until: March 28, 2025

Grand Total (USD): **\$34,484.40**

Items	Quantity	Price	Amount
Webb County Southern Fire Station 2045 Mangana-Hein Rd. Laredo, TX 78046	1	\$18,085.77	\$18,085.77
FIRE LINE EXTENSION			
Waterworks Services of Laredo, LLC., will furnish all material, equipment and labor necessary to preform and complete the project.			
FIRE LINE EXTENSION			
- (1) Tee 6x6			
- (2) 6" 90 Elbow DI			
- (4) 6" Gate Valve			
- (16) 6" Mega-Lug PVC			
- (150') 6" PVC C900			
- (1) 6" Sleeve			
- (1) Cap			
- (39') 4" PVC C900			
- (1) 4" 90 Elbow DI			
INSTALLATION	1	\$16,398.63	\$16,398.63

Grand Total (USD) **\$34,484.40**

Notes / Terms

This change of order PW190-2 will be applied to our contract PO#238521.
Based in ASI #8 provided by client

* Includes *

- Permits and Inspections
- Excavation, installation, backfill and compaction.

*Not Included *

- No concrete or asphalt demolition hauling or patching.
- No compaction Testing.
- No Intake Connection (Storz or standpipe), need details and model to proceed.
- No connection to Fire Tank just underground piping installation an preparation.
- No Bollards

Any additional work not mentioned will be done with an approved Change Order. This must be executed by both parties to commencing work. (Soil types 1 and 2 considered to work in this budget, otherwise a change of order will be required to proceed).

WW, LLC

Powered by  wave