

1848 Generator Relocation and Installation Bid Tabulation				CID Group Inc. 1519 E. Price Ste. B Laredo, TX	Alcan Contracting 1019 Mier St. Laredo, TX	Chris's Electric 1122 Topaz Trl Laredo, TX	American Generator Services 14317 Northwest Blvd., Ste. D Corpus Christi, TX 78410
Item	Description	Qty	Unit	Price	Price	Price	Price
1	Project Management & Demolition						
1.1	Project Mobilization, Permitting, and Administration	1	Lot	\$ 3,500.00	\$ 2,000.00	\$ 6,000.00	\$ 6,000.00
1.2	Site Preparation and Grading (Pad Prep)	102	sq ft	\$ 759.00	\$ 1,000.00	\$ 5,600.00	\$ 1,500.00
1.3	Trenching (50 ft, 4-6" W, 30" D)	50	ft	\$ 1,500.00	\$ 2,200.00	\$ 500.00	\$ 4,000.00
1.4	Existing Service Demolition (277/480V, 200A)	1	Lot	\$ 1,200.00	\$ 1,500.00	\$ 1,500.00	\$ 2,000.00
2	Concrete Foundation						
2.1	Foundation Formwork (17' x 6' x 8" slab)	1	Lot	\$ 750.00	\$ 750.00	\$ 1,200.00	\$ 800.00
2.2	Rebar Reinforcement (#5 at 12" o.c.)	1	Lot	\$ 250.00	\$ 500.00	\$ 3,500.00	\$ 4,000.00
2.3	Concrete Pour (102 sq ft @ 8" thick, 3000 PSI)	2.5	cu yds	\$ 700.00	\$ 850.00	\$ 1,200.00	\$ 3,000.00
2.4	Grounding System (5/8" x 8' rod, clamp)	1	Lot	\$ 90.00	\$ 500.00	\$ 850.00	\$ 675.00
3	Generator Relocation & Installation						
3.1	Loading & Transport (350kW Gen, 11 miles)	1	Lot	\$ 5,500.00	\$ 5,500.00	\$ 5,000.00	\$ 1,150.00
3.2	Installation of Existing 350 kW Generator	1	Ea	\$ 4,800.00	\$ 4,800.00	\$ 2,500.00	\$ 1,150.00
4	Electrical System						
4.1	New Electrical Service Installation (ATS as main)	1	Lot	\$ 1,800.00	\$ 1,800.00	\$ 6,800.00	\$ 14,700.00
4.2	4" PVC Schedule 40 Conduit	50	ft	\$ 600.00	\$ 750.00	\$ 157.19	\$ 3,200.00
4.3	500 MCM THHN/THWN Copper Stranded Wire	300	ft	\$ 6,800.00	\$ 6,800.00	\$ 5,827.88	\$ 13,500.00
4.4	3 AWG Green XHHW Copper Wire	75	ft	\$ 180.00	\$ 300.00	\$ 182.10	\$ 1,000.00
4.5	400A Automatic Transfer Switch (ATS)	1	Ea	\$ 6,890.00	\$ 6,890.00	\$ 10,497.50	\$ 8,871.00
4.6	200A 3-Phase 600V NEMA 3R Safety Switch	2	Ea	\$ 550.00	\$ 550.00	\$ 1,995.00	\$ 1,850.00
4.7	200A 1-Gang 3-Phase Meter Socket	2	Ea	\$ 380.00	\$ 580.00	\$ 868.23	\$ 1,850.00
5	Final Restoration & Commissioning						
5.1	Backfill & Soil Restoration (102 sq ft)	1	Lot	\$ 800.00	\$ 2,000.00	\$ 5,000.00	\$ 2,000.00
5.2	Testing and Commissioning	1	Lot	\$ 2,000.00	\$ 1,500.00	\$ 4,000.00	\$ 4,000.00
Total				\$ 39,049.00	\$ 40,770.00	\$ 63,177.90	\$ 75,246.00

1848 Generator Relocation and Installation Bid Tabulation				Ready Power LLC 4900 Callipe St. New Orleans, LA 70125	LED Electric & Lighting 815 E. Calton Rd., Ste. 4 Laredo, TX 78041	Midas Contractors 2710 Zacatecas St. Laredo, TX	360 General Contractor 1312 Houston St., Ste. 10 Laredo, TX 78040
Item	Description	Qty	Unit	Price	Price	Price	Price
1	Project Management & Demolition						
1.1	Project Mobilization, Permitting, and Administration	1	Lot	\$ 2,861.00	\$ 5,600.00	\$ 6,000.00	\$ 28,239.00
1.2	Site Preparation and Grading (Pad Prep)	102	sq ft	\$ 973.00	\$ 1,351.50	\$ 1,600.00	\$ 600.00
1.3	Trenching (50 ft, 4-6" W, 30" D)	50	ft	\$ 1,669.00	\$ 2,300.00	\$ 1,200.00	\$ 1,800.00
1.4	Existing Service Demolition (277/480V, 200A)	1	Lot	\$ 2,098.00	\$ 3,400.00	\$ 5,000.00	\$ 1,600.00
2	Concrete Foundation						
2.1	Foundation Formwork (17' x 6' x 8" slab)	1	Lot	\$ 1,526.00	\$ 1,500.00	\$ 600.00	\$ 4,800.00
2.2	Rebar Reinforcement (#5 at 12" o.c.)	1	Lot	\$ 858.00	\$ 1,300.00	\$ 800.00	\$ 600.00
2.3	Concrete Pour (102 sq ft @ 8" thick, 3000 PSI)	2.5	cu yds	\$ 2,145.00	\$ 2,500.00	\$ 1,800.00	\$ 1,600.00
2.4	Grounding System (5/8" x 8' rod, clamp)	1	Lot	\$ 334.00	\$ 250.00	\$ 500.00	\$ 150.00
3	Generator Relocation & Installation						
3.1	Loading & Transport (350kW Gen, 11 miles)	1	Lot	\$ 4,768.00	\$ 5,800.00	\$ 2,500.00	\$ 4,800.00
3.2	Installation of Existing 350 kW Generator	1	Ea	\$ 4,577.00	\$ 3,200.00	\$ 4,500.00	\$ 15,000.00
4	Electrical System						
4.1	New Electrical Service Installation (ATS as main)	1	Lot	\$ 24,891.00	\$ 10,000.00	\$ 39,000.00	\$ 12,000.00
4.2	4" PVC Schedule 40 Conduit	50	ft	\$ 763.00	\$ 1,750.00	\$ 300.00	\$ 2,000.00
4.3	500 MCM THHN/THWN Copper Stranded Wire	300	ft	\$ 10,107.00	\$ 10,200.00	\$ 6,500.00	\$ 8,000.00
4.4	3 AWG Green XHHW Copper Wire	75	ft	\$ 477.00	\$ 849.75	\$ 300.00	\$ 600.00
4.5	400A Automatic Transfer Switch (ATS)	1	Ea	\$ 14,303.00	\$ 13,200.00	\$ 3,000.00	\$ 23,308.00
4.6	200A 3-Phase 600V NEMA 3R Safety Switch	2	Ea	\$ 1,335.00	\$ 6,500.00	\$ 2,500.00	\$ 1,200.00
4.7	200A 1-Gang 3-Phase Meter Socket	2	Ea	\$ 954.00	\$ 5,800.00	\$ 1,800.00	\$ 800.00
5	Final Restoration & Commissioning						
5.1	Backfill & Soil Restoration (102 sq ft)	1	Lot	\$ 763.00	\$ 1,050.00	\$ 800.00	\$ 1,400.00
5.2	Testing and Commissioning	1	Lot	\$ 2,288.00	\$ 1,900.00	\$ 3,500.00	\$ 2,800.00
Total				\$ 77,690.00	\$ 78,451.25	\$ 82,200.00	\$ 111,297.00