

BIANCO ANNEXATION

Infrastructure and Services Plan

Northeast Corner of Bianco Road and Equinox Road

Submittal: May 24, 2024

Table of Contents

Section I Introduction 1

Section II Annexation Area 1

Section III Existing and Planned Public Utility Infrastructure..... 2

Section III Current and Planned City Services..... 2

Section IV Conclusion 3

Appendix

- Vicinity Map
- Annexation Legal Description and Exhibit

Section I Introduction

This document is being prepared for the City of Casa Grande per the Arizona Revised Statutes 9-471 (O):

On or before the date the governing body adopts the ordinance annexing territory, the governing body shall have approved a plan, policy or procedure to provide the annexed territory with appropriate levels of infrastructure and services to serve anticipated new development within ten years after the date when the annexation becomes final pursuant to subsection D of this section.

This plan is intended to provide a detailed summary of the existing and planned public infrastructure and city services for the Annexation Area.

Section II Annexation Area

The Bianco Annexation is approximately 81 acres, comprised of 3 parcels generally located at the northeast corner of Bianco Road and Equinox Road in unincorporated Pinal County, Arizona. See below aerial vicinity map and attached Legal Description and Map. The Property is undeveloped land used for agricultural purposes and is zoned GR General Rural within Pinal County. The Property is located within the City of Casa Grande Planning Boundary.



Section III Existing and Planned Public Utility Infrastructure

A. Roadway(s)

Bianco Road

- Existing 2 Paved lanes of traffic
- Proposed Principal Arterial
 - Full road section = 140' of ROW

Illinois Road

- Existing Unimproved dirt road
- Proposed Collector
 - Full road section = 60' of ROW

There is adequate access to the annexation site from abutting Bianco Road. Improvements to these proposed roadways will be determined as development occurs.

B. Utilities

- Water Arizona Water Company
 - Existing 12" water line along Kortsen Road north of the annexation area.
- Wastewater The City of Casa Grande
 - Existing 36" gravity main along Burris Road east of the annexation area.
- Power APS
- Gas Southwest Gas Corporation
- Telephone Cox Communications

Water and wastewater, power, gas, and communications are currently accessible or nearby and available to support any proposed development of the Annexation Area.

Section III Current and Planned City Services

The City of Casa Grande will provide a variety of services to the proposed annexation area following adoption. The following outline describes those services in more detail.

A. Police

The City of Casa Grande police department will service and patrol the area immediately following the effective date of the annexation.

B. Fire and Emergency

Fire Station 501 is located approximately 2.8 miles southeast from the proposed annexation site. The City of Casa Grande fire department will review all plans for new development on the annexed property to ensure proper fire protection is provided. The review will include access, fire hydrants, water lines and flow, and conformity to the Uniform Fire Code.

C. Library

The annexation is not expected to impact the library services.

D. General Government

The City of Casa Grande provides a variety of services that will be available to the property following annexation. Future projects and/or site development will be permitted and processed through the City.

E. Sanitation

The City of Casa Grande Sanitation Division is prepared to collect refuse from the proposed site following the annexation at the request of the property owners.

F. Sewer

The City of Casa Grande will provide necessary sewer services in accordance with any proposed use to the proposed site.

G. Parks and Recreation

The annexation is not expected to impact park services.


H. Street Maintenance

Roadway(s) will be constructed and maintained as required by the City in accordance with any proposed use or development.

Section IV Conclusion

At the time of annexation, the City of Casa Grande can effectively furnish appropriate levels of infrastructure and services to provide for the annexation area.

APPENDIX



BIANCO ANNEXATION

PINAL COUNTY, AZ

VICINITY MAP

HILGARTWILSON

ENGINEER | PLAN | SURVEY | MANAGE
HAS JOINED COLLIER'S ENGINEERING & DESIGN

MAY 10, 2024
8.5X11



0 3,000' 6,000'
Scale: 1" = 6,000'

2062
CP

BIANCO ANNEXATION PROPERTY
BIANCO ROAD & EQUINOX DRIVE
LEGAL DESCRIPTION

A portion of land being situated with Sections 15 and 16. Township 6 South, Range 5 East of the Gila and Salt River Meridian, Pinal County, Arizona, being more particularly described as follows:

BEGINNING at a rebar accepted as the West Quarter Corner of said Section 15 from which an Aluminum cap stamped LS 21065 dated 2005 accepted as the Northwest Corner of said Section 15, bears North $00^{\circ}52'55''$ West a distance of 2669.82 feet as the Basis of Bearing.

THENCE South $89^{\circ}42'04''$ East, 2655.02 feet on the north line of the Northwest Quarter of said Section 15;

THENCE leaving said north line of the Northwest Quarter, South $00^{\circ}38'11''$ East, 1328.68 feet on the North-South Mid-Section line of said Section 15;

THENCE North $89^{\circ}47'13''$ West, 2724.18 feet on the north line of the south half of the Northwest Quarter of said Section 15;

THENCE North $00^{\circ}53'07''$ West, 23.44 feet to a non-tangent curve, concave northwesterly, having a radius of 25.00 feet, the center of which bears North $00^{\circ}53'07''$ West;

THENCE northeasterly on said curve, through a central angle of $90^{\circ}00'00''$, an arc length of 39.27 feet to a non-tangent line;

THENCE North $00^{\circ}53'07''$ West, 375.00 feet to the beginning of a tangent curve, concave southwesterly, having a radius of 50.00 feet;

THENCE northwesterly on said curve, through a central angle of $90^{\circ}00'01''$, an arc length of 78.54 feet to the beginning of a reverse curve, concave easterly, having a radius of 50.00 feet;

THENCE northwesterly and northeasterly on said curve, through a central angle of $180^{\circ}00'02''$, an arc length of 157.08 feet to the beginning of a reverse curve, concave northwesterly, having a radius of 50.00 feet;

THENCE northeasterly on said curve, through a central angle of $90^{\circ}00'01''$, an arc length of 78.54 feet to a tangent line;

THENCE North $00^{\circ}53'07''$ West, 320.00 feet to the beginning of a tangent curve, concave southwesterly, having a radius of 50.00 feet;

THENCE northwesterly on said curve, through a central angle of 90°00'01", an arc length of 78.54 feet to the beginning of a reverse curve, concave easterly, having a radius of 50.00 feet;

THENCE northwesterly and northeasterly on said curve, through a central angle of 180°00'02", an arc length of 157.08 feet to the beginning of a reverse curve, concave northwesterly, having a radius of 50.00 feet;

THENCE northeasterly on said curve, through a central angle of 90°00'01", an arc length of 78.54 feet to a tangent line;

THENCE North 00°53'07" West, 124.43 feet to the beginning of a tangent curve, concave southwesterly, having a radius of 25.00 feet;

THENCE northwesterly on said curve, through a central angle of 88°46'31", an arc length of 38.74 feet to a non-tangent line;


THENCE North 00°20'22" East, 40.00 feet;

THENCE leaving said westerly Right of Way line, South 89°41'18" East, 73.63 feet to the West Quarter corner of said Section 15 to the **POINT OF BEGINNING**.

The above described parcel contains a computed area of 3,617,076 sq. ft. (83.0366 acres) more or less and being subject to any easements, restrictions, rights-of-way of record or otherwise.

The description shown hereon is not to be used to violate any subdivision regulation of the state, county and/or municipality or any land division restrictions.



Prepared by: HILGARTWILSON, LLC
2141 E. Highland Avenue, Suite 250
Phoenix, AZ 85016
Project No. : 2062
Date: May 2024



May 10, 2024

PAGE 2 OF 4

U:\2000\2062\SURVEY\DOCS\2062 - BIANCO ANNEXATION PROPERTY LEGAL.docx




RADIALS:
R1 – N00°53'07\"W

PAGE 3 OF 4

PROJ.NO.: 2062	BIANCO ANNEXATION PROPERTY BIANCO ROAD & EQUINOX DRIVE PINAL COUNTY, ARIZONA EXHIBIT	 HILGARTWILSON 2141 E. HIGHLAND AVE., STE. 250 PHOENIX, AZ 85016 P: 602.490.0535 / F: 602.368.2436
DATE: MAY 2024		
SCALE: NTS		
DRAWN BY: BMG		
CHECKED BY: DMS		

LINE TABLE		
LINE NO.	DIRECTION	LENGTH
L1	S89°42'04"E	2655.02'
L2	S00°38'11"E	1328.68'
L3	N89°47'13"W	2724.18'
L4	N00°53'07"W	23.44'
L5	N00°53'07"W	375.00'
L6	N00°53'07"W	320.00'
L7	N00°53'07"W	124.43'
L8	N00°20'22"E	40.00'
L9	S89°41'18"E	73.63'

CURVE TABLE			
CURVE NO.	RADIUS	DELTA	LENGTH
C1	25.00'	90°00'00"	39.27'
C2	50.00'	90°00'01"	78.54'
C3	50.00'	180°00'02"	157.08'
C4	50.00'	90°00'01"	78.54'
C5	50.00'	90°00'01"	78.54'
C6	50.00'	180°00'02"	157.08'
C7	50.00'	90°00'01"	78.54'
C8	25.00'	88°46'31"	38.74'



PAGE 4 OF 4

PROJ.NO.: 2062	BIANCO ANNEXATION PROPERTY BIANCO ROAD & EQUINOX DRIVE PINAL COUNTY, ARIZONA EXHIBIT	 HILGARTWILSON 2141 E. HIGHLAND AVE., STE. 250 PHOENIX, AZ 85016 P: 602.490.0535 / F: 602.368.2436
DATE: MAY 2024		
SCALE: NTS		
DRAWN BY: BMG		
CHECKED BY: DMS		