

14IFB00219 - Lakeline Blvd Extension Phase 2

Project Summary

Project Description:

Construction of two lanes of a four lane divided arterial roadway from Old Quarry Rd to Old RM 2243. Major work items include Earthwork, Flexible Base, Asphalt Pavement, Drainage Structures, Temporary and Permanent Erosion Control, and Signing & Pavement Markings. Project has no bridges or bridge class structures.

Length: 2.622 miles

Duration: 9 months

Limits: From Old Quarry Rd to Old RM 2243

Funding: Williamson County Road Bond Program

Estimated Cost: \$3.4 M

Major Items of Work: (quantities are rounded)

Excavation – 25,000 CY

Embankment – 5,000 CY

Flexible Base – 8,000 CY

Topsoil/Seeding – 40,000 SY

Type C HMA – 7,000 TON

Asphalt Driveways – 1,000 SY

Wire Fence – 3,500 LF

Reinforced Concrete Pipe (18" to 24") – 800 LF

Concrete Box Culverts (4'x2' and 4'x3') – 400 LF

Soil Retention Blankets – 19,000 SY

Silt Fence – 7,000 LF

Bioswale – 6,500 LF

Concrete Curb & Gutter – 14,000 LF

Small Signs – 16 EA

Ty I & II Striping (4") – 28,000 LF