Proposal

DATE: JUNE 22, 2015



Westar Construction, Inc.

4500 Williams Dr. Ste 212 PMB 411, Georgetown, TX 78633 Phone 512.630.5930 Fax 512.233.0691 lamont@westarconstruction.com

TO Williamson County, TX- Facilities Christi Stromberg 512-943-3377 PROJECT: WILCO- Radio Tower Access Road

Maintenance- Taylor Location (Old

Coupland Rd.)

DESCRIPTION

Item	Description	Qty	Unit	Unit \$	Total
	Concrete Entrance (6" thick w/ #4 rebar reinforcement, with slight toe-down on west edge				
1	at drop off)	1	LS	\$2,900.00	\$2,900.00
2	Concrete SET on upstream side of Entrance at CMP	1	EA	\$1,800.00	\$1,800.00
3	Concrete Driveway (5" thick with toe-down on west edge)	480	SF	\$6.25	\$3,000.00
	175 LF of Base Road Repair(Remove fabric under base road, import 1 load of road base, and				
5	reshape as needed)	291	SY	\$9.00	\$2,619.00
6	Add Gravel to Radio Tower Enclosure	1	LS	\$1,100.00	\$1,100.00
	Clean out drainage ditch below neighboring				
7	entrance	1	LS	\$750.00	\$750.00

Total Proposal \$12,169.00

^{*}Not including bonds or permits if needed.

^{*}Standard insurance will be provided.