

INDEX SHEET

BEING A 71.851 ACRE TRACT OF LAND, BEING A PORTION OF THE JOHN MCDEVITT SURVEY, ABSTRACT NO. 415, THE HENRY RHOADS SURVEY, ABSTRACT NO. 535, THE JAMES LEONARD SURVEY, ABSTRACT NO. 383, THE WILLIAM B BILLINGSLEY SURVEY, ABSTRACT NO. 95, AND THE JAMES HACKETT SURVEY, ABSTRACT NO. 312, WILLIAMSON COUNTY, TEXAS, SAID 71.851 ACRE TRACT BEING A PORTION OF THAT CERTAIN 72.888 ACRE TRACT RECORDED IN DOCUMENT NO. 2015073681, OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS, SAID 71.851 ACRE TRACT BEING MORE PARTICULARLY DESCRIBD BY METES AND BOUNDS AS FOLLOWS:

BEGINNING at a 1/2" iron rod with "Matkin-Hoover Eng. & Survey" cap set in the southeast boundary line of Lot 119-B, Drake's Crossing, recorded in Cabinet W, Slide 59, Plat Records of Williamson County, Texas, said point bears **North 69° 06' 00" East, a distance of 3.00'** (record North 69° 04' 53" East) from a 1" metal pipe found in the northeast right-of-way line of San Gabriel Ranch Road (right-of-way varies), being the south corner of Lot 119-B;

Thence, **North 69° 06' 00" East, along the southeast line of Drake's Crossing, a distance of 1303.93'** (record North 69° 04' 53" East) to a 1/2" iron rod found for angle at the east corner of Lot 119-J1, Drake's Crossing, the south corner of Lot 104, San Gabriel River Ranch, recorded in Cabinet 8, Slide 94, Plat Records of Williamson County, Texas;

Thence, along the southeast line of San Gabriel River Ranch, the following courses and distances:

- a. **North 69° 09' 28" East, 1003.02'** (record North 69° 09' 24" East, a distance of 1003.07') to a 1/2" iron rod found for angle;
- b. **North 68° 49' 10" East**, at a distance of 526.54 pass a 5/8" iron rod found on line, a total distance of **1053.67'** (record North 68° 45' 04" East) to a calculated point for corner in the southwest line of a called 232.61 acre tract recorded in Volume 845, Page 441, Deed Records of Williamson County, Texas;

Thence, with the southwest line of the called 232.61 acre tract, the following courses and distances:

- a. **South 07° 52' 50" East, 120.65'** (record South 07° 52' 31" East, 120.76') to a calculated point for angle;
- b. **South 30° 14' 20" East, 263.64'** (record South 30° 14' 01" East, 263.89') to a calculated point for corner at the north corner of a called 492 acre tract designated as "Tract 3", recorded in Volume 442, Page 122, Deed Records of Williamson County, Texas;

Thence, departing the southwest line of the called 232.61 acre tract, with the northwest line of the called 492 acre tract, the following courses and distances:

- a. **South 70° 01' 32" West**, at a distance of 298.42' pass a 1/2" iron rod with red "FOREST 1847" cap found for a point on line, a total distance of **745.12'** to a60d nail found for angle;
- b. **South 68° 49' 46" West, 288.46'** (record South 68° 51' 04" West, 288.37') to a 1/2" iron rod with red "FOREST 1847" cap found for angle;
- c. **South 69° 50' 42" West, 725.61'** (record South 69° 51' 53" West, 725.47') to a 1/2" metal pipe found for interior corner at the west corner of the called 492 acre tract;

Thence, with the southwest line of the called 492 acre tract, the following courses and distances:

- a. **South 18° 54' 38" East, 355.97'** (record S18° 51' 16" East, 355.27') to a 1/2" iron rod found for angle;
- b. **South 19° 54' 43" East, 438.45'** (record South 19° 55' 28" East, 438.35') to a 1/2" iron rod found for angle;
- c. **South 19° 06' 05" East, 284.40'** (record South 19° 06' 18" East, 284.50') to a 1/2" iron rod with red "FOREST 1847" cap found for angle;
- d. **South 19° 12' 21" East, 166.78'** (record South 19° 11' 59" East, 166.70') to a 1/2" iron rod found for corner at the north corner of a called 126-1/4 acre tract designated as "Tract 2", recorded in Volume 442, Page 122, Deed Records of Williamson County, Texas;



Thence, departing the southwest line of the called 492 acre tract, with the northwest line of the called 126-1/4 acre tract, the following courses and distances:

- a. **South 69° 36' 56" West, 440.57'** (record South 69° 37' 24" West, 440.59') to a 60d nail found for angle;
- b. **South 68° 54' 37" West, 459.95'** (record South 68° 54' 06" West, 459.89') to a 1/2" iron rod with "Matkin-Hoover Eng. & Survey" cap set for angle;
- c. **South 69° 35' 05" West, 623.57'** (record South 69° 34' 35" West, 626.59') to a 1/2" iron rod with "Matkin-Hoover Eng. & Survey" cap set for corner, said point bears North 69° 35' 05" East, a distance of 33.01' from a cotton spindle set in the northeast right-of-way line of San Gabriel Ranch Road (right-of-way varies);

Thence, departing the northwest line of the called 126-1/4 acre tract, the following courses and distances:

- a. **North 20° 04' 37" West, 498.89'** to a 1/2" iron rod with "Matkin-Hoover Eng. & Survey" cap set for angle;
- b. **North 21° 40' 53" West, 173.20'** to a 1/2" iron rod with "Matkin-Hoover Eng. & Survey" cap set for angle;
- c. **North 30° 44' 55" West, 279.21'** to a 1/2" iron rod with "Matkin-Hoover Eng. & Survey" cap set for angle;
- d. **North 21° 40' 53" West, 641.37'** to the **Place of Beginning** and containing w. more or less.

Note: The basis of bearing was established using the Trimble VRS Network, NAD (83), Texas State Plane Coordinate System, Central Zone, US Survey Foot, Grid. A survey plat was prepared by a separate document.



VICINITY MAP
NOT TO SCALE

REPLAT FOR ESTABLISHING
THE HIDDEN CREEK ESTATES SUBDIVISION

OWNER/DEVELOPER:
SAN GABRIEL
HIDDEN CREEK ESTATES, LLC
C/O DAVY ROBERTS
9508 EAST HWY 71
SPICEWOOD, TX 78669
OFF: 1-(800) 511-2430
DROBERTS@
LONESTARLANDPARTNERS.COM

AGENT/PREPARER:
MATKIN HOOVER
ENGINEERING & SURVEYING
C/O GARRETT D. KELLER, P.E.
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFF: (830) 249-0600
FAX: (830) 249-0099
GKELLER@MATKINHOOVER.COM

MATKINHOOVER
ENGINEERING
& SURVEYING
P.O. BOX 54
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFFICE: 830.249.0600 FAX: 830.249.0099
TEXAS REGISTERED ENGINEERING FIRM F-004512
TEXAS REGISTERED SURVEYING FIRM F-10024000
CIVIL ENGINEERS SURVEYORS LAND PLANNERS CONSTRUCTION MANAGERS CONSULTANTS

DATE: JULY 2016


JOB NO. 2738.00

SHEET 1 OF 5

0 50' 100' 150' 200'


BILL WARREN
232.61 ACRES
VOLUME 845, PAGE 441
DEED RECORDS
WILLIAMSON COUNTY, TEXAS

JOHN MCDEVITT
SURVEY
ABSTRACT NO. 415



P.U.D.E.E.	PUBLIC UTILITY, DRAINAGE, EMBANKMENT/BACKSLOPE EASEMENT
F.F.E.	FINISHED FLOOR ELEVATION
P.O.B.	POINT OF BEGINNING
O.S.S.F.	ON SITE SEWAGE FACILITY
○	SET 1/2" IRON ROD WITH A RED "MATKIN-HOOVER ENG. & SURVEY." PLASTIC CAP - UNLESS NOTED
●	FOUND 1/2" IRON ROD
⊙	FOUND 5/8" IRON ROD
⊗	FOUND 6/8" NAIL
⊗	FOUND 1/2" METAL PIPE
⊗	FOUND 1" METAL PIPE
⊗	FOUND 1/2" IRON ROD WITH A RED "FOREST 1847" PLASTIC CAP
⊙	CALCULATED POINT

CURVE TABLE					
CURVE	RADIUS	LENGTH	DELTA	CHORD BEARING	CHORD LENGTH
C7	350.00'	212.77'	34°49'51"	N35° 04' 35"E	209.51'
C8	205.00'	184.25'	51°29'49"	N43° 24' 34"E	178.11'
C9	60.00'	177.44'	169°26'18"	S63° 52' 09"W	119.49'
C10	25.00'	34.81'	79°46'55"	N71° 18' 09"W	32.07'
C11	1025.00'	6.29'	0°21'05"	S68° 58' 56"W	6.29'
C12	155.00'	139.31'	51°29'49"	S43° 24' 34"W	134.67'
C13	400.00'	243.17'	34°49'51"	S35° 04' 35"W	239.44'



EASEMENT LINE TABLE		
L16	N44° 27' 46"E	327.45'
L17	N81° 50' 14"E	200.13'
L18	N87° 11' 18"E	161.59'
L19	N58° 00' 47"E	74.11'
L20	N17° 08' 23"E	92.30'
L30	N59° 19' 50"E	154.62'
L31	N29° 05' 50"E	88.33'
L32	N38° 07' 42"W	149.08'
L33	S56° 28' 18"E	220.43'
L34	S67° 53' 51"E	151.23'
L35	N30° 30' 47"E	127.95'
L36	N51° 37' 40"W	237.26'

REPLAT FOR ESTABLISHING
THE HIDDEN CREEK ESTATES SUBDIVISION


OWNER/DEVELOPER:
SAN GABRIEL
HIDDEN CREEK ESTATES, LLC
C/O DAVY ROBERTS
9508 EAST HWY 71
SPICEWOOD, TX 78669
OFF: 1-(800) 511-2430
DROBERTS@
LONESTARLANDPARTNERS.COM

AGENT/PREPARER:
MATKIN HOOVER
ENGINEERING & SURVEYING
C/O GARRETT D. KELLER, P.E.
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFF: (830) 249-0600
FAX: (830) 249-0099
GKELLER@MATKINHOOVER.COM

MATKIN
P.O. BOX 54
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFFICE: 830.249.0600 FAX: 830.249.0059
HOOPER
ENGINEERING
& SURVEYING
TEXAS REGISTERED ENGINEERING FIRM F-004512
TEXAS REGISTERED SURVEYING FIRM F-10024000
CIVIL ENGINEERS SURVEYORS LAND PLANNERS CONSTRUCTION MANAGERS CONSULTANTS

SHEET 2 **OF** 5

LOTS 1A; 2A & 3A - LINE TABLE		
LINE	BEARING	DISTANCE
L100	N20° 55' 25"W	20.00'
L101	S69° 04' 35"W	35.00'
L102	N20° 55' 25"W	100.00'
L103	N69° 04' 35"E	100.00'
L104	S20° 55' 25"E	100.00'
L105	S69° 04' 35"W	35.00'
L106	S20° 55' 25"E	20.00'



CURVE TABLE				
CURVE	RADIUS	LENGTH	DELTA	CHORD BEARING
C1	475.00'	83.57'	10°04'52"	N64° 02' 09"E
C2	425.00'	232.28'	31°18'52"	N74° 39' 09"E
C3	475.00'	86.03'	10°15'24"	N85° 10' 53"E
C4	205.00'	100.12'	27°59'02"	S85° 57' 18"E
C5	25.00'	33.79'	77°26'40"	N69° 18' 53"E
C6	300.00'	114.66'	21°53'57"	N41° 32' 32"E
C14	250.00'	95.55'	21°53'57"	S41° 32' 32"W
C15	25.00'	33.79'	77°26'38"	S08° 07' 46"E
C16	205.00'	85.24'	23°49'25"	S34° 56' 23"E
C17	25.00'	22.69'	51°59'35"	S49° 01' 28"E
C18	60.00'	301.44'	287°51'08"	S68° 54' 18"W

CURVE TABLE				
CURVE	RADIUS	LENGTH	DELTA	CHORD BEARING
C19	25.00'	25.02'	57°20'51"	N04° 09' 27"E
C20	155.00'	204.06'	75°25'51"	N62° 13' 54"W
C21	525.00'	93.98'	10°15'24"	S85° 10' 53"W
C22	375.00'	204.95'	31°18'52"	S74° 39' 09"W
C23	525.00'	28.89'	3°09'09"	S60° 34' 18"W
C24	25.00'	36.25'	83°04'17"	S20° 36' 43"W
C25	25.00'	39.27'	90°00'00"	S65° 55' 25"E
C26	25.00'	34.83'	79°50'09"	N29° 09' 30"E
C27	60.00'	272.10'	259°50'09"	S60° 50' 30"E
C28	75.00'	117.81'	90°00'00"	N65° 55' 25"W
C29	25.00'	39.27'	90°00'00"	N65° 55' 25"W

LEGEND
P.U.D.E.B.E. PUBLIC UTILITY, DRAINAGE, EMBANKMENT/BACKSLOPE EASEMENT
F.F.E. FINISHED FLOOR ELEVATION
P.O.B. POINT OF BEGINNING
O.S.S.F. ON SITE SEWAGE FACILITY
○ SET 1/2" IRON ROD WITH A RED "MATKIN-HOOVER
ENG. & SURVEY." PLASTIC CAP - UNLESS NOTED
● FOUND 1/2" IRON ROD
● FOUND 5/8" IRON ROD
● FOUND 60D NAIL
● FOUND 1/2" METAL PIPE
● FOUND 1" METAL PIPE
● FOUND 1/2" IRON ROD WITH A RED
"FOREST 1847" PLASTIC CAP
CALCULATED POINT
HATCHED AREA REPRESENTS A 0.848 ACRE
VARIABLE WIDTH RIGHT-OF-WAY DEDICATION
○ VERTICAL REFERENCE MARK
COTTON SPINDLE SET IN ASPHALT

REPLAT FOR ESTABLISHING THE HIDDEN CREEK ESTATES SUBDIVISION

OWNER/DEVELOPER:
SAN GABRIEL
HIDDEN CREEK ESTATES, LLC
C/O DAVY ROBERTS
9508 EAST HWY 71
SPICEWOOD, TX 78669
OFF: (830) 511-2430
DROBERTS@
LONESTARLANDPARTNERS.COM

AGENT/PREPARER:
MATKIN HOOVER
ENGINEERING & SURVEYING
C/O GARRETT D. KELLER, P.E.
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFF: (830) 249-0600
FAX: (830) 249-0099
GKELLER@MATKINHOOVER.COM

MATKINHOOVER
ENGINEERING
& SURVEYING
P.O. BOX 54
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFFICE: (830) 249-0600 FAX: (830) 249-0099
TEXAS REGISTERED ENGINEERING FIRM F-004512
TEXAS REGISTERED SURVEYING FIRM F-10024000
CIVIL ENGINEERS SURVEYORS LAND PLANNERS CONSTRUCTION MANAGERS CONSULTANTS

DATE: JULY 2016

JOB NO. 2738.00

SHEET 3 OF 5

NOTES:

1. ACREAGE OF SUBDIVISION = 71.851 ACRES. THE OVERALL AVERAGE DENSITY OF LOTS IN THIS SUBDIVISION IS 1.142 AC/Lot.
2. LOTS IN THIS SUBDIVISION ARE ENCLOSED BY SPECIAL FLOOD HAZARD AREAS INUNDED BY 100 YEAR FLOOD AS IDENTIFIED BY THE U.S. FEDERAL EMERGENCY MANAGEMENT AGENCY BOUNDARY MAP, (FLOOD INSURANCE RATE MAP), COMMUNITY PANEL NO. 48491C0250E. EFFECTIVE DATE SEPTEMBER 28, 2008 FOR WILLIAMSON COUNTY, TEXAS. A DE FACTO CERTIFICATE OF COMPLIANCE IS HEREBY ISSUED FOR ALL LOTS WITHIN THIS SUBDIVISION EXCEPT FOR LOTS 12, 13, 14, 15, 16, AND 17. THIS CERTIFICATE IS VALID UNTIL SUCH TIME AS FEMA REVISES OR NEWLY ADOPTS FLOODPLAIN BOUNDARIES IN THIS AREA. A FLOODPLAIN DEVELOPMENT PERMIT MUST BE OBTAINED FROM THE WILLIAMSON COUNTY FLOODPLAIN ADMINISTRATOR FOR LOTS 12, 13, 14, 15, 16, AND 17 PRIOR TO ANY CONSTRUCTION OR DEVELOPMENT.
3. WATER SERVICE FOR THIS SUBDIVISION WILL BE PROVIDED BY AQUA TEXAS INC.
4. SEWER SERVICE FOR THIS SUBDIVISION, EXCEPT FOR LOT 2A, WILL BE PROVIDED BY ONSITE SEWAGE FACILITIES.
5. ELECTRIC SERVICE PROVIDED BY PEDERNALES ELECTRIC COOPERATIVE.
6. RURAL MAILBOXES SHALL BE SET THREE FEET FROM THE EDGE OF THE PAVEMENT OR BEHIND CURBS, WHEN USED. ALL MAILBOXES WITHIN COUNTY ARTERIAL RIGHT-OF-WAY SHALL MEET THE CURRENT TxDOT STANDARDS. ANY MAILBOX THAT DOES NOT MEET THIS REQUIREMENT MAY BE REMOVED BY WILLIAMSON COUNTY.
7. A TWENTY (20) FOOT UTILITY EMBANKMENT/BACKSLOPE AND DRAINAGE EASEMENT (P.U.D.E.B.E.) IS HEREBY DEDICATED ALONG THE FRONT PROPERTY LINE OF ALL LOTS IN THIS SUBDIVISION IN ADDITION TO THOSE UTILITY AND DRAINAGE EASEMENTS SHOWN ON THE PLAT. THERE IS ALSO HEREBY DEDICATED A FIVE (5) FOOT WIDE UTILITY AND DRAINAGE EASEMENT ADJACENT TO ALL NON-ROADWAY LOT LINES UNLESS OTHERWISE NOTED ON THE PLAT. IF TWO OR MORE LOTS ARE COMBINED AS A SINGLE HOMESITE, THIS EASEMENT SHALL BE RELINQUISHED ALONG THE COMMON LINE OR LINES OF THE COMBINED LOTS SO LONG AS NO UTILITY LINES OR DRAINAGE IMPROVEMENTS ARE LOCATED THEREIN.
8. ALL PUBLIC UTILITY EASEMENTS ARE FOR UTILITY IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO ELECTRIC, TELEPHONE AND/OR CATV LINES AND APPURTENANCES.
9. GRANTOR HEREBY AGREES TO DEDICATE TO THE PUBLIC A UTILITY EASEMENT AND/OR UTILITY RIGHT-OF-WAY ON THIS PLAT FOR UTILITY PURPOSES.
10. EXCEPT AS SHOWN, ALL CORNERS ARE 1/2" IRON RODS.
11. BASIS OF BEARING: WAS ESTABLISHED USING THE TRIMBLE VRS NETWORK, TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, 4203, US SURVEY FOOT, GRID. VERTICAL DATUM: NAVD 88.
12. IN APPROVING THIS REPLAT BY THE COMMISSIONER'S COURT OF WILLIAMSON COUNTY, TEXAS, IT IS UNDERSTOOD THAT THE BUILDING OF ALL STREETS, ROADS, AND OTHER PUBLIC THOROUGHFARES AND ANY BRIDGES OR CULVERTS NECESSARY TO BE CONSTRUCTED OR PLACED IS THE RESPONSIBILITY OF THE OWNERS OF THE TRACT OF LAND COVERED BY THIS PLAT IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS PRESCRIBED BY THE COMMISSIONER'S COURT OF WILLIAMSON COUNTY, TEXAS. SAID COMMISSIONER'S COURT ASSUMES NO OBLIGATION TO BUILD ANY OF THE STREETS, ROADS, OR OTHER PUBLIC THOROUGHFARES SHOWN ON THIS REPLAT OR OF CONSTRUCTING ANY OF THE BRIDGES OR DRAINAGE IMPROVEMENTS IN CONNECTION THEREWITH. THE COUNTY WILL ASSUME NO RESPONSIBILITY FOR DRAINAGE WAYS OR EASEMENTS IN THE SUBDIVISION, OTHER THAN THOSE DRAINING OR PROTECTING THE ROAD SYSTEM AND STREETS.
13. IT IS THE RESPONSIBILITY OF THE OWNER, NOT THE COUNTY, TO ASSURE COMPLIANCE WITH THE PROVISIONS OF ALL APPLICABLE STATE, FEDERAL, AND LOCAL LAWS AND REGULATIONS RELATING TO THE PLATTING AND DEVELOPMENT OF THE PROPERTY. THE COUNTY ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF REPRESENTATIONS BY OTHER PARTIES IN THIS PLAT. FLOODPLAIN DATA, IN PARTICULAR, MAY CHANGE DEPENDING ON SUBSEQUENT DEVELOPMENT. IT IS FURTHER UNDERSTOOD THAT THE OWNERS OF THE TRACT OF LAND COVERED BY THIS PLAT MUST INSTALL AT THEIR OWN EXPENSE ALL TRAFFIC CONTROL DEVICES AND SIGNAGE THAT MAY BE REQUIRED BEFORE THE STREETS IN THE SUBDIVISION HAVE FINALLY BEEN ACCEPTED FOR MAINTENANCE BY THE COUNTY.
14. ALL PUBLIC ROADWAYS AND EASEMENTS AS SHOWN ON THE PLAT ARE FREE OF LIENS. REQUIRED RELEASE OF LIENS SHALL BE PROVIDED TO THE COMMISSIONER'S COURT.
15. THE MINIMUM LOWEST FINISHED FLOOR ELEVATION SHALL BE ONE FOOT HIGHER THAN THE HIGHEST SPOT ELEVATION THAT IS LOCATED WITHIN FIVE FEET OUTSIDE THE PERIMETER OF THE BUILDING, OR ONE FOOT ABOVE THE BFE, WHICHEVER IS HIGHER.
16. ALL DRIVEWAYS ONTO RURAL COUNTY ROADS WHOSE LOT IS SERVED BY A SEPTIC SYSTEM SHALL BE REQUIRED TO OBTAIN A PERMIT FROM THE WILLIAMSON COUNTY AND CITIES HEALTH DISTRICT PRIOR TO CONSTRUCTION. THE SUBDIVISION DEVELOPER WILL BE HELD RESPONSIBLE TO NOTIFY BUILDERS AND LOT OWNERS OF THIS REQUIREMENT.
17. ONE-WAY "CIRCULAR" DRIVEWAYS SHALL BE PROHIBITED. EACH LOT SHALL BE ALLOWED ONE ACCESS POINT TO THE COUNTY ROAD WITH A MINIMUM DRIVEWAY SPACING OF 120' FOR ANY ADJOINING DRIVEWAY.
18. RIGHT-OF-WAY EASEMENTS FOR WIDENING ROADWAYS OR IMPROVING DRAINAGE SHALL BE MAINTAINED BY THE LANDOWNER UNTIL ROAD OR DRAINAGE IMPROVEMENTS ARE ACTUALLY CONSTRUCTED ON THE PROPERTY. THE COUNTY HAS THE RIGHT AT ANY TIME TO TAKE POSSESSION OF ANY ROAD WIDENING EASEMENT FOR THE CONSTRUCTION, IMPROVEMENT OR MAINTENANCE OF THE ADJACENT ROAD. THE LANDOWNER ASSUMES ALL RISKS ASSOCIATED WITH IMPROVEMENTS LOCATED IN THE RIGHT-OF-WAY OR ROAD WIDENING EASEMENTS. BY PLACING ANYTHING IN THE RIGHT-OF-WAY OR ROAD WIDENING EASEMENTS, THE LANDOWNER INDEMNIFIES AND HOLDS THE COUNTY, ITS OFFICERS AND EMPLOYEES HARMLESS FROM ANY LIABILITY OWING TO PROPERTY DEFECTS OR NEGLIGENCE NOT ATTRIBUTABLE TO THEM AND ACKNOWLEDGES THAT THE IMPROVEMENTS MAY BE REMOVED BY THE COUNTY AND THAT THE OWNER OF THE IMPROVEMENT SHALL BE RESPONSIBLE FOR THE RELOCATION AND/OR REPLACEMENT OF THE IMPROVEMENT.
19. DRIVEWAY ACCESS TO SAN GABRIEL RANCH ROAD SHALL BE RESTRICTED FOR LOTS 1A, 33, 34, 35, 36, 37 AND 57.
20. RESIDENTIAL DRIVEWAYS ARE TO BE LOCATED NO CLOSER TO THE CORNER OF INTERSECTING RIGHTS OF WAY THAN 60 PERCENT OF THE PARCEL FRONTAGE OR 50 FEET, WHICHEVER IS LESS.
21. A LOCKED GATE WITH A KNOX PAD LOCK SHALL BE INSTALLED WHERE THE EMERGENCY ACCESS ROAD CONNECTS TO SAN GABRIEL RANCH ROAD.
22. LOTS 33 AND 34 CAN UTILIZE THE 25' PRIVATE DRIVEWAY AND EMERGENCY ACCESS EASEMENT FOR INGRESS AND EGRESS FROM STAG LEAP COURT ONLY. NO PARKING IS ALLOWED ON THE EMERGENCY ACCESS ROAD CONNECTING STAG LEAP COURT TO SAN GABRIEL RANCH ROAD.
23. THE MINIMUM FINISHED FLOOR ELEVATIONS SHOWN ON THIS PLAT WERE DETERMINED BY ADDING A MINIMUM OF ONE (1) FOOT TO THE BASE FLOOD ELEVATION (BFE) AS DETERMINED BY THE SUPPLEMENTAL INUNDATION ANALYSIS PREPARED BY MATKIN HOOVER ENGINEERING & SURVEYING DATED JANUARY 29, 2016.
24. LOT 2A MAY NOT BE FURTHER SUBDIVIDED.
25. THIS REPLAT IS SUBJECT TO ALL APPLICABLE RECORDED EASEMENTS AND RESTRICTIONS AND AS SET FORTH IN THE ORIGINAL PLAT OF HIDDEN CREEK ESTATES, AS RECORDED IN DOCUMENT 2016032981 IN THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY.
26. DRIVEWAY ACCESS TO LOTS WITHIN THIS SUBDIVISION FROM SIDE STREETS IS PROHIBITED.

STATE OF TEXAS ☒
COUNTY OF WILLIAMSON ☒



I HEREBY CERTIFY THAT THIS PLAT IS TRUE AND CORRECT AND WAS PREPARED FROM AN ACTUAL SURVEY OF THE PROPERTY MADE UNDER MY SUPERVISION ON THE GROUND

REGISTERED PROFESSIONAL LAND SURVEYOR
JEFF BOERNER, R.P.L.S.

STATE OF TEXAS ☒
COUNTY OF WILLIAMSON ☒

I HEREBY CERTIFY THAT RECOGNIZED ENGINEERING PRACTICES AND STANDARDS WERE USED IN THE PREPARATION OF THIS FINAL PLAT AND IN THE DESIGN OF SITE IMPROVEMENT STRUCTURES AND WERE ACCOMPLISHED UNDER MY DIRECT SUPERVISION TO CONFORM TO ALL REQUIREMENTS OF THE WILLIAMSON COUNTY DEVELOPMENT RULES AND REGULATIONS. THIS TRACT IS NOT LOCATED WITHIN EDWARDS AQUIFER RECHARGE ZONE.


LICENSED PROFESSIONAL ENGINEER
GARRETT D. KELLER, PE



REPLAT OF HIDDEN CREEK ESTATES

THE PURPOSE OF THIS REPLAT IS TO RECONFIGURE LOTS 1,2 AND 3 INTO 1A, 2A AND 3A RESPECTIVELY AND TO CORRECT SCRIBNER ERRORS FOR THE FINAL PLAT OF HIDDEN CREEK ESTATES

BEING A 71.851 ACRE TRACT OF LAND, BEING A PORTION OF THE JOHN MCDEVITT SURVEY, ABSTRACT NO. 415, THE HENRY RHOADS SURVEY, ABSTRACT NO. 525, THE JAMES LEONARD SURVEY, ABSTRACT NO. 383, THE WILLIAM B BILLINGSLEY SURVEY, ABSTRACT NO. 95, AND THE JAMES HACKETT SURVEY, ABSTRACT NO. 312, WILLIAMSON COUNTY, TEXAS, SAID 71.851 ACRE TRACT BEING A PORTION OF THAT CERTAIN 72.6888 ACRE TRACT RECORDED IN DOCUMENT NO. 2015073681, OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS.



LOCATION MAP


N.T.S.

ROAD NAME AND ADDRESS ASSIGNMENTS VERIFIED THIS THE 19th DAY OF August, 2016 A.D.

Teresa Baker
WILLIAMSON COUNTY ADDRESSING COORDINATOR
TERESA BAKER

20' PUBLIC UTILITY, DRAINAGE AND EMBANKMENT/BACKSLOPE EASEMENT (P.U.D.E.B.E.)

PUBLIC RIGHT-OF-WAY



TYPICAL LOT EASEMENTS

N.T.S. (ESTABLISHED ON ALL LOTS)

SITE SUMMARY

SAN GABRIEL HIDEAWAY CREEK: 1491 L.F.
DESIGN SPEED: 25MPH
SEA SMOKE COVE: 1333 L.F.
DESIGN SPEED: 25MPH
STAG LEAP COURT: 684 L.F.
DESIGN SPEED: 25MPH
TAYLOR CREEK WAY: 1370 L.F.
DESIGN SPEED: 25MPH

OWNER/DEVELOPER:
SAN GABRIEL HIDDEN CREEK ESTATES, LLC
C/O DAVY ROBERTS
9508 EAST HWY 71
BOERNE, TEXAS 78006
OFF: (830) 511-2430
DROBERTS@LONESTARLANDPARTNERS.COM

AGENT/PREPARER:
MATKIN HOOVER
ENGINEERING & SURVEYING
C/O GARRETT D. KELLER, P.E.
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFF: (830) 249-0600
FAX: (830) 249-0099
GKELLER@MATKINHOOVER.COM

MATKINHOOVER
ENGINEERING & SURVEYING
P.O. BOX 54
8 SPENCER ROAD SUITE 100
BOERNE, TEXAS 78006
OFFICE: (830) 249-0600 FAX: (830) 249-0099
TEXAS REGISTERED ENGINEERING FIRM F-004512
TEXAS REGISTERED SURVEYING FIRM F-10024000
CIVIL ENGINEERS SURVEYORS LAND PLANNERS CONSTRUCTION MANAGERS CONSULTANTS

DATE: JULY 2016

JOB NO. 2738.00
SHEET 5 OF 5

STATE OF TEXAS ☒
COUNTY OF WILLIAMSON ☒


KNOW ALL MEN BY THESE PRESENTS:

I, DAVY ROBERTS, CO-OWNER AND AGENT FOR SAN GABRIEL HIDDEN CREEK ESTATES, LLC, SOLE OWNER OF THE CERTAIN TRACT OF LAND SHOWN HEREON AND DESCRIBED IN A DEED RECORDED IN DOCUMENT NO. 2015073681 OF THE OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS, AND DO HEREBY STATE THAT THERE ARE NO LIEN HOLDERS OF THE CERTAIN TRACT OF LAND, AND DO HEREBY SUBDIVIDE SAID TRACT AS SHOWN HEREON, AND DO HEREBY CONSENT TO ALL PLAT NOTE REQUIREMENTS SHOWN HEREON, AND DO HEREBY FOREVER DEDICATE TO THE PUBLIC THE ROADS, ALLEYS, RIGHTS-OF-WAY, EASEMENTS AND PUBLIC PLACES SHOWN HEREON FOR SUCH PUBLIC PURPOSES AS WILLIAMSON COUNTY MAY DEEM APPROPRIATE, AND DO HEREBY STATE THAT ALL PUBLIC ROADWAYS AND EASEMENTS AS SHOWN ON THIS PLAT ARE FREE OF LIENS. THIS SUBDIVISION IS TO BE KNOWN AS HIDDEN CREEK ESTATES.

SAN GABRIEL HIDDEN CREEK ESTATES, LLC
C/O DAVY ROBERTS
9508 EAST HWY 71
SPICEWOOD, TX 78669

Davy Roberts
OWNER
DAVY ROBERTS

BEFORE ME, THE ABOVE AUTHORITY, ON THIS DAY PERSONALLY APPEARED _____, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THIS FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED, AND IN THE CAPACITY THEREIN STATED. AND SEAL OF OFFICE THIS 17th DAY OF August, 2016 A.D.



Allyson Lynn Brown
NOTARY PUBLIC, STATE OF TEXAS

BASED UPON THE ABOVE REPRESENTATIONS OF THE ENGINEER OR SURVEYOR WHOSE SEAL IS AFFIXED HERETO, AND AFTER A REVIEW OF THE SURVEY AS REPRESENTED BY THE SAID ENGINEER OR SURVEYOR, I FIND THAT THIS BLUE LINE (SURVEY) COMPLIES WITH THE REQUIREMENTS OF EDWARDS AQUIFER REGULATIONS FOR WILLIAMSON COUNTY AND WILLIAMSON COUNTY ON-SITE SEWAGE FACILITY REGULATIONS. THIS CERTIFICATION IS MADE SOLELY UPON SUCH REPRESENTATIONS AND SHOULD NOT BE RELIED UPON FOR VERIFICATIONS OF THE FACTS ALLEGED. THE WILLIAMSON COUNTY AND CITIES HEALTH DISTRICT (WCCHD) AND WILLIAMSON COUNTY DISCLAIM ANY RESPONSIBILITY TO ANY MEMBER OF THE PUBLIC FOR INDEPENDENT VERIFICATION OF THE REPRESENTATIONS, FACTUAL OR OTHERWISE, CONTAINED IN THIS BLUE LINE (SURVEY) AND THE DOCUMENTS ASSOCIATED WITH IT.

Deborah L. Marlow, R.S. 050029596
DIRECTOR, ENVIRONMENTAL HEALTH SERVICES, WCCHD
8/18/2016
DATE

STATE OF TEXAS ☒
COUNTY OF WILLIAMSON ☒

KNOW ALL MEN BY THESE PRESENTS:

I, DAN A. GATTIS, COUNTY JUDGE OF WILLIAMSON COUNTY, TEXAS, DO HEREBY CERTIFY THAT THIS MAP OR PLAT, WITH FIELD NOTES HEREON, THAT A SUBDIVISION HAVING BEEN FULLY PRESENTED TO THE COMMISSIONER'S COURT OF WILLIAMSON COUNTY, TEXAS, AND BY THE SAID COURT DULY CONSIDERED, WERE ON THIS DAY APPROVED AND PLAT IS AUTHORIZED TO BE REGISTERED AND RECORDED IN THE PROPER RECORDS OF THE COUNTY CLERK OF WILLIAMSON COUNTY, TEXAS

DATED THIS _____ DAY OF _____, 20____ A.D.

BY:

DAN A. GATTIS, COUNTY JUDGE
WILLIAMSON COUNTY, TEXAS
DATE

STATE OF TEXAS ☒
COUNTY OF WILLIAMSON ☒

KNOW ALL MEN BY THESE PRESENTS:

I, NANCY E. RISTER, CLERK OF THE COUNTY COURT OF SAID COUNTY, DO HEREBY CERTIFY THAT THE FOREGOING INSTRUMENT IN WRITING, WITH ITS CERTIFICATE OF AUTHENTICATION WAS FILED FOR RECORD IN MY OFFICE ON THE _____ DAY OF _____, 20____ A.D. AT _____ O'CLOCK, _____ M AND DULY RECORDED THIS THE _____ DAY OF _____, 20____ A.D. AT _____ O'CLOCK, _____ M, IN THE OFFICIAL PUBLIC RECORDS OF SAID COUNTY IN INSTRUMENT NO. _____

TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT THE COUNTY COURT OF SAID COUNTY, AT MY OFFICE IN GEORGETOWN, TEXAS, THE DATE LAST SHOWN ABOVE WRITTEN.

NANCY E. RISTER, CLERK COUNTY COURT
OF WILLIAMSON COUNTY, TEXAS

BY: _____, DEPUTY