



Change Order Request

Williamson County Expo Center

210 Carlos G. Parker Blvd, NW

Flintco, LLC

Project # 15035

Taylor, TX 76574

Change Order Request: 018

Date: 9/7/2016

To: Dale Butler
Williamson County Texas
3101 SE Inner Loop
Georgetown, TX 78626

From: David Freisner
Flintco, LLC
8100 Cross Park Dr.
Austin, TX 78754-5249

Description

Addition Sitework and Drive At North Covered Penning Per RFI 138R1

Category**Status**

New

Reference**Required By**

9/14/2016

Days Req

3

Amt Req

\$0.00

Notes

PCO No	Date	Reference	Amt Prop	Days Req	Category	Reason
049	9/7/2016		\$0.00	0	Contingency	Change Condition

RFI 138 Additional Parking Sitework At Covered Penning

Item No	Item Description	Amt Prop	Reference
001	Champion Add for Additional Sitework/Parking Specs as issued in RFI 138 R1	\$29,883.00	
002	Buyout Contingency	\$(29,883.00)	

Flintco, LLC

CONTRACTOR

8100 Cross Park Dr.
Austin, TX 78754-5249

Address

By

SIGNATURE

DATE

Williamson County Texas

OWNER

3101 SE Inner Loop
Georgetown, TX 78626

Address

By

SIGNATURE

DATE

REQUEST FOR ADDITIONAL PRICING

CHAMPION SITE PREP, INC

455-A HIGHWAY 195
GEORGETOWN, TX 78628
512-863-3453 / FAX 512-863-3463
bart@idigdirt.com
RCO#7REV1 Rock around warm-up

DATE: 09/01/16
TO: Flintco, LLC.
ATTN: David Freisner

JOB NAME: WilCo Expo
ESTIMATOR: BL
LOCATION: Taylor, TX

We hereby request a change order for furnishing all materials and performing all of the labor necessary, per Plans and Specifications, for the completion of :

1	Mobilization	1	EA	\$	877.00	\$	877.00
2	Cut staking	4	HR	\$	124.00	\$	496.00
3	Excavate out section	0.5	DY	\$	2,870.00	\$	1,435.00
4	Haul spoils onsite (NO HAUL OFF INCLUDED)	25	LD	\$	47.00	\$	1,175.00
5	6" MC of subgrade	2	DY	\$	2,870.00	\$	5,740.00
5	Bluetop subgrade	4	HR	\$	124.00	\$	496.00
6	Import 6" flex base	9	LD	\$	345.00	\$	3,105.00
7	Process/place/compact/finish base	1.5	DY	\$	2,870.00	\$	4,305.00
8	Bluetop of base course	4	HR	\$	124.00	\$	496.00
9	Import 4" of TCS 567 rock	16	LD	\$	411.00	\$	6,576.00
10	Spread/compact 4" of rock to finish grade	1.5	DY	\$	2,870.00	\$	4,305.00
11	Demobilization	1	EA	\$	877.00	\$	877.00

Place 4" TCS 567 rock, 6" flex base on N side Covered Penning/Warm-up area. Place 4" of rock on along N & W sides per map. Moisture condition subgrade 6". Haul onsite cut for section. All work to be performed at one time.

Anything not listed is not included. Please call with any question.

Total Price: \$ 29,883.00

ACCEPTANCE OF PROPOSAL- The above prices, specifications and conditions are satisfactory and are hereby accepted.

AUTHORIZED SIGNATURE

DATE OF ACCEPTANCE



Potential Change Orders

Detailed, Grouped by Each Number

Williamson County Expo Center
 210 Carlos G. Parker Blvd, NW
 Taylor, TX 76574
Project # 15035
Flintco, LLC
 Tel: Fax: 15035

PCO #: 049	9/7/2016	RFI 138 Additional Parking Sitework At Covered Penning				New
Category	Reason	Reference	COR Number		PCCO Number	
Contingency	Change Condition					
Notes					Revenue Code	



Potential Change Orders
Detailed, Grouped by Each Number