

Received

Received

RECEIVED  
SEP 7 2018  
BY: PSI

SEP 12 2018

WILLIAMSON COUNTY, TEXAS

CHANGE ORDER NUMBER: 3

HNTB Corporation  
Round Rock

SEP 06 2018

HNTB Corporation  
Round Rock

- 1. CONTRACTOR: Chasco Constructors  
Inner Loop at Wilco Way
- 2. Change Order Work Limits: Sta. 100+00 to Sta. 110+00
- 3. Type of Change(on federal-aid non-exempt projects): Major (Major/Minor)
- 4. Reasons: 3F, 2C (3 Max. - In order of importance - Primary first)

Project:	<u>1706-168</u>
Roadway:	<u>Inner Loop Improvements</u>
CSJ Number:	_____

5. Describe the work being revised:

**3F: County Convenience. Additional work desired by the County. 2C: Differing Site Conditions(unforeseeable). New development (conditions changing after PS&E completed).** This Change Order deletes a driveway from Inner Loop that went to the Williamson County Animal Shelter and adds the construction of a new driveway to the shelter from Wilco Way.

- 6. Work to be performed in accordance with Items: See attached
- 7. New or revised plan sheet(s) are attached and numbered: \_\_\_\_\_
- 8. New Special Provisions/Specifications to the contract are attached: No
- 9. New Special Provisions to Item N/A No. N/A, Special Specification Item N/A are attached.

Each signatory hereby warrants that each has the authority to execute this Change Order (CO).

*The contractor must sign the Change Order and, by doing so, agrees to waive any and all claims for additional compensation due to any and all other expenses; additional changes for time, overhead and profit; or loss of compensation as a result of this change.*

**The following information must be provided**

Time Ext. #: 1 Days added on this CO: 90  
 Amount added by this change order: \$183,780.89

THE CONTRACTOR Date 8-15-18  
 By [Signature]  
 Typed/Printed Name BILL BANBRICK  
 Typed/Printed Title SR. PM

RECOMMENDED FOR EXECUTION:

[Signature] P.E. 9/6/18  
 Project Manager Date

N/A  
 Design Engineer Date

[Signature] 9/11/18  
 Program Manager Date

Design Engineer's Seal:  
 See attached plan sheets

County Commissioner Precinct 1 Date  
 APPROVED  REQUEST APPROVAL

County Commissioner Precinct 2 Date  
 APPROVED  REQUEST APPROVAL

County Commissioner Precinct 3 Date  
 APPROVED  REQUEST APPROVAL

County Commissioner Precinct 4 Date  
 APPROVED  REQUEST APPROVAL

County Judge Date  
 APPROVED

# WILLIAMSON COUNTY, TEXAS

CHANGE ORDER NUMBER:     3    

Project #     1706-168    

**TABLE A:** Force Account Work and Materials Placed into Stock

	LABOR	HOURLY		HOURLY RATE

**TABLE B:** Contract Items:

ITEM	DESCRIPTION	UNIT	UNIT PRICE	ORIGINAL + PREVIOUSLY REVISED		ADD or (DEDUCT)	NEW		OVERRUN/UNDERRUN
				QUANTITY	ITEM COST	QUANTITY	QUANTITY	ITEM COST	
	Inner Loop at Wilco Way								
110-6001	EXCAVATION(ROADWAY)	CY	\$8.00	11,275	\$90,200.00	781.00	12,056.00	\$96,448.00	\$6,248.00
132-6003	EMBANKMENT (FINAL)(ORD COMP)(TY B)	CY	\$12.00	13,247	\$158,964.00	(876.00)	12,371.00	\$148,452.00	(\$10,512.00)
160-WC02	FURNISHING AND PLACING TOPSOIL (4")	SY	\$1.50	24,389	\$36,583.50	848.00	25,237.00	\$37,855.50	\$1,272.00
166-6002	FERTILIZER	TON	\$820.00	2.20	\$1,804.00	0.10	2.30	\$1,886.00	\$82.00
168-WC01	VEGETATIVE WATERING	MG	\$28.00	1,019	\$28,532.00	25.40	1,044.40	\$29,243.20	\$711.20
169-6001	SOIL RETENTION BLANKETS (CL 1)(TY A)	SY	\$1.30	0	\$0.00	3,500.00	3,500.00	\$4,550.00	\$4,550.00
247-6044	FL BS (CMP IN PLC)(TY A GR 4)(FINAL POS)	CY	\$42.00	2,144	\$90,048.00	826.00	2,970.00	\$124,740.00	\$34,692.00
310-6001	PRIME COAT (MULTI OPTION)	GAL	\$4.20	1,520	\$6,384.00	59.00	1,579.00	\$6,631.80	\$247.80
316-6193	AGGR (TYPD GR 5 SAC B)	CY	\$100.00	143	\$14,300.00	(37.00)	106.00	\$10,600.00	(\$3,700.00)
316-6413	ASPH (AC-15P,HFRS-2P, CRS-2P)	GAL	\$3.25	6,250	\$20,312.50	(267.00)	5,983.00	\$19,444.75	(\$867.75)
341-6008	D-GR HMA TY B PG64-22	TON	\$68.00	1,292	\$87,856.00	51.00	1,343.00	\$91,324.00	\$3,468.00
341-6042	D-GR HMA TY D SAC B PG70-22	TON	\$81.20	1,875	\$152,250.00	(63.00)	1,812.00	\$147,134.40	(\$5,115.60)
432-6024	RIPRAP (STONE COMMON)(DRY)(12IN)	CY	\$130.00	11	\$1,430.00	4.00	15.00	\$1,950.00	\$520.00
464-6003	RC PIPE (CL III)(18IN)	LF	\$50.00	195	\$9,750.00	(87.00)	108.00	\$5,400.00	(\$4,350.00)
464-6008	RC PIPE (CL III)(36IN)	LF	\$111.00	138	\$15,318.00	9.00	147.00	\$16,317.00	\$999.00
464-6009	RC PIPE (CL III)(42IN)	LF	\$122.00	434	\$52,948.00	9.00	443.00	\$54,046.00	\$1,098.00
467-6363	SET (TY II)(18IN)(RCP)(6:1)(P)	EA	\$800.00	2	\$1,600.00	(2.00)	0.00	\$0.00	(\$1,600.00)
467-6477	SET (TY II)(48IN)(RCP)(4:1)C	EA	\$5,000.00	9	\$45,000.00	(8.00)	1.00	\$5,000.00	(\$40,000.00)
<b>TOTALS</b>					<b>\$813,280.00</b>			<b>\$801,022.65</b>	<b>(\$12,257.35)</b>

## WILLIAMSON COUNTY, TEXAS

CHANGE ORDER NUMBER: 3

Project # 1706-168

TABLE B: Contract Items:

ITEM	DESCRIPTION	UNIT	UNIT PRICE	ORIGINAL + PREVIOUSLY REVISED		ADD or (DEDUCT)	NEW		OVERRUN/ UNDERRUN
				QUANTITY	ITEM COST	QUANTITY	QUANTITY	ITEM COST	
	Inner Loop at Wilco Way								
506-6002	ROCK FILTER DAMS (INSTALL)(TY 2)	LF	\$20.00	170	\$3,400.00	15.00	185.00	\$3,700.00	\$300.00
506-6011	ROCK FILTER DAMS (REMOVE)	LF	\$10.00	170	\$1,700.00	15.00	185.00	\$1,850.00	\$150.00
506-6041	BIODEGR EROSN CONT LOGS (INSTL)(12")	LF	\$5.00	4,095	\$20,475.00	96.00	4,191.00	\$20,955.00	\$480.00
506-6043	BIODEGR EROSN CONT LOGS (REMOVE)	LF	\$0.30	4,095	\$1,228.50	96.00	4,191.00	\$1,257.30	\$28.80
530-6004	DRIVEWAY (CONC)	SY	\$68.00	891	\$60,588.00	(432.00)	459.00	\$31,212.00	(\$29,376.00)
531-6002	CONC SIDEWALKS (5")	SY	\$44.00	1,405	\$61,820.00	67.00	1,472.00	\$64,768.00	\$2,948.00
666-6029	REFL PAV MRK TY I (W)8"(DOT)(090 MIL)	LF	\$1.50	44	\$66.00	24.00	68.00	\$102.00	\$36.00
666-6035	REFL PAV MRK TY I (W)8"(SLD)(090 MIL)	LF	\$0.85	932	\$792.20	(52.00)	880.00	\$748.00	(\$44.20)
666-6047	REFL PAV MRK TY I (W)24"(SLD)(090MIL)	EA	\$4.80	24.00	\$115.20	51.00	75.00	\$360.00	\$244.80
666-5053	REFL PAV MRK TY I (W)(ARROW)(090 MIL)	EA	\$85.00	10.00	\$850.00	(2.00)	8.00	\$680.00	(\$170.00)
666-6077	REFL PAV MRK TY I (WORD)(090 MIL)	EA	\$95.00	6.00	\$570.00	(2.00)	4.00	\$380.00	(\$190.00)
666-6170	REFL PAV MRK TY II (W) 4" (SLD)	LF	\$0.15	4898.00	\$734.70	136.00	5,034.00	\$755.10	\$20.40
666-6176	REFL PAV MRK TY II (W) 8" (DOT)	LF	\$0.35	44.00	\$15.40	24.00	68.00	\$23.80	\$8.40
666-6178	REFL PAV MRK TY II (W) 8" (SLD)	LF	\$0.30	932.00	\$279.60	(220.00)	712.00	\$213.60	(\$66.00)
666-6184	REFL PAV MRK TY II (W)(ARROW)	EA	\$42.00	10.00	\$420.00	(2.00)	8.00	\$336.00	(\$84.00)
666-6192	REFL PAV MRK TY II (W)(WORD)	EA	\$50.00	6.00	\$300.00	(2.00)	4.00	\$200.00	(\$100.00)
666-6207	REFL PAV MRK TY II (Y) 4" (SLD)	LF	\$0.15	6411.00	\$961.65	481.00	6,892.00	\$1,033.80	\$72.15
666-6302	RE PM W/RET REQ TY I (W) 4" (SLD)(090 MIL)	LF	\$0.35	4898.00	\$1,714.30	136.00	5,034.00	\$1,761.90	\$47.60
666-6314	RE PM W/RET REQ TY I (Y) 4" (SLD)(090 MIL)	LF	\$0.35	6411.00	\$2,243.85	481.00	6,892.00	\$2,412.20	\$168.35
672-6007	REFL PAV MRKR TY I-C	EA	\$4.00	47.00	\$188.00	(13.00)	34.00	\$136.00	(\$52.00)
999-WC04	RE-STOCKING FEE FOR UNUSED MATERIALS	LS	\$2,100.00	0	\$0.00	1.00	1.00	\$2,100.00	\$2,100.00
The "Totals" from Table B of the previous work sheet:						\$813,280.00		\$801,022.65	(\$12,257.35)
<b>TOTALS</b>						<b>\$971,742.40</b>		<b>\$936,007.35</b>	<b>(\$35,735.05)</b>

# WILLIAMSON COUNTY, TEXAS

CHANGE ORDER NUMBER: 3

Project # 1706-168

TABLE B: Contract Items (Continued)

ITEM	DESCRIPTION	UNIT	UNIT PRICE	ORIGINAL + PREVIOUSLY REVISED		ADD or (DEDUCT)	NEW		OVERRUN/ UNDERRUN
				QUANTITY	ITEM COST	QUANTITY	QUANTITY	ITEM COST	
	Animal Shelter Driveway								
100-6002A	PREPARING ROW	STA	\$1,600.00	0.00	\$0.00	4.85	4.85	\$7,760.00	\$7,760.00
104-6029A	REMOVING CONC (CURB OR CURB AND GUTTER)	LF	\$8.00	0.00	\$0.00	181.00	181.00	\$1,448.00	\$1,448.00
110-6001A	EXCAVATION (ROADWAY)	CY	\$8.00	0.00	\$0.00	270.00	270.00	\$2,160.00	\$2,160.00
110-6002A	EXCAVATION (CHANNEL)	CY	\$18.00	0.00	\$0.00	23.00	23.00	\$414.00	\$414.00
132-6003A	EMBANKMENT (FINAL)(ORD COM)(TY B)	CY	\$12.00	0.00	\$0.00	199.00	199.00	\$2,388.00	\$2,388.00
160-WC02A	FURNISHING AND PLACING TOPSOIL (4")	SY	\$1.50	0.00	\$0.00	2766.00	2,766.00	\$4,149.00	\$4,149.00
164-WC05A	SEEDING FOR EROSION CONTROL (PERM)(WARM)(TY 5)	SY	\$0.25	0.00	\$0.00	2766.00	2,766.00	\$691.50	\$691.50
166-6002A	FERTILIZER	TON	\$820.00	0.00	\$0.00	0.02	0.02	\$16.40	\$16.40
168-WC01A	VEGETATIVE WATERING	MG	\$28.00	0.00	\$0.00	83.00	83.00	\$2,324.00	\$2,324.00
169-6001A	SOIL RETENTION BLANKET (CL 1)(TY A)	SY	\$1.30	0.00	\$0.00	1000.00	1,000.00	\$1,300.00	\$1,300.00
247-6044A	FL BS (COMP IN PLC)(TY A GR 4)(FINAL POS)	CY	\$42.00	0.00	\$0.00	795.00	795.00	\$33,390.00	\$33,390.00
260-6009A	LIME TRT (EXST MATL)(10")	SY	\$11.26	0.00	\$0.00	2329.00	2,329.00	\$26,224.54	\$26,224.54
260-6016A	LIME (SLURRY)	TON	\$182.00	0.00	\$0.00	53.00	53.00	\$9,646.00	\$9,646.00
310-6001A	PRIME COAT (MULTI OPTION)	GAL	\$4.20	0.00	\$0.00	263.00	263.00	\$1,104.60	\$1,104.60
316-6193A	AGGR (TY D GR 5 SAC-B)	CY	\$100.00	0.00	\$0.00	9.00	9.00	\$900.00	\$900.00
316-6413A	ASPH (AC-15P, HFRS-2P OR CRS-2P)	GAL	\$3.25	0.00	\$0.00	499.00	499.00	\$1,621.75	\$1,621.75
341-6008A	D-GR HMA TY B PG 64-22	TON	\$68.00	0.00	\$0.00	302.00	302.00	\$20,536.00	\$20,536.00
341-6042A	D-GR HMA TY D SAC B PG 70-22	TON	\$80.00	0.00	\$0.00	151.00	151.00	\$12,080.00	\$12,080.00
432-6024A	RIP RAP (STONE COMMON)(DRY)(12IN)	CY	\$130.00	0.00	\$0.00	4.00	4.00	\$520.00	\$520.00
464-6018A	RPIPE (CL IV)(24IN)	LF	\$58.00	0.00	\$0.00	131.00	131.00	\$7,598.00	\$7,598.00
465-6126A	INLET (COMPL)(PSL)(FG)(3FT X 3FT )	EA	\$2,900.00	0.00	\$0.00	1.00	1.00	\$2,900.00	\$2,900.00
467-6388A	SET (TY II)(24IN)(RCP)(3:1)C	EA	\$1,400.00	0.00	\$0.00	1.00	1.00	\$1,400.00	\$1,400.00
506-6002A	ROCK FILTER DAMS (INSTALL)(TY 2)	LF	\$20.00	0.00	\$0.00	5.00	5.00	\$100.00	\$100.00
506-6011A	ROCK FILTER DAMS (REMOVE)	LF	\$10.00	0.00	\$0.00	5.00	5.00	\$50.00	\$50.00
506-6041A	BIODEG EROSN CONT LOGS (INSTL)(12IN)	LF	\$5.00	0.00	\$0.00	540.00	540.00	\$2,700.00	\$2,700.00
506-6043A	BIODEG EROSN CONT LOGS (REMOVE)	LF	\$0.30	0.00	\$0.00	540.00	540.00	\$162.00	\$162.00
529-6030A	CONC CURB & GUTTER (VALLEY GUTTER)	LF	\$13.00	0.00	\$0.00	800.00	800.00	\$10,400.00	\$10,400.00
530-6004A	DRIVEWAYS (CONC)	SY	\$98.00	0.00	\$0.00	650.00	650.00	\$63,700.00	\$63,700.00
666-6035A	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF	\$0.85	0.00	\$0.00	168.00	168.00	\$142.80	\$142.80
666-6047A	REFL PAV MRK TY I (W)24"(SLD)(090MIL)	LF	\$4.80	0.00	\$0.00	51.00	51.00	\$244.80	\$244.80
666-6053A	REFL PAV MRK TY I (W)(ARROW)(090MIL)	EA	\$85.00	0.00	\$0.00	4.00	4.00	\$340.00	\$340.00
666-6077A	REFL PAV MRK TY I (W)(WORD)(090MIL)	EA	\$95.00	0.00	\$0.00	2.00	2.00	\$190.00	\$190.00
666-6178A	REFL PAV MRK TY II(W)8"(SLD)	LF	\$0.30	0.00	\$0.00	168.00	168.00	\$50.40	\$50.40
666-6182A	REFL PAV MRK TY II (W)24"(SLD)	LF	\$1.65	0.00	\$0.00	51.00	51.00	\$84.15	\$84.15
666-6184A	REFL PAV MRK TY II (W)(ARROW)	EA	\$42.00	0.00	\$0.00	4.00	4.00	\$168.00	\$168.00
666-6192A	REFL PAV MRK TY II (W)(WORD)	EA	\$50.00	0.00	\$0.00	2.00	2.00	\$100.00	\$100.00
666-6207A	REFL PAV MRK TY II (Y)4"(SLD)	LF	\$0.15	0.00	\$0.00	944.00	944.00	\$141.60	\$141.60
666-6314A	RE PM WRET REQ TY I (Y)4"(SLD)(090MIL)	LF	\$0.35	0.00	\$0.00	944.00	944.00	\$330.40	\$330.40
672-6007A	REFL PAV MRKR TY I-C	EA	\$4.00	0.00	\$0.00	10.00	10.00	\$40.00	\$40.00
The "Totals" from Table B of the previous work sheet:						\$971,742.40		\$936,007.35	(\$35,735.05)
<b>TOTALS</b>						<b>\$971,742.40</b>		<b>\$1,155,523.29</b>	<b>\$183,780.89</b>

# CHANGE ORDER REASON(S) CODE CHART

<p>1. Design Error or Omission</p>	<p>1A. Incorrect PS&amp;E 1B. Other</p>
<p>2. Differing Site Conditions (unforeseeable)</p>	<p>2A. Dispute resolution (expense caused by conditions and/or resulting delay) 2B. Unavailable material 2C. New development (conditions changing after PS&amp;E completed) 2D. Environmental remediation 2E. Miscellaneous difference in site conditions (unforeseeable)(Item 9) 2F. Site conditions altered by an act of nature 2G. Unadjusted utility (unforeseeable) 2H. Unacquired Right-of-Way (unforeseeable) 2I. Additional safety needs (unforeseeable) 2J. Other</p>
<p>3. County Convenience</p>	<p>3A. Dispute resolution (not resulting from error in plans or differing site conditions) 3B. Public relations improvement 3C. Implementation of a Value Engineering finding 3D. Achievement of an early project completion 3E. Reduction of future maintenance 3F. Additional work desired by the County 3G. Compliance requirements of new laws and/or policies 3H. Cost savings opportunity discovered during construction 3I. Implementation of improved technology or better process 3J. Price adjustment on finished work (price reduced in exchange for acceptance) 3K. Addition of stock account or material supplied by state provision 3L. Revising safety work/measures desired by the County 3M. Other</p>
<p>4. Third Party Accommodation</p>	<p>4A. Failure of a third party to meet commitment 4B. Third party requested work 4C. Compliance requirements of new laws and/or policies (impacting third party) 4D. Other</p>
<p>5. Contractor Convenience</p>	<p>5A. Contractor exercises option to change the traffic control plan 5B. Contractor requested change in the sequence and/or method of work 5C. Payment for Partnering workshop 5D. Additional safety work/measures desired by the contractor 5E. Other</p>
<p>6. Untimely ROW/Utilities</p>	<p>6A. Right-of-Way not clear (third party responsibility for ROW) 6B. Right-of-Way not clear (County responsibility for ROW) 6C. Utilities not clear 6D. Other</p>

**Williamson County Road Bond Program  
Inner Loop Improvements**

**Williamson County Project No. 1706-168**

**Change Order No. 3**

**Reason for Change**

This Change Order deletes a driveway from Inner Loop that went to the Williamson County Animal Shelter and adds the construction of a new driveway to the shelter from Wilco Way.

The driveway was deleted because it was located at a low spot in the profile of the existing roadway that did not provide visibility of vehicles on Inner Loop. Deleting the driveway modified elements of the Wilco Way portion of the project. The right turn lane to the Animal Shelter driveway was deleted which changed quantities for various items such as excavation, embankment, erosion control, pavement markings and drainage. The Contractor maintained the original bid prices in the contract for the additional work. The Change Order also documents reductions in quantities for Safety End treatments on the Wilco Way portion of the project. The construction of new safety end treatments on existing pipes was deleted because the existing pipes functioned normally and replacement was not necessary. This resulted in a cost savings for the project. In exchange for deletion of the safety end treatments, a small re-stocking fee will be paid for the unused materials that were already delivered to the project.

The Contractor requested 90 days to be added to the contract for this additional work because they have completed work on the original contract and demobilized from the project. Due to their workload of other projects it is unknown at this time when work will begin on the driveway. The Contractor has assured that work will begin as soon as possible. There will be no additional cost to the County for this delay.

The following summarizes the new Contract items required for this Change Order. The unit rate submitted by the Contractor is consistent with the County and TxDOT average low bid unit price.

ITEM	DESCRIPTION	QTY	UNIT
260-6009A	LIME TRT (EXIST MATL)(10")	2329.00	SY
260-6016A	LIME (SLURRY)	53.00	TON
464-6018A	RCPIPE (CL IV)(24IN)	131.00	LF
999-WC04	RE-STOCKING FEE FOR UNUSED MATERIALS	1.00	LS

This Change Order results in a net increase of \$183,780.89 to the Contract amount, for an adjusted Contract total of \$5,580,209.02. The original Contract amount was \$5,352,696.00. As a result of this and all Change Orders to-date, \$227,513.02 has been added to the Contract, resulting in a 4.25% net increase in the Contract cost. Ninety (90) days will be added to the Contract as a result of this Change Order.

**HNTB Corporation**

James Klotz, P.E.

## Dawn Haggard

---

**From:** Bill Bambrick <bill@chasco.com>  
**Sent:** Wednesday, August 01, 2018 2:56 PM  
**To:** Clayton Weber; Steven Shull; Eddie R. Church; 62811\_1706-168\_InnerLoopImprovements  
**Cc:** Scott Warner  
**Subject:** New Animal Shelter access road

Clayton,

With regard to the schedule for the new access road to the Animal Shelter on Wilco Way Chasco requests 90 days be added to the contract time. The actual construction of the drive will take about two months however due to our current work load it will likely be a month (or more) before we can even get started on it. Please let me know if you have any questions.

Thanks,

**Bill Bambrick**  
*Senior Project Manager*



General Contractor  
Construction Manager  
Excavation  
Concrete  
Utilities

P.O. Box 1057  
Round Rock, TX 78680  
Tel: (512) 244-0600  
Fax: (512) 244-6085  
www.chasco.com



## Dawn Haggard

---

**From:** Bill Bambrick <bill@chasco.com>  
**Sent:** Tuesday, June 26, 2018 11:33 AM  
**To:** Clayton Weber; Eddie R. Church; Steven Shull; 62811\_1706-168\_InnerLoopImprovements  
**Cc:** Shelley Butler  
**Subject:** Animal Shelter access roadway  
**Attachments:** CO #3, Animal Shelter added roadway.pdf

Clayton,

Please see the attached.

Thanks,

**Bill Bambrick**  
*Senior Project Manager*



General Contractor  
Construction Manager  
Excavation  
Concrete  
Utilities

P.O. Box 1057  
Round Rock, TX 78680  
Tel: (512) 244-0600  
Fax: (512) 244-6085  
www.chasco.com



# WILLIAMSON COUNTY, TEXAS

CHANGE ORDER NUMBER: 3

Project # 1706-168

TABLE B: Contract Items (Continued)

ITEM	DESCRIPTION	UNIT	UNIT PRICE	ORIGINAL + PREVIOUSLY REVISED		ADD or (DEDUCT)	NEW		OVERRUN/ UNDERRUN
				QUANTITY	ITEM COST	QUANTITY	QUANTITY	ITEM COST	
	Animal Shelter Driveway								
100-6002	PREPARING ROW	STA		4.85		4.85	4.85	\$1,600.00	\$7,760.00
104-6029	REMOVING CONC (CURB OR CURB AND GUTTER)	LF		0.00		181.00	215.00	\$8.00	\$1,720.00
110-6001	EXCAVATION (ROADWAY)	CY		0.00		270.00	270.00	\$8.00	\$2,160.00
110-6002	EXCAVATION (CHANNEL)	CY		0.00		23.00	23.00	\$18.00	\$414.00
132-6003	EMBANKMENT (FINAL)(ORD COM)(TY B)	CY		0.00		199.00	199.00	\$12.00	\$2,388.00
160-WC02	FURNISHING AND PLACING TOPSOIL (4")	SY		0.00		2766.00	2,766.00	\$1.50	\$4,149.00
164-WC05	SEEDING FOR EROSION CONTROL (PERM)(WARM)(TY 5)	SY		0.00		2766.00	2,766.00	\$0.25	\$691.50
166-6002	FERTILIZER	TON		0.00		0.02	0.02	\$820.00	\$16.40
168-WC01	VEGETATIVE WATERING	MG		0.00		83.00	83.00	\$28.00	\$2,324.00
169-6001	SOIL RETENTION BLANKET (CL 1)(TY A)	SY		0.00		1000.00	845.00	\$1.30	\$1,098.50
247-6044	FL BS (COMP IN PLC)(TY A GR 4)(FINAL POS)	CY		0.00		795.00	795.00	\$42.00	\$33,390.00
260-6009	LIME TRT (EXST MATL)(10")	SY		0.00		2329.00	2,329.00	\$11.26	\$26,224.54
260-6016	LIME (SLURRY)	TON		0.00		53.00	53.00	\$182.00	\$9,646.00
310-6001	PRIME COAT (MULTI OPTION)	GAL		0.00		263.00	263.00	\$4.20	\$1,104.60
316-6193	AGGR (TY D GR 5 SAC-B)	CY		0.00		9.00	9.00	\$100.00	\$900.00
316-6413	ASPH (AC-15P, HFRS-2P OR CRS-2P)	GAL		0.00		499.00	499.00	\$3.25	\$1,621.75
341-6008	D-GR HMA TY B PG 64-22	TON		0.00		302.00	302.00	\$68.00	\$20,536.00
341-6042	D-GR HMA TY D SAC B PG 70-22	TON		0.00		151.00	151.00	\$80.00	\$12,080.00
432-6024	RIP RAP (STONE COMMON)(DRY)(12IN)	CY		0.00		4.00	4.00	\$130.00	\$520.00
464-6026	RC PIPE (CL IV) (24 IN) <span style="color: blue;">ADDED ITEM</span>	LF		0.00		140.00	140.00	\$58.00	\$8,120.00
465-6126	INLET (COMPL)(PSL)(FG)(3FT X 3FT )	EA		0.00		1.00	1.00	\$2,900.00	\$2,900.00
467-6388	SET (TY II)(24IN)(RCP)(3:1)C	EA		0.00		1.00	1.00	\$1,400.00	\$1,400.00
502-6001	BARRICADES, SIGNS AND TRAFFIC HANDLING <span style="color: blue;">ADDED</span>	MO		0.00		2.00	2.00	\$3,000.00	\$6,000.00
506-6002	ROCK FILTER DAMS (INSTALL)(TY 2)	LF		0.00		5.00	5.00	\$20.00	\$100.00
506-6011	ROCK FILTER DAMS (REMOVE)	LF		0.00		5.00	5.00	\$10.00	\$50.00
506-6041	BIODEG EROSN CONT LOGS (INSTL)(12IN)	LF		0.00		540.00	540.00	\$5.00	\$2,700.00
506-6043	BIODEG EROSN CONT LOGS (REMOVE)	LF		0.00		540.00	540.00	\$0.30	\$162.00
529-6030	CONC CURB & GUTTER (VALLEY GUTTER)	LF		0.00		800.00	800.00	\$13.00	\$10,400.00
530-6004	DRIVEWAYS (CONC)	SY		0.00		650.00	650.00	\$98.00	\$63,700.00
666-6035	REFL PAV MRK TY I (W)8"(SLD)(090MIL)	LF		0.00		168.00	168.00	\$0.85	\$142.80
666-6047	REFL PAV MRK TY I (W)24"(SLD)(090MIL)	LF		0.00		51.00	51.00	\$4.80	\$244.80
666-6053	REFL PAV MRK TY I (W)(ARROW)(090MIL)	EA		0.00		4.00	4.00	\$85.00	\$340.00
666-6077	REFL PAV MRK TY I (W)(WORD)(090MIL)	EA		0.00		2.00	2.00	\$95.00	\$190.00
666-6178	REFL PAV MRK TY II(W)8"(SLD)	LF		0.00		168.00	168.00	\$0.30	\$50.40
666-6182	REFL PAV MRK TY II (W)24"(SLD)	LF		0.00		51.00	51.00	\$1.65	\$84.15
666-6184	REFL PAV MRK TY II (W)(ARROW)	EA		0.00		4.00	4.00	\$42.00	\$168.00
666-6192	REFL PAV MRK TY II (W)(WORD)	EA		0.00		2.00	2.00	\$50.00	\$100.00
666-6207	REFL PAV MRK TY II (Y)4"(SLD)	LF		0.00		944.00	944.00	\$0.15	\$141.60
666-6314	RE PM W/RET REQ TY I (Y)4"(SLD)(090MIL)	LF		0.00		944.00	944.00	\$0.35	\$330.40
672-6007	REFL PAV MRK TY I-C	EA		0.00		10.00	10.00	\$4.00	\$40.00
The "Totals" from Table B of the previous work sheet:									
TOTALS									\$226,108.44