

2007 Rutland Drive Austin, Texas 78758 United States			
Phone:	(512) 491-8773		
Fax:			www.safway.com
DATE 2/25/2019	JOB NAME Williamson County Historic Courthouse: District Courtroom		JOB NUMBER 616292
CUSTOMER STARCRAFT INTERIOR CONTRACTORS		JOB SITE CONTACT Bob Hopkins	
CONTACT		PERSON AUTHORIZED TO REQUEST CHANGE ORDERS	
ADDRESS AUSTIN JOBSITE PO BOX 7687 HOUSTON, Texas 77270 United States		JOB SITE ADDRESS 710 S Main St Georgetown, TX 78626	
PHONE 713-686-8464	FAX 713-686-8489	PHONE 713-817-4220	FAX _____
CONTRACT PRICE	\$2,450 + TAX	INCLUDING	4 WEEKS EQUIPMENT RENTAL
EXTENDED EQUIPMENT RENTAL	\$9.11	PER DAY	\$255 + TAX PER 28 DAYS
THIS QUOTATION IS VALID FOR 60 DAYS			
SPECIAL TERMS AND CONDITIONS AND DESCRIPTION OF WORK			

BrandSafway will provide, install, dismantle, and remove one scaffold at the Williamson County Historic Courthouse for Starcraft Interiors. The scaffold will be constructed on the 2nd floor to access a ceiling area. The scaffold will be 6ft. wide x 6ft. long x 21ft. high. The scaffold will be constructed of BrandSafway Systems and Tube & Clamp. The scaffold will be planked at the top level only. The scaffold will be complete with guardrails, gates, and toeboards. Contractor to provide clear area to mobilize and stage scaffold materials. ***Site Unseen*** Ladder access will be provided as required by OSHA. Constructed per Safway concept sketch. Proposal is subject scope of work, schedule, and scaffold design. **TAX NOT INCLUDED IN QUOTE PRICING.**

In the event of high winds, inclement weather, damage, alteration, add or revision. Safway will provide you a method of costing your scaffold service using what we call a combined rate/time & material. The rate is per worker, per hour, based on using OSHA trained scaffold erectors for routine scaffold construction and dismantling. Straight time rate will be \$35.00 and \$52.50 premium per worker, per hour. Straight time rates are in effect Monday thru Friday 7:00am to 3:30pm with 1/2 hour lunch break. Overtime/Premium rates will be in effect unless and alternative time frame is agreed upon in advance. Scaffolds will be built in an area that is free of debris, ready for scaffolds, and is capable of supporting the live and dead loads imposed upon the scaffold. All scaffolds will be built in accordance with OSHA subpart L requirements (CFR 1926.450, 1926.451, 1926.452, 1926.454). Upgrades from this standard may necessitate additional charges to the Customer. A Customer representative is requested to be on site to verify the material counts of all rental equipment delivered to and removed from the site. The counts are most easily taken upon arrival of the delivery trucks before the installation begins and after the dismantle is complete and the material is being loaded back on the return trucks. At the time of the dismantle and return, any shortages of equipment from the counts taken upon delivery are the Customer's responsibility and will be billed to the Customer at Safway list price. An inspection will be required upon the completion of the installation of the scaffold to ensure that all aspects of the scope of work outlined in this proposal have been provided. Once accepted by the customer, any call backs or changes to the scaffold will be