



## Work Order Signature Document

### ezIQC Buy Board Contract No.: 520-16 Area G - LMC

☐

New Work Order

☒

Modify an Existing Work Order

Work Order Number.: 072853.01

Work Order Date: 05/07/2020

Work Order Title: Williamson County - Medic 11 EMS Bay Addition\_Supplemental 1

Owner Name: County of Williamson

Contractor Name: LMC Corporation

Contact: Tom Stanfield

Contact: Zring Kareem

Phone: 512-818-4180

Phone: 210-643-9392

### Work to be Performed

Work to be performed as per the Final Detailed Scope of Work Attached and as per the terms and conditions of ezIQC Buy Board Contract No 520-16 Area G - LMC.

Brief Work Order Description:

Medic 11 EMS Bay Addition: Fire Lane.

### Time of Performance

Estimated Start Date:

Estimated Completion Date:

### Liquidated Damages

Will apply: ☐

Will not apply: ☒

### Work Order Firm Fixed Price: \$13,811.32

Owner Purchase Order Number:

### Approvals

Owner

Date

*Zring Kareem*  
Contractor

5/11/2020

Date

## Detailed Scope of Work

---

**To:** Zring Kareem  
LMC Corporation  
9191 Winkler Drive, Suite A  
Houston, TX 77017-5967  
210-643-9392

**From:** Tom Stanfield  
County of Williamson  
301 SE Inner Loop  
Georgetown, TX 78626  
512-818-4180

**Date Printed:** May 07, 2020

**Work Order Number:** 072853.01

**Work Order Title:** Williamson County - Medic 11 EMS Bay Addition\_Supplemental 1

**Brief Scope:** Medic 11 EMS Bay Addition: Fire Lane.

---

☐ Preliminary

☐ Revised

☒ Final

---

The following items detail the scope of work as discussed at the site. All requirements necessary to accomplish the items set forth below shall be considered part of this scope of work.

1. Concrete Apron: excavation, fill, compact and pour concrete in area. Not to exceed 1,022.23 Sf.
2. Concrete Fire Lane: excavation, fill, compact and pour concrete in area. Not to exceed 635.37 SF
3. Credit for Asphalt removed from scope.
4. Credit for concrete area removed from scope.

**Note:**

- Any changes to square footage will be priced in a supplemental work order.
- Extend contract 30 calendar days to if approved.

Subject to the terms and conditions of JOC Contract **520-16 Area G - LMC**.

Zring Kareem  
Contractor

5/11/2020  
Date

\_\_\_\_\_  
Owner

\_\_\_\_\_  
Date

# Contractor's Price Proposal - Summary

|       |                        |  |
|-------|------------------------|--|
| Date: | May 07, 2020           |  |
| Re:   | IQC Master Contract #: | 520-16 Area G - LMC  |
|       | Work Order #:          | 072853.01  |
|       | Owner PO #:            |  |
|       | Title:                 | Williamson County - Medic 11 EMS Bay Addition_Supplemental 1 |
|       | Contractor:            | LMC Corporation  |
|       | Proposal Value:        | \$13,811.32  |

|                |              |
|----------------|--------------|
| Credit Back    | - \$4,484.90 |
| Entry Apron    | \$10,887.60  |
| Fire Lane      | \$7,408.62   |
| Proposal Total | \$13,811.32  |

This total represents the correct total for the proposal. Any discrepancy between line totals, sub-totals and the proposal total is due to rounding.

The Percentage of NPP on this Proposal: %

## Contractor's Price Proposal - Detail

Date: May 07, 2020

Re: IQC Master Contract #: 520-16 Area G - LMC  
 Work Order #: 072853.01  
 Owner PO #:  
 Title: Williamson County - Medic 11 EMS Bay Addition\_Supplemental 1  
 Contractor: LMC Corporation  
 Proposal Value: \$13,811.32

| Sect.                           | Item                  | Mod.     | UOM          | Description   | Line Total         |
|---------------------------------|-----------------------|----------|--------------|---|--------------------|
| Labor                           | Equip.                | Material | (Excludes)   |   |                    |
| <b>Credit Back</b>              |                       |          |              |   |                    |
| 1                               | 03 31 13 00 0036      |          | CY           | >6", By Direct Chute, Place 3,000 PSI Concrete Slab On Grade  | -\$959.60          |
|                                 |                       |          | Installation | Quantity -6.00 x Unit Price 126.13 x Factor 1.2680 = Total -959.60  |                    |
| 2                               | 03 31 13 00 0036 0029 |          | MOD          | For 3,500 PSI Concrete, Add   | -\$43.90           |
|                                 |                       |          | Installation | Quantity -6.00 x Unit Price 5.77 x Factor 1.2680 = Total -43.90   |                    |
| 3                               | 03 35 16 00 0005      |          | SF           | Concrete Floor Finishes, Final Float  | -\$459.12          |
|                                 |                       |          | Installation | Quantity -496.00 x Unit Price 0.73 x Factor 1.2680 = Total -459.12  |                    |
| 4                               | 32 12 13 13 0002      |          | SY           | Tack Coat, 0.05 Gallon/SY   | -\$64.67           |
|                                 |                       |          | Installation | Quantity -150.00 x Unit Price 0.34 x Factor 1.2680 = Total -64.67   |                    |
| 5                               | 32 12 13 19 0002      |          | SY           | Surface Prime Coat, 0.28 Gallon/SY  | -\$180.69          |
|                                 |                       |          | Installation | Quantity -150.00 x Unit Price 0.95 x Factor 1.2680 = Total -180.69  |                    |
| 6                               | 32 12 16 13 0018      |          | SY           | 3" Thick Surface CourseIncludes placement, rolling, finishing and sweeping.   | -\$2,776.92        |
|                                 |                       |          | Installation | Quantity -150.00 x Unit Price 14.60 x Factor 1.2680 = Total -2,776.92   |                    |
| <b>Subtotal for Credit Back</b> |                       |          |              |   | <b>-\$4,484.90</b> |
| <b>Entry Apron</b>              |                       |          |              |   |                    |
| 7                               | 01 22 23 00 0258      |          | DAY          | 2,400 LB Capacity, 72" Wide, Skid-Steer Loader (Bobcat) With Full-Time Operator   | \$2,377.80         |
|                                 |                       |          | Installation | Quantity 3.00 x Unit Price 625.08 x Factor 1.2680 = Total 2,377.80  |                    |
| 8                               | 01 71 13 00 0003      |          | EA           | Equipment Delivery, Pickup, Mobilization And Demobilization Using A Tractor Trailer With Up To 53' BedIncludes delivery of equipment, off loading on site, rigging, dismantling, loading and transporting away. For equipment such as bulldozers, motor scrapers, hydraulic excavators, gradalls, road graders, loader-backhoes, heavy duty construction loaders, tractors, pavers, rollers, bridge finishers, straight mast construction forklifts, telescoping boom rough terrain construction forklifts, telescoping and articulating boom manlifts with >40' boom lengths, etc. | \$380.40           |
|                                 |                       |          | Installation | Quantity 1.00 x Unit Price 300.00 x Factor 1.2680 = Total 380.40  |                    |
| 9                               | 03 21 16 00 0006      |          | LF           | #3, Grade 50, Beams And Girders, Epoxy Coated Steel Reinforcement Bar   | \$1,389.22         |
|                                 |                       |          | Installation | Quantity 2,739.00 x Unit Price 0.40 x Factor 1.2680 = Total 1,389.22  |                    |
| 10                              | 03 31 13 00 0005      |          | SF           | 6" 3,000 PSI Slab On Grade Concrete Slabs Assembly  | \$6,740.18         |
|                                 |                       |          | Installation | Quantity 1,022.23 x Unit Price 5.20 x Factor 1.2680 = Total 6,740.18  |                    |

## Contractor's Price Proposal - Detail Continues..

Work Order Number: 072853.01

Work Order Title: Williamson County - Medic 11 EMS Bay Addition\_Supplemental 1

---

|                                 |                    |
|---------------------------------|--------------------|
| <b>Subtotal for Entry Apron</b> | <b>\$10,887.60</b> |
|---------------------------------|--------------------|

---

### Fire Lane

|    |                  |              |   |            |        |        |       |          |            |
|----|------------------|--------------|---|------------|--------|--------|-------|----------|------------|
| 11 | 01 22 23 00 0258 | DAY          | 2,400 LB Capacity, 72" Wide, Skid-Steer Loader (Bobcat) With Full-Time Operator   |            |        |        |       |          | \$2,377.80 |
|    |                  | Installation | Quantity  | Unit Price | Factor | =      | Total |          |            |
|    |                  |              | 3.00  | 625.08     | x      | 1.2680 | =     | 2,377.80 |            |
| 12 | 01 71 13 00 0003 | EA           | Equipment Delivery, Pickup, Mobilization And Demobilization Using A Tractor Trailer With Up To 53' BedIncludes delivery of equipment, off loading on site, rigging, dismantling, loading and transporting away. For equipment such as bulldozers, motor scrapers, hydraulic excavators, gradalls, road graders, loader-backhoes, heavy duty construction loaders, tractors, pavers, rollers, bridge finishers, straight mast construction forklifts, telescoping boom rough terrain construction forklifts, telescoping and articulating boom manlifts with >40' boom lengths, etc. |            |        |        |       |          | \$380.40   |
|    |                  | Installation | Quantity  | Unit Price | Factor | =      | Total |          |            |
|    |                  |              | 1.00  | 300.00     | x      | 1.2680 | =     | 380.40   |            |
| 13 | 03 21 16 00 0006 | LF           | #3, Grade 50, Beams And Girders, Epoxy Coated Steel Reinforcement Bar   |            |        |        |       |          | \$461.04   |
|    |                  | Installation | Quantity  | Unit Price | Factor | =      | Total |          |            |
|    |                  |              | 909.00  | 0.40       | x      | 1.2680 | =     | 461.04   |            |
| 14 | 03 31 13 00 0005 | SF           | 6" 3,000 PSI Slab On Grade Concrete Slabs Assembly  |            |        |        |       |          | \$4,189.38 |
|    |                  | Installation | Quantity  | Unit Price | Factor | =      | Total |          |            |
|    |                  |              | 635.37  | 5.20       | x      | 1.2680 | =     | 4,189.38 |            |

---

|                               |                   |
|-------------------------------|-------------------|
| <b>Subtotal for Fire Lane</b> | <b>\$7,408.62</b> |
|-------------------------------|-------------------|

---

---

|                       |                    |
|-----------------------|--------------------|
| <b>Proposal Total</b> | <b>\$13,811.32</b> |
|-----------------------|--------------------|

---

This total represents the correct total for the proposal. Any discrepancy between line totals, sub-totals and the proposal total is due to rounding.

The Percentage of NPP on this Proposal: %

## Subcontractor Listing

**Date:** May 07, 2020

**Re:** IQC Master Contract #: 520-16 Area G - LMC  
Work Order #: 072853.01  
Owner PO #:  
Title: Williamson County - Medic 11 EMS Bay Addition\_Supplemental 1  
Contractor: LMC Corporation  
Proposal Value: \$13,811.32

| Name of Contractor                                       | Duties | Amount | %    |
|--|--------|--------|------|
| No Subcontractors have been selected for this Work Order |        | \$0.00 | 0.00 |