

Road and Bridge Training RM

3101 SE Inner Loop
Georgetown TX 78626

Data Release : Year 2020 Quarter 1

Unit Cost Estimate

Quantity	LineNumber	Line Source	Description	Unit	O&P	Ext. Total	Type	Labor	Data Release	CCI Location
4	013113200260		Field personnel, superintendent, average	Week	\$	14,900.00	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1200	019313031040		Sealing concrete floor, oil or urethane base, spray, 1 coat	S.F.	\$	204.00	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
60	024113175200		Demolish, remove pavement & curb, remove concrete, mesh reinforced, to 6" thick, hydraulic hammer, excludes hauling and disposal fees	S.Y.	\$	932.40	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
870	028713330450		Demolition in mold contaminated area, partitions, non load bearing, gypsum board & studs	S.F.	\$	2,409.90	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	050505100240		Selective metals demolition, structural framing members, 1/4-2 tons, remove whole or cut up into smaller pieces, incl loading, excl shoring, bracing, cutting, hauling, dumping	Ea.	\$	111.36	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	054113050160		Bracing strap, shear wall X-bracing for LB studs, galvanized steel, one face, per 10' x 10' bay, 18 ga x 4" W	Ea.	\$	90.17	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
25	054113050430		Bracing strap, continuous horizontal row, for LB studs, galvanized steel, both faces, studs 16" OC, 20 ga x 2" W	C.L.F.	\$	2,918.50	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
100	054113100210		Bridging, solid, length of load bearing track between load bearing studs, per stud bay, 18 ga x 3-5/8" W x 12" L, incl bent tabs at ends	Ea.	\$	498.00	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
870	072116200820		Blanket insulation, for walls or ceilings, unfaced fiberglass, 3-1/2" thick, R13, 15" wide	S.F.	\$	626.40	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
320	074213300900		Steel siding, colored, corrugated or ribbed, on steel frame, 10 year finish, 26 gauge, incl. fasteners	S.F.	\$	1,340.80	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
920	079219100030		Joint sealants, caulking and sealants, acoustical sealants, elastomeric, cartridges, 1/4" x 1/2", in place	L.F.	\$	2,125.20	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
62	080505102201		Door demolition, door frames, wood, remove, alternate pricing method per LF	L.F.	\$	104.78	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	081213130040		Frames, steel, knock down, hollow metal, double, 16 ga., up to 5-3/4" deep, 6'-8" h x 6'-0" w	Ea.	\$	330.34	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	081213259000		Door frames, minimum labor/equipment charge	Job	\$	409.50	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	087120151000		Door hardware, apartment, interior	Door	\$	715.40	RR		Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)

920	090505100200		Ceiling demolition, gypsum wall board, furred and nailed, remove	S.F.	\$ 662.40	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
920	092116335200		Partition wall, interior, water resistant, taped both sides, installed on & incl. 25 ga, NLB metal studs, 3-5/8" wide, 16" OC, 8' to 12' high, 5/8" gypsum drywall	S.F.	\$ 3,183.20	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
100	096513130700		Wall base, vinyl, straight or cove, standard colors, 4" high, 1/8" thick	L.F.	\$ 248.00	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1956	099123741240		Paints & coatings, walls & ceilings, interior, concrete, drywall or plaster, zero voc latex, 3 coats, smooth finish, roller	S.F.	\$ 1,212.72	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	099123749900		Paints & coatings, walls & ceilings, interior, zero voc latex, minimum labor/equipment charge	Job	\$ 124.64	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
5	210523509990		Water-based fire suppression piping, minimum labor/equipment charge	Job	\$ 790.85	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
200	260505100100		Conduit, rigid galvanized steel, 1/2" to 1" diameter, electrical demolition, remove conduit to 10' high, including fittings & hangers	L.F.	\$ 356.00	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
200	260505100280		Armored cable, (BX), #14, 2 wire, average 50' runs, electrical demolition, remove	L.F.	\$ 124.00	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
158	260505100290		Armored cable, (BX), #14, 3 wire, average 50' runs, electrical demolition, remove	L.F.	\$ 120.08	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
6	260505101720		Junction boxes, 4" square & octagon, electrical demolition, remove, including removal of supports and terminations	Ea.	\$ 32.46	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
21	260505101830		Wire, THW-THWN-THHN, #14, electrical demolition, removed from in place conduit, to 10' high	C.L.F.	\$ 139.44	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
20	260505101840		Wire, THW-THWN-THHN, #12, electrical demolition, removed from in place conduit, to 10' high	C.L.F.	\$ 157.40	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
4	260505102120		Fluorescent fixtures, interior, 2 lamp, 2' x 4', electrical demolition, remove, recessed drop-in, to 10' high, including supports & whips	Ea.	\$ 105.24	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	260505109000		Electrical demolition, minimum labor/equipment charge	Job	\$ 108.11	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
23	260519900100		Wire, copper, stranded, 600 volt, #12, type THW, normal installation conditions in wireway, conduit, cable tray	C.L.F.	\$ 1,258.33	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
23	260519900120		Wire, copper, stranded, 600 volt, #10, type THW, normal installation conditions in wireway, conduit, cable tray	C.L.F.	\$ 1,559.17	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
160	260533131750		Rigid galvanized steel conduit, 1/2" diameter, to 10' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	L.F.	\$ 1,267.20	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
18	260533131991		Rigid galvanized steel conduit, field bends, 45 Deg. to 90 Deg., 1/2" diameter	Ea.	\$ 176.58	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
16	260533132000		Rigid galvanized steel conduit elbows, 1/2" diameter, to 10' high	Ea.	\$ 284.96	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)

16	260533132250		Rigid galvanized steel conduit couplings, 1/2" diameter, to 10' high	Ea.	\$ 44.64	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	260533139990		Conduit, to 10' high, minimum labor/equipment charge	Job	\$ 108.11	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
20	260533160170		Outlet boxes, pressed steel, for Romex or BX, with bracket, 4" square	Ea.	\$ 639.80	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
22	260533251130		Conduit fittings for rigid galvanized steel, bushings, plastic, 1/2" diameter	Ea.	\$ 240.02	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
22	260533251630		Conduit fittings for rigid galvanized steel, sealing locknuts, 1/2" diameter	Ea.	\$ 280.72	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
22	260533251760		Conduit fittings for rigid galvanized steel, grounding bushing, insulated, 1/2" diameter	Ea.	\$ 417.56	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	262726209000		Wiring devices, minimum labor/equipment charge	Job	\$ 108.11	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
6	265113500600		Fluorescent fixture, interior, acrylic lens, grid recess ceiling mounted, 4-40 W, 2' W x 4' L, incl lamps, mounting hardware and connections	Ea.	\$ 989.22	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
1	265113509000		Interior lighting fixtures, minimum labor/equip charge	Job	\$ 144.14	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)
8	270505200220		Voice/data outlet, electrical demolition, remove	Ea.	\$ 24.72	RR	Year 2020 Quarter 1	TEXAS / AUSTIN (786-787)

Summary of Base Cost:

RS Means Total "O&P":	\$ 42,624.57
Contractor Coefficient:	\$ 0.98
Subtotal:	\$ 41,772.08
Non Pre-Priced Item:	\$ -
Bond Cost:	\$ 1,044.00
Total Base Cost:	\$ 42,816.08