Received

WILLIAMSON COUNTY, TEXAS CHANGE ORDER NUMBER: 4

JUL 17 2020

HNTB Corporation 1. CONTRACTOR: Joe Bland Construction Project: CR 176 at RM 2. Change Order Work Limits: Sta. 100+26 to Sta. 139+81 Roadway: 2243 3. Type of Change(on federal-aid non-exempt projects): Minor (Major/Minor) CSJ Number: 4. Reasons: 3F (3 Max. - In order of importance - Primary first) 5. Describe the work being revised: 3F: County Convenience. Additional work desired by the County. This Change Order adds a Shared Use Path to (SUP) the project at the request of the County. The path extends from RM 2243 (Leander Road) to CR 176, located along the west right of way. The SUP required a pedestrian crossing at Parkside Parkway on the south end of the project. 6. Work to be performed in accordance with Items: See Attached. 7. New or revised plan sheet(s) are attached and numbered: PED 1-7 8. New Special Provisions/Specifications to the contract are attached: Yes No 9. New Special Provisions to Item N/A No. N/A, Special Specification Item N/A are attached. Each signatory hereby warrants that each has the authority to execute this Change Order (CO). The following information must be provided The contractor must sign the Change Order and, by doing so, agrees to waive any and all claims for additional compensation due to any and all other expenses; additional changes for time, overhead and profit; or loss of Time Ext. #: 1 Days added on this CO: compensation as a result of this change. Amount added by this change order: \$452,885.58 Date 7-17-20 THE CONTRACTOR Typed/Printed Name Typed/Printed Title RECOMMENDED FOR EXECUTION: County Commissioner Precinct 1 **APPROVED** REQUEST APPROVAL Project Manager County Commissioner Precinct 2 Date N/A **APPROVED** П REQUEST APPROVAL Design Engineer Date County Commissioner Precinct 3 Date 07/21/2020 **APPROVED** REQUEST APPROVAL Program Manager Date Design Engineer's Seal: County Commissioner Precinct 4 Date

APPROVED

П

REQUEST APPROVAL

see attached plan sheets

WILLIAMSON COUNTY, TEXAS

CHANGE ORDER NUMBER: _	4	Project#_	1901-285
------------------------	---	-----------	----------

TABLE A: Force Account Work and Materials Placed into Stock

LABOR	HOURLY RATE		HOURLY RATE	

TABLE B: Contract Items:

			ORIGINAL + PRE	/IOUSLY REVISED	ADD or (DEDUCT)		NEW		
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	ITEM COST	QUANTITY	QUANTITY	ITEM COST	OVERRUN/ UNDERRUN
432-6005	RIPRAP (CONC)(CL A)	CY	\$569.00	0.00	\$0.00	750.00	750.00	\$426,750.00	\$426,750.00
464-6005	RCPIPE (CL III)(24IN)	LF	\$70.00	0.00	\$0.00	78.00	78.00	\$5,460.00	\$5,460.00
467-6376	SET (TY II)(24IN)(RCP)(3:1)(P)	EA	\$1,778.00	0.00	\$0.00	8.00	8.00	\$14,224.00	\$14,224.00
502-WC01	BARRICADES, SIGNS AND TRAFFIC HANDLING (FOR SUP)	MO	\$975.79	0.00	\$0.00	2.00	2.00	\$1,951.58	\$1,951.58
532-6004	CURB RAMPS (TY I)	EA	\$1,500.00	0.00	\$0.00	3.00	3.00	\$4,500.00	\$4,500.00
	TOTALS		\$0.00			\$452,885.58	\$452,885.58		

CHANGE ORDER REASON(S) CODE CHART

Design Error or Omission	1A. Incorrect PS&E
, v	1B. Other
Differing Site Conditions	2A. Dispute resolution (expense caused by conditions and/or resulting delay)
(unforeseeable)	2B. Unavailable material
	2C. New development (conditions changing after PS&E completed)
	2D. Environmental remediation
	2E. Miscellaneous difference in site conditions (unforeseeable)(Item 9)
	2F. Site conditions altered by an act of nature
	2G. Unadjusted utility (unforeseeable)
	2H. Unacquired Right-of-Way (unforeseeable)
	2I. Additional safety needs (unforeseeable)
	2J. Other
3. County Convenience	3A. Dispute resolution (not resulting from error in plans or differing site conditions)
	3B. Public relations improvement
	3C. Implementation of a Value Engineering finding
	3D. Achievement of an early project completion
	3E. Reduction of future maintenance
	3F. Additional work desired by the County
	3G. Compliance requirements of new laws and/or policies
	3H. Cost savings opportunity discovered during construction
	3I. Implementation of improved technology or better process
	3J. Price adjustment on finished work (price reduced in exchange for acceptance)
	3K. Addition of stock account or material supplied by state provision
	3L. Revising safety work/measures desired by the County
	3M. Other
Third Party Accommodation	4A. Failure of a third party to meet commitment
	4B. Third party requested work
	4C. Compliance requirements of new laws and/or policies (impacting third party)
	4D. Other
5 Contractor Convenience	5A. Contractor evereigns ention to change the traffic central plan
Contractor Convenience	5A. Contractor exercises option to change the traffic control plan
	5B. Contractor requested change in the sequence and/or method of work
	5C. Payment for Partnering workshop
	5D. Additional safety work/measures desired by the contractor
	5E. Other
6. Untimely ROW/Utilities	6A. Right-of-Way not clear (third party responsibility for ROW)
,	6B. Right-of-Way not clear (County responsibility for ROW)
	6C. Utilities not clear
	6D. Other
	OD. Other

Williamson County Road Bond Program

CR 176 at RM 2243 Williamson County Project No. 1902-285 Change Order No. 4

Reason for Change

This Change Order adds a Shared Use Path (SUP) to the project at the request of the County. The path extends from RM 2243 (Leander Road) to CR 176, along the west right of way. The SUP required a pedestrian crossing at Parkside Parkway on the south end of the project.

The following is a list of new items required for this Change Order.

ITEM	DESCRIPTION	QTY	UNIT
432-6005	RIPRAP (CONC) (CL A)	750.00	CY
464-6005	RCPIPE (CL III) (24IN)	78.00	LF
467-6376	SET (TY II) (24IN) (RCP) (3:1) (P)	8.00	EA
502-WC01	BARRICADES, SIGN, AND TRAFIC HANDLING (FOR SUP)	2.00	МО
532-6004	CURB RAMPS (TY I)	3.00	EA

This Change Order results in an increase of \$452,885.58 to the Contract amount, for an adjusted Contract total of \$2,968,233.13. The original Contract amount was \$2,447,560.00. As a result of this Change Order, \$520,673.13 has been added to the Contract, resulting in an 21.27% increase in the Contract cost. Sixty (60) additional days will be added to the Contract as a result of this Change Order.

HNTB Corporation

James Klotz, P.E.



JOE BLAND CONSTRUCTION, L.P.

13111 DESSAU ROAD

AUSTIN, TX 78754

Contact: Andrew Batten
Phone: 512-579-9221

Fax:

Quote To:HNTBJob Name:CR 176 Shared Use PathDate of Plans:

Phone: Revision Date: Fax:

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
10	RIPRAP (CL A)	750.00	CY	569.00	426,750.00
20	RC PIPE (CL III)(24 IN)	78.00	LF	70.00	5,460.00
30	SET (TY II)(24 IN)(RCP)(3:1)(P)	8.00	EA	1,778.00	14,224.00
40	CURB RAMPS (TY 1)	3.00	EA	1,500.00	4,500.00

GRAND TOTAL \$450,934.00





Flasher Equipment Co. 5827 W. US Hwy. 90

San Antonio, TX 78227

210-736-4251 Fax 210-736-2084

INVOICE

Invoice Date	Invoice No.
4/30/2020	00335470

Terms: Net 10 Days

Joe Bland Construction, L.P.

Ellen Edmondson 13111 Dessau Road Austin, Texas 78754

Sub in eCMS - 843

Item 1: \$850.00

Job ID: 250536

Cr 176

CR 176;; Deer Draw;; RM 2243

Georgetown

Project#: CR 176

Highway:

County:

Customer	er Customer Job No. Customer P.O. No. Period Covered		ed	Fore	eman Name / Ph	one#		
JOEBLACO	CR 176	4/1/2020	- 4/30/2	2020	Andrew Batten			
Date	Descr	iption	From - To	Qty	Days	Units	Price	Total
	RENT	ALS						
04/30/20	MONTHLY CONTRACT	04/01 04/30	1	30	1	850.00	\$850.0	
04/01/20	42" CHANNELIZER		04/01 04/30	56	30	1,680	0.00	\$0.0
04/01/20	30LB CHANNELIZER BASE		04/01 04/30	56	30	1,680	0.00	\$0.0
04/01/20	8 FT TY III PLASTIC BARRIO	CADE	04/01 04/28	24	28	672	0.00	\$0.0
04/29/20	8 FT TY III PLASTIC BARRIO	CADE	04/29 04/30	12	2	24	0.00	\$0.0
04/01/20	METAL BASE FOR TYPE III	BARRICADE	04/01 04/28	48	28	1,344	0.00	\$0.0
04/29/20	METAL BASE FOR TYPE III	BARRICADE	04/29 04/30	24	2	48	0.00	\$0.0
04/01/20	PLASTIC TRAFFIC BARREL	04/01 04/28	6	28	168	0.00	\$0.0	
04/01/20	TIRE RING FOR BARREL	04/01 04/28	6	28	168	0.00	\$0.0	
04/01/20	18 X 36 CORO DGFO BLAC	04/01 04/30	3	30	90	0.00	\$0.0	
04/01/20	18 X 36 CORO WHITE BLAC	CK - When Workers Are Pre	04/01 04/30	5	30	150	0.00	\$0.0
04/01/20	24X30 CORO DGFO BKV - N	/4-9L Detour Left	04/01 04/28	2	28	56	0.00	\$0.0
04/01/20	24X30 CORO DGFO BKV - N	//4-9R Detour Right	04/01 04/28	2	28	56	0.00	\$0.0
04/01/20	24 X 48 CORO DGFO BLAC	K - Begin Road Work Next _	04/01 04/30	5	30	150	0.00	\$0.0
04/01/20	24 X 48 CORO DGFO BLACI	K - End Road Work	04/01 04/30	5	30	150	0.00	\$0.0
04/01/20	24 X 48 CORO DGFO BLAC	K - End Work Zone	04/01 04/30	5	30	150	0.00	\$0.0
04/01/20	30X36 CORO DGFO BKV - E	Begin Work Zone	04/01 04/30	5	30	150	0.00	\$0.0
04/01/20	30X36 CORO DGFO BKV - N	//4-9AL DETOUR W/90 DE	04/01 04/28	1	28	28	0.00	\$0.0
04/01/20	30X36 CORO DGFO BKV - N	14-9AR DETOUR W/90 DE	04/01 04/28	1	28	28	0.00	\$0.0
04/01/20	30 X 48 CORO WHITE BLAC	04/01 04/30	5	30	150	0.00	\$0.0	
04/01/20	30 X 48 CORO WHITE BLAC	04/01 04/28	5	28	140	0.00	\$0.0	
04/01/20	30 X 60 CORO WHITE BLAC	K - Road Closed Mile A	04/01 04/28	2	28	56	0.00	\$0.0
04/01/20	36 X 36 CORO DGFO BLAC	K - DETOUR 1500 FT	04/01 04/28	2	28	56	0.00	\$0.0
04/01/20	36 X 36 CORO DGFO BLAC	K - No Center Line	04/01 04/30	2	30	60	0.00	\$0.0

Customer: Joe Bland Construction, L.P. - Job ID: 250536 - Invoice#: 00335470 - Invoice Date: 4/30/2020 (cont.)

Date	Description	From - To	Qty	Days	Units	Price	Total
	RENTALS					t t	
04/01/20	36 X 36 CORO DGFO BLACK - Road Work Ahead	04/01 04/30	3	30	90	0.00	\$0.00
04/01/20	36 X 36 CORO WHITE BLACK - Traffic Fines Double	04/01 04/30	6	30	180	0.00	\$0.00
04/01/20	42 X 48 CORO WHITE BLACK - Obey Warning Sign	04/01 04/30	5	30	150	0.00	\$0.00
04/01/20	48 X 48 CORO DGFO BLACK - Road Work Ahead	04/01 04/30	5	30	150	0.00	\$0.00
04/01/20	48X48 ALUM YLP BKV - Stay Alert Talk Or Text Later	04/01 04/30	5	30	150	0.00	\$0.00
04/01/20	SANDBAG	04/01 04/30	360	30	10,800	0.00	\$0.00
04/01/20	TELE 10 FT SQ POST BREAK AWAY 1 INCH	04/01 04/30	33	30	990	0.00	\$0.00
04/01/20	TELE 12 FT SQ POST BREAK AWAY 1 INCH	04/01 04/30	40	30	1,200	0.00	\$0.00
04/01/20	TELE 14 FT SQ POST BREAK AWAY 1 INCH	04/01 04/30	10	30	300	0.00	\$0.00
04/01/20	TELE 4ft upright with 5ft square foot welded	04/01 04/30	33	30	990	0.00	\$0.00
04/01/20	8 IN UPRIGHT FOR T-LEG	04/01 04/30	50	30	1,500	0.00	\$0.00
04/01/20	TELE 6in round to 3ft sq adjustable foot for sign	04/01 04/30	58	30	1,740	0.00	\$0.00
04/01/20	TELE 1.75 x 38inch 14 ga Crossbrace	04/01 04/30	28	30	840	0.00	\$0.00
04/01/20	52 IN X BRACE SET	04/01 04/30	50	30	1,500	0.00	\$0.00
		1					

EQUIPMENT RENTAL TOTAL	\$850.00
ONE-TIME CHARGES	\$0.00
SALES TAX	\$70.12
TOTAL CHARGES	\$920.12
PLEASE PAY THIS AMOUNT	\$920.12
*** Job Not Complete ***	

	SHARED USE PATH QUANTITIES SUMMARY													
	ITEM 432	ITEM 464	ITEM 467	ITEM 532		ITEM 100	ITEM 110	ITEM 132	ITEM 247		160	164	ITEM 166	168
	6005	6005	6376	6004	SUBSIDIARY	WC01	6001	6005	WC01	FOR	WC02	WC05	6002	WC001
SUP SHEET NO.	RIPRAP (CL A)	RC PIPE (CL III) (24 IN)	SET (TY II) (24 IN)(RCP) (3:1)(P)	CURB RAMPS (TY 1)	ТО	PREPARING ROW	EXCAVATION (RDWY)	EMBANKMENT (FINAL) (ORD COMP) (TY C)	FL BS (CMP IN PLACE) (8")	INFORMATION PURPOSED ONLY >	FURNISHING & PLACING TOPSOIL (4")	EROSION	FERTILIZER	VEGETATIVE WATERING
	CY	LF	EA	EA		LS	CY	CY	CY		SY	SY	TON	MG
1 OF 2	307	54	6	1		0.5	635	107	198		1670	1670	0.3	81.7
2 OF 2	310	24	2	2		0.5	437	181	184		1823	1823	0.3	85.7
TOTAL	617	78	8	3		1.0	1072	288	382		3493	3493	0.6	167.4






WILLIAMSON COUNTY PRECINCT #3



CR 176 AT RM 2243 SHARED USE PATH SUMMARY OF QUANTITIES

> SHEET 1 OF 1 SHEET PED1

FED. RD. DIV. NO. STATE PROJECT NO. 2103-01-033 STATE DIST. COUNTY TEXAS AUS WILLIAMSON CONT. SECT. JOB 2103 01 033 HIGHWAY NO. CR 176



DANIEL A. ROGERS

88794

S. CENSE

SONAL ENGL

1/10/2020





WILLIAMSON COUNTY PRECINCT #3



CR 176 AT RM 2243 SHARED USE PATH TYPICAL SECTIONS

DIV. NO.	STA	SHEET						
6	21	PED2						
STATE	DIST.	COUNTY						
TEXAS	AUS	WILLIAMSON						
CONT.	SECT.	JOB HIGHWAY NO.						
2103	01	033 CR 176						

N. T. S.

HORZONTAL ALIGNMENT DATA (PED1)

HORZONTAL ALIGNMENT DATA (PED1) (CONT.)

1 DESCRIBE CHAIN PED1					
Chain PED1 contains: PED04 CUR PED11 CUR PED12 CUR PED13 CUR PED14 CUR PED15 CUR PED16 PED05 PED06 PED07					
Beginning chain PED1 description					
Point PED04 N 10,191,031.9156 E 3,102,256.3147 Sta 9+00.00					
Course from PED04 to PC PED11 S 10° 21' 39.67" E Dist 126.0000					
Curve Data **					
Curve PEDI1 P.I. Station 10+30.99 N 10,190,903.0599 E 3,102,279.8735 Delta = 0° 35′ 05.51" (RT) Degree = 5° 51′ 30.47" Tangent = 4.9916 Length = 9.9832 Radius = 978.0000 External = 0.0127 Long Chord = 9.9832					
Mid. Ord. = 0.0127 P.C. Station 10+26.00 N 10,190,907.9702 E 3,102,278.9758 P.T. Station 10+35.98 N 10,190,898.1407 E 3,102,280.7211 C.C. N 10,190,732.0769 E 3,101,316.9230 Back = S 10° 21′ 39.67" E Ahead = S 9° 46′ 34.17" E Chord Bear = S 10° 04′ 06.92" E					
Curve Da†a **					
Curve PED12 P.I. Station 10+53.10 N 10,190,881.2741 E 3,102,283.6273 Delta = 64° 44′ 27.61" (LT) Degree = 212° 12′ 23.76" Tangent = 17.1152					
Length = 30.5085 Radius = 27.0000 External = 4.9677 Long Chord = 28.9112 Mid. Ord. = 4.1957 P.C. Station 10.35.98 N 10,190,898.1407 E 3,102,280.7211 P.T. Station 10.66.49 N 10,190,876.7051 E 3,102,300.1214 C.C. N 10,190,902.7253 E 3,102,307.3290 Back = S 9° 46′ 34.17" E Ahead = S 74° 31′ 01.77" E					
Chord Bear = S 42° 08′ 47.97" E					
Curve Da†a **					
Curve PEDI3 P.I. Station					
Long Chord = 74.3265 Mid. Ord. = 25.2050 P.C. Station 10+66.49 N 10,190,876.7051 E 3,102,300.1214 P.T. Station 11+61.85 N 10,190,802.8169 E 3,102,308.1809 C.C. N 10,190,838.1567 E 3,102,289.4434					
Back = S 74° 31′ 01.77" E Ahead = S 62° 04′ 01.38" W Chord Bear = S 6° 13′ 30.19" E					
Curve Data **					
Curve PED14 P.I. Station					
Long Chord = 28.9112 Mid. Ord. = 4.1957 P.C. Station 11:61.85 N 10,190,802.8169 E 3,102,308.1809 P.T. Station 11:92.35 N 10,190,777.7029 E 3,102,293.8581 C.C. N 10,190,778.9625 E 3,102,320.8287 Back = S 62° 04′ 01.38" W Ahead = S 2° 40′ 26.22" E Chord Bear = S 29° 41′ 47.58" W					

Curve Data **				
Curve PED15 P.I. Station	3, 102, 310. 4986			
Radius = 978.0000 External = 63.0149 Long Chord = 670.1983 Mid. Ord. = 59.2005 P.C. Station 11+92.35 N 10,190,777.7029 E P.T. Station 18+76.41 N 10,190,138.0457 E C.C. Back = S 2° 40′ 26.22" E Ahead = S 37° 24′ 04.68" W Chord Bear = S 17° 21′ 49.23" W	3,102,293.8581 3,102,093.8470 3,101,316.9230			
Course from PT PED15 to PC PED16 S 37° 24' 04.68" W Dist 146.1635				
Curve Data **				
Curve PED16 P.I. Station 26*33.17 N 10,189,536.8734 E Delta = 58° 05′ 25.81" (LT) Degree = 5° 12′ 39.87" Tangent = 610.5985 Length = 1,114.7506	3,101,634.1945			
Radius = 1,099.5000 External = 158.1688 Long Chord = 1,067.6150 Mid. Ord. = 138.2769 P.C. Station 20+22.57 N 10,190,021.9333 E P.T. Station 31+37.33 N 10,188,965.6520 E	3,102,005.0682 3,101,849.9180			
C.C. Back = S 37° 24′ 04.68" W Ahead = S 20° 41′ 21.13" E Chord Bear = S 8° 21′ 21.78" W	3,102,878.5120			
Course from PT PED16 to PED05 S 20° 41′ 21.13" E Dist 837.1996				
Point PED05 N 10,188,182.4429 E 3,102,145.6994 Sta	39+74.52			
Course from PED05 to PED06 S 21° 20′ 10.69" E Dist 1,063.0618				
Point PED06 N 10,187,192.2424 E 3,102,532.4854 Sta	50+37.59			
Course from PED06 to PED07 N 68° 39′ 49.31" E Dist 143.3463				
Point PED07 N 10,187,244.3978 E 3,102,666.0069 Sta	51+80.93			

Ending chain PED1 description







WILLIAMSON COUNTY PRECINCT #3

SHEET 1 OF 1



CR 176 AT RM 2243 SHARED USE PATH HORZONTAL ALIGNMENT DATA

FED. RD. DIV. NO. SHEET PED3 STATE PROJECT NO. 2103-01-033 STATE DIST. COUNTY TEXAS AUS WILLIAMSON CONT. SECT. JOB HIGHWAY NO. 2103 01 033 CR 176

STATION	X-SLOPE	PGL ELEV	DESC.
10+00.00	-0.50%	981.83	VPI
10+20.00	-0.50%	981.32	VPI
10+40.00	-0.50%	979.92	POINT ON GRADE
10+60.00	-0.50%	978.52	VPI
10+80.00	-0.50%	977.91	POINT ON GRADE
11+00.00	-0.50%	977.30	VPI
11+20.00	-0.50%	978.02	POINT ON GRADE
11+40.00	-0.50%	978.75	VPI
11+50.00	-0.50%	978.75	VPI
11+60.00	-0.50%	979.34	POINT ON GRADE
11+80.00	0.50%	980.51	POINT ON GRADE
12+00.00	0.50%	981.13	VPI
12+50.00	0.50%	981.25	VPI
13+00.00	0.50%	981.41	VPI
13+50.00	0.50%	981.52	VPI
14+00.00	0.50%	981.46	VPI
14+50.00	0.50%	981.77	VPI
15+00.00	0.50%	982.26	VPI
15+50.00	0.50%	982.57	VPI
16+00.00	0.50%	983.03	VPI
16+50.00	0.50%	983.60	VPI
17+00.00	0.50%	984.39	VPI
17+50.00	0.50%	985.00	VPI
18+00.00	0.50%	985.29	VPI
18+50.00	0.50%	985.77	VPI
19+00.00	0.50%	986.40	VPI
19+50.00	0.50%	986.63	VPI
20+00.00	0.50%	986.75	VPI
20+50.00	0.50%	987.13	VPI
21+00.00	0.00%	987.26	VPI
21+50.00	-0.50%	987.27	VPI
22+00.00	-0.50%	987.30	VPI
22+50.00	-0.50%	987.04	VPI
23+00.00	-0.50%	986.72	VPI
23+50.00	-0.50%	986.60	VPI
24+00.00	-0.50%	986.44	VPI
24+50.00	-0.50%	986.23	VPI
25+00.00	-0.50%	986.31	VPI
25+50.00	-0.50%	986.94	VPI
26+00.00	-0.50%	986.40	VPI
26+50.00	-0.50%	986.24	VPI
27+00.00	-0.50%	985.74	VPI

STATION	X-SLOPE	PGL ELEV	DESC.
27+50.00	-0.50%	985.28	VPI
28+00.00	-0.50%	985.32	VPI
28+50.00	-0.50%	985.62	VPI
29+00.00	-0.50%	985.87	VPI
29+50.00	-0.50%	986.38	VPI
30+00.00	-0.50%	986.64	VPI
30+50.00	-0.50%	986.98	VPI
31+00.00	-0.50%	987.08	VPI
31+50.00	-0.50%	987.27	VPI
32+00.00	-0.50%	987.68	VPI
32+50.00	-1.50%	988.45	VPI
33+00.00	-1.50%	989.33	VPI
33+50.00	-1.50%	989.93	VPI
34+00.00	-1.50%	990.94	VPI
34+50.00	-1.50%	991.42	VPI
35+00.00	-1.50%	991.40	VPI
35+50.00	-1.50%	990.40	VPI
36+00.00	-1.50%	988.48	VPI
36+50.00	-1.50%	987.09	VPI
37+00.00	-1.50%	986.37	VPI
37+50.00	-1.50%	985.70	VPI
38+00.00	-1.50%	984.84	VPI
38+50.00	-1.50%	983.82	VPI
39+00.00	-1.50%	982.94	VPI
39+50.00	-1.50%	982.13	VPI
40+00.00	-1.50%	980.91	VPI
40+50.00	-1.50%	980.10	VPI
41+00.00	-1.50%	979.64	VPI
41+50.00	-1.50%	978.74	VPI
42+00.00	-1.50%	978.07	VPI
42+50.00	-1.50%	977.31	VPI
43+00.00	-1.50%	976.64	VPI
43+50.00	-1.50%	976.01	VPI
44+00.00	-1.50%	975.28	VPI
44+50.00	-1.50%	974.19	VPI
45+00.00	-1.50%	973.05	VPI
45+50.00	-1.50%	972.09	VPI
46+00.00	-1.50%	971.27	VPI
46+50.00	-1.50%	970.58	VPI
47+00.00	-1.50%	969.81	VPI
47+50.00	-1.50%	969.58	VPI
48+00.00	-1.50%	968.81	VPI
48+50.00	-1.50%	968.59	VPI
49+00.00	-1.50%	968.10	VPI
49+60.00	-1.50%	967.63	VPI
50+00.00	-1.50%	969.50	VPI
50+37.50	-1.50%	966.92	VPI

NOTES:

- 1. REFER TO TYPICAL SECTIONS
 FOR PGL LOCATION RELATIVE TO
 ALIGNMENT.
 2. X-SLOPE IS MEASURED FROM
 PGL TOWARD OPPOSITE EDGE
 OF PATH.








WILLIAMSON COUNTY PRECINCT #3




WSB & ASSOCIATES, INC. FIRM # 16849

CR 176 AT RM 2243 SHARED USE PATH X-SLOPE/PGL DATA

SHEET 1 OF 1 FED. RD. DIV. NO. SHEET PED4 STATE PROJECT NO. 2103-01-033 STATE DIST. COUNTY TEXAS AUS WILLIAMSON CONT. HIGHWAY NO. SECT. JOB 2103 01 033 CR 176






2103

01 033

CR 176



SHEET 1 OF

PED7

CR 176

2103