



301 SE Inner Loop
Georgetown, TX
78626

T: (210) 328-0193

October 02, 2020

Dwayne Gossett
Williamson County
710 Main Street, Ste 101
Georgetown, TX 78626

Re: Annex Renovation

Job No: 279101

Subj: Change Proposal No. 279101-0035

Dear Sir or Madam:

We respectfully submit our proposal for an increase to our contract in the amount of \$1,006 (one thousand six) dollars to provide Relocating (3) "A" Fixtures in Elections Storage 409 for the above referenced project.

Our price is valid for Ten (10) days

Please indicate your acceptance of this change proposal by signing and returning one copy of the attached Form B breakdown of our cost.

Very truly yours,
VAUGHN CONSTRUCTION

A handwritten signature in blue ink, appearing to read "Doug Boram", with a stylized flourish at the end.

Doug Boram

Attachments: Form B and Backup

CC:

FORM B

PROJECT: Annex Renovation

CHANGE PROPOSAL NO: 279101-0035

QUOTATION :

<u>Item</u>	<u>Labor</u>	<u>Materials</u>	<u>Subs</u>	<u>Total</u>
Relocating (3) "A" Fixtures in Elections Storage 409	\$0.00	\$0.00	\$903.00	\$903.00

Totals	\$0.00	\$0.00	\$903.00	\$903.00
--------	--------	--------	----------	----------

Insurance, Tax, Benefits on Labor	\$0.00
-----------------------------------	--------

Overhead	\$0.00
----------	--------

Fee on Subs	\$90.30
-------------	---------

Fee on JTV	\$0.00
------------	--------

Bond	\$12.57
------	---------

Remodel Tax	\$0.00
-------------	--------

TOTAL	\$1,005.87
-------	------------

TIME EXTENSION TO CONTRACT: 0 Days

Submitted Date: 10/2/2020

Accepted

VAUGHN CONSTRUCTION

By: DeWayne Domet

By: Doug Boram

Date 10-29-2020

Proposal Valid for 10 Days



Doyle Electric, LLC
917 Sixth St
Marble Falls, Texas 78654
Phone: 512-743-5534

Request for Change Order

09/22/2020

TO:

Vaughn Construction
Doug Boram
Houston, Texas 77042

JOB:

Project: Annex Renovation
301 SE Inner Loop #109
Georgetown, TX 78626

Change Order Number: 552 – 39

CHANGE ORDER INFORMATION: Relocation of (3) “A” Fixtures

WORK DESCRIPTION: Includes relocating (3) “A” Fixtures in Elections Storage 409 per RFI – 127.

The total amount of this Change Order is: **\$903.00**

Total Number of Working Days: 1

Exclusions:

- Overtime
- Tax
- Sheetrock Cutting, or Repair
- Paint
- Grid Repair
- Schedule Delays

Sincerely,

Dustin Doyle

Dustin Doyle
Doyle Electric, LLC
512-743-5534

Item#	Description	Qty	Price	Price Unit	Ext Price	Labor	Labor Unit	Ext Labor
1001	3/4" EMT	40.00	139.54	C	55.82	5.00	C	2.00
1445	3/4" Set Screw Steel Conn	6.00	381.23	C	22.87	0.10	E	0.60
1545	3/4" Set Screw Steel Cplg	4.00	368.95	C	14.76	0.12	E	0.48
2395	3/4" Beam Clamp w/Conduit Hanger	6.00	204.26	C	12.26	12.00	C	0.72
2472	4" Square x 2-1/8" Deep Box w/brkt (1/2&3/4 KO's)	3.00	5.95	C	17.85	0.30	E	0.90
2660	#12 THHN CU Stranded Wire	132.00	174.15	M	22.99	6.00	M	0.79
4409	#14-12-10 Wire Termination Labor	12.00	0.00	E	0.00	0.18	E	2.16
6133	Red Wirenuts	18.00	145.79	M	2.62	3.50	C	0.63
6168	1/4X4 Toggle Bolt	8.00	37.85	C	3.03	12.00	C	0.96
7114	Ground Screw with Bare Pigtail	3.00	265.76	C	7.97	2.00	C	0.06
					160.17	9.30		

REQUEST FOR INFORMATION



301 SE Inner Loop
Georgetown, TX
78626

T: (210) 328-0193

RFI NO: 127

To: Luma Jaffar
KGA Architecture
1701 Directors Blvd., Ste. 770
Austin, TX 78744
Phone: (512) 441-8200
Fax:
From: Jarvis Brawley

Date: 09/15/2020

Required By: 09/22/2020

Owner: Williamson County, Texas

Job No : 279101

Project: Annex Renovation
301 SE Inner Loop #109
Georgetown, TX 78626

Re: Election Storage 409 "A" Fixtures Conflicting With Pallet Racks

Spec. Section:

Drawing Number: E2.02

Other Reference: See attached sketch

Question:

In Election Storage 409, "A" fixtures are in conflict with the pallet racks. These "A" fixtures are to be at a height of 12' AFF and pallet racks are 16' tall. Please advise if we are to change the layout or change the fixture height

Answer:

Since the racks are going to be 16 ft in height, our recommendation is to install the lights to the center of the room and install at an elevation of 20 ft. See below. Before finalizing height and location, recommend testing lift to be used with racks and verify light locations will not cause a conflict.

Donald Smith, P.E.
Agnew Associates (F-1005)
9/21/20

Very truly yours,

VAUGHN CONSTRUCTION

Attachments:

CC: