

SANTA RITA RANCH PHASE 6, SECTION 5 FINAL PLAT



Minimum Finished Floor Elevation			
(NAVD '88)			
Block	Lot	Min FFE	
А	56	986.2'	
А	57	986.2'	
А	58	986.6'	
А	59	989.5'	
А	60	989.6'	
А	61	990.3'	
А	62	990.6'	
А	63	992.0'	
А	64	992.1'	
А	65	992.9'	
А	66	992.9'	


LEGEND

- BENCHMARK
 CAPPED 1/2" IRON ROD FOUND STAMPED "CBD SETSTONE"
 CAPPED 1/2" IRON ROD SET STAMPED "CBD SETSTONE"
- 1 LOT NUMBER (A) BLOCK DESIGNATION
- B.S.L. BUILDING SETBACK LINE
- p.u.e. PUBLIC UTILITY EASEMENT



(IN FEET) 1 inch = 100 ft.

VICINITY MAP APPROX. SCALE: 1"=2000'



SANTA RITA RANCH PHASE 6, SECTION 5 FINAL PLAT

METES AND BOUNDS

BEING ALL OF THAT CERTAIN 13.147 ACRE TRACT OR PARCEL OF LAND OUT OF THE GREENLEAF FISK SURVEY, ABSTRACT NUMBER 5, SITUATED IN WILLIAMSON COUNTY, TEXAS, BEING A PORTION OF A CALLED 118.212 ACRE TRACT OF LAND CONVEYED TO SANTA RITA KC, LLC, BY DEED IN DOCUMENT NUMBER 2023033961, OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS, SAID 13.147 ACRE TRACT OF LAND BEING MORE FULLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING, AT A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" AT THE NORTHWEST CORNER OF LOT 67, BLOCK A, SANTA RITA RANCH, PHASE 6, SECTION 2, A SUBDIVISION RECORDED IN DOCUMENT NUMBER 2024011244, OFFICIAL PUBLIC RECORDS, WILLIAMSON COUNTY, TEXAS, BEING ON THE EAST LINE OF LOT 85, BLOCK A, SANTA RITA RANCH PHASE 6, SECTION 3, A SUBDIVISION RECORDED IN DOCUMENT NUMBER 2024046349, OFFICIAL PUBLIC RECORDS, WILLIAMSON COUNTY, TEXAS, FOR THE SOUTHWEST CORNER AND THE POINT OF BEGINNING OF THE HEREIN DESCRIBED TRACT OF LAND,

THENCE, WITH THE WEST, NORTH, AND EAST LINES OF SAID SANTA RITA RANCH PHASE 6, SECTION 3, THE FOLLOWING TWELVE (12) COURSES AND DISTANCES, NUMBERED 1 THROUGH 12,

- 1) N10°56'49"E, A DISTANCE OF 461.61 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, 2) N04°36'00"E, A DISTANCE OF 320.65 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
- 3) N66'04'40"E, A DISTANCE OF 28.65 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
 4) S52'26'40"E, A DISTANCE OF 170.27 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, BEING AT THE BEGINNING OF A CURVE TO THE RIGHT,
- 5) ALONG SAID CURVE TO THE RIGHT, HAVING A RADIUS OF 50.00 FEET, AN ARC LENGTH OF 24.72 FEET, AND A CHORD THAT BEARS N51°43'01"E, A DISTANCE OF 24.47 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
- 6) N10°56'49"E, A DISTANCE OF 150.00 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, 7) S77°31'39"E, A DISTANCE OF 316.14 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
- 8) S72'36'48"E, A DISTANCE OF 278.74 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR THE NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT,
- 9) S09'47'28"E, A DISTANCE OF 278.13 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, BEING AT THE BEGINNING OF A CURVE TO THE LEFT,
- 10) ALONG SAID CURVE TO THE LEFT, HAVING A RADIUS OF 235.00 FEET, AN ARC LENGTH OF 33.22 FEET, AND A CHORD THAT BEARS S85'24'47"E, A DISTANCE OF 33.19 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
- 11) SO0'32'15"W, A DISTANCE OF 50.00 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, AND
- 12) S20°09'40"E, A DISTANCE OF 143.60 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR THE SOUTHEAST CORNER OF THE HEREIN DESCRIBED TRACT OF LAND, BEING ON THE WEST LINE OF LOT 3, BLOCK C, SAID SANTA RITA RANCH PHASE 6, SECTION 3, SAME BEING AT THE NORTHEAST CORNER OF LOT 25, BLOCK C, SAID SANTA RITA RANCH PHASE 6, SECTION 2,

THENCE, ALONG THE NORTH LINE OF SAID SANTA RITA RANCH PHASE 6, SECTION 2, THE FOLLOWING NINE (9) COURSES AND DISTANCES, NUMBERED 1 THROUGH 9,

1) S66'03'44"W, A DISTANCE OF 188.78 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
 2) S74'17'37"W, A DISTANCE OF 163.28 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
 3) N83'41'54"W, A DISTANCE OF 454.34 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, BEING AT THE BEGINNING OF A CURVE TO THE LEFT,

- 4) ALONG SAID CURVE TO THE LEFT, HAVING A RADIUS OF 775.00 FEET, AN ARC LENGTH OF 39.97 FEET, AND A CHORD THAT BEARS S07*46'45"W, A DISTANCE OF 39.96 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
- 5) SO6'18'06"W, A DISTANCE OF 89.15 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER,
- 6) N83'41'54"W, A DISTANCE OF 50.00 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, BEING AT THE BEGINNING OF A CURVE TO THE RIGHT,
- 7) ALONG SAID CURVE TO THE RIGHT, HAVING A RADIUS OF 25.00 FEET, AN ARC LENGTH OF 21.03 FEET, AND A CHORD THAT BEARS S30°23'47"W, A DISTANCE OF 20.41 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, BEING AT THE BEGINNING OF A CURVE TO THE LEFT,

<u>GENERAL:</u>

- 1. BEARINGS ARE BASED ON THE TEXAS COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83.
- 2. THIS SUBDIVISION LIES WITHIN THE CITY OF LIBERTY HILL EXTRA-TERRITORIAL JURISDICTION.
- 3. IT IS THE RESPONSIBILITY OF THE OWNER, NOT THE COUNTY, TO ASSURE COMPLIANCE WITH PROVISIONS OF ALL APPLICABLE STATE, FEDERAL AND LOCAL LAWS, AND REGULATIONS RELATING TO PLATTING AND DEVELOPMENT OF THIS PROPERTY. THE COUNTY ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF REPRESENTATIONS BY OTHER PARTIES IN THIS PLAT. FLOODPLAIN DATA, IN PARTICULAR, MAY CHANGE. IT IS FURTHER UNDERSTOOD THAT THE OWNERS OF THE TRACT OF LAND COVERED BY THIS PLAT MUST INSTALL AT THEIR OWN EXPENSE ALL TRAFFIC CONTROL DEVICES AND SIGNAGE THAT MAY BE REQUIRED BEFORE THE ROADS IN THE SUBDIVISION HAVE FINALLY BEEN ACCEPTED FOR MAINTENANCE BY THE COUNTY.
- 4. ALL PUBLIC ROADWAYS AND EASEMENTS AS SHOWN ON THIS PLAT ARE FREE OF LIENS.

DRAINAGE AND FLOODPLAIN:

- 1. EXCEPT IN CERTAIN ISOLATED AREAS REQUIRED TO MEET ACCESSIBILITY REQUIREMENTS, THE MINIMUM LOWEST FINISHED FLOOR ELEVATION SHALL BE ONE FOOT HIGHER THAN THE HIGHEST SPOT ELEVATION THAT IS LOCATED WITHIN FIVE FEET OUTSIDE THE PERIMETER OF THE BUILDING, OR ONE FOOT ABOVE THE BFE, WHICHEVER IS HIGHER.
- 2. A CERTIFICATE OF COMPLIANCE IS HEREBY ISSUED FOR ALL LOTS WITHIN THIS SUBDIVISION. THIS CERTIFICATE OF COMPLIANCE IS VALID UNTIL SUCH TIME AS FEMA OR THE COUNTY REVISES OR NEWLY ADOPTS FLOODPLAIN BOUNDARIES IN THIS VICINITY.
- 3. THIS SUBDIVISION IS SUBJECT TO STORM-WATER MANAGEMENT CONTROLS AS REQUIRED BY WILLIAMSON COUNTY SUBDIVISION REGULATIONS, SECTION B11.1, ON NEW DEVELOPMENT THAT WOULD EVOKE SUCH CONTROLS BEYOND EXISTING CONDITIONS.
- 4. MAINTENANCE RESPONSIBILITY FOR DRAINAGE WILL NOT BE ACCEPTED BY THE COUNTY OTHER THAN THAT ACCEPTED IN CONNECTION WITH DRAINING OR PROTECTING THE ROAD SYSTEM. MAINTENANCE RESPONSIBILITY FOR STORM WATER MANAGEMENT CONTROLS WILL REMAIN WITH THE OWNER.

WATER AND WASTEWATER:

- 1. NO LOT IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTION IS MADE TO AN APPROVED PUBLIC SEWER SYSTEM.
- 2. NO LOT IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL WATER SATISFACTORY FOR HUMAN CONSUMPTION IS AVAILABLE FROM A SOURCE IN ADEQUATE AND SUFFICIENT SUPPLY.
- 3. WATER SERVICE IS PROVIDED BY: WILLIAMSON COUNTY MUD 19F/ GEORGETOWN UTILITY SYSTEMS
- 4. WASTEWATER SERVICE IS PROVIDED BY: WILLIAMSON COUNTY MUD 19F/CITY OF LIBERTY HILL

5. ELECTRIC SERVICE IS PROVIDED BY: PEC

ROADWAY AND RIGHT-OF-WAY:

- 1. IN APPROVING THIS PLAT BY THE COMMISSIONERS COURT OF WILLIAMSON COUNTY, TEXAS, IT IS UNDERSTOOD THAT THE BUILDING OF ALL ROADS, AND OTHER PUBLIC THOROUGHFARES AND ANY BRIDGES OR CULVERTS NECESSARY TO BE CONSTRUCTED OR PLACED IS THE RESPONSIBILITY OF THE OWNER(S) OF THE TRACT OF LAND COVERED BY THIS PLAT IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS PRESCRIBED BY THE COMMISSIONERS COURT OF WILLIAMSON COUNTY, TEXAS. SAID COMMISSIONERS COURT ASSUMES NO OBLIGATION TO BUILD ANY OF THE ROADS, OR PUBLIC THOROUGHFARES SHOWN ON THIS PLAT, OR OF CONSTRUCTING ANY OF THE BRIDGES OR DRAINAGE IMPROVEMENTS IN CONNECTION THEREWITH. THE COUNTY WILL ASSUME NO RESPONSIBILITY FOR DRAINAGE WAYS OR EASEMENTS IN THE SUBDIVISION, OTHER THAN THOSE DRAINING OR PROTECTING THE ROAD SYSTEM.
- 2. SIDEWALKS SHALL BE MAINTAINED BY THE HOMEOWNERS' ASSOCIATION.
- 3. DRIVEWAY ACCESS TO LOTS WITHIN THIS SUBDIVISION FROM SIDE STREETS IS PROHIBITED.
- 4. IMPROVEMENTS WITHIN THE COUNTY ROAD RIGHT-OF-WAY INCLUDING, BUT NOT LIMITED TO LANDSCAPING, IRRIGATION, LIGHTING, CUSTOM SIGNS, ARE PROHIBITED WITHOUT FIRST OBTAINING AN EXECUTED LICENSE AGREEMENT WITH WILLIAMSON COUNTY.

8) ALONG SAID CURVE TO THE LEFT, HAVING A RADIUS OF 50.00 FEET, AN ARC LENGTH OF 42.05 FEET, AND A CHORD THAT BEARS S30°23'47"W, A DISTANCE OF 40.82 FEET TO A CAPPED 1/2 INCH IRON ROD FOUND STAMPED "CBD SETSTONE" FOR CORNER, AND
9) N83°41'54"W, A DISTANCE OF 150.03 FEET TO THE POINT OF BEGINNING, AND CONTAINING 13.147 ACRES OF LAND.

- 5. NO CONSTRUCTION, PLANTING OR GRADING SHALL BE PERMITTED TO INTERFERE WITH SIGHT EASEMENTS BETWEEN THE HEIGHTS OF THREE AND EIGHT FEET AS MEASURED FROM THE CROWNS OF THE ADJACENT STREETS.
- 6. THE OWNER SHALL CREATE A MANDATORY HOMEOWNERS' ASSOCIATION THAT SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND LIABILITY OF ANY LANDSCAPING, IRRIGATION, SIDEWALKS, ILLUMINATION, SUBDIVISION IDENTIFICATION SIGNS, WATER QUALITY FEATURES, ETC. PLACED WITHIN THE WILLIAMSON COUNTY RIGHT-OF-WAY. THIS ASSOCIATION SHALL HAVE ASSESSMENT AUTHORITY TO ENSURE THE PROPER FUNDING FOR MAINTENANCE.
- 7. A PUBLIC UTILITY EASEMENT 10 FEET WIDE IS HEREBY DEDICATED ADJACENT TO ALL STREET RIGHT-OF-WAY.

			Curve Ta	ble		
Curve #	Length	Radius	Chord Direction	Chord Length	Tangent	DELTA
C1	24.72	50.00	N51°43'01"E	24.47	12.62	28°19'21"
C2	33.22	235.00	S85°24'47"E	33.19	16.64	8°05'56"
C3	39.97	775.00	S07°46'45"W	39.96	19.99	2*57'18"
C4	21.03	25.00	S30°23'47"W	20.41	11.18	48°11'23"
C5	42.05	50.00	S30°23'47"W	40.82	22.36	48°11'23"
C6	66.89	825.00	S08°37'27"W	66.87	33.46	4°38'43"
C7	22.86	775.00	S10°06'06"W	22.86	11.43	1°41'25"
C8	39.27	25.00	S55*56'49"W	35.36	25.00	90°00'00"
C9	21.03	25.00	N13°08'53"W	20.41	11.18	48°11'23"
C10	21.03	25.00	S54°57'30"E	20.41	11.18	48°11'23"
C11	162.65	50.00	S55*56'49"W	99.85	897.21	186°22'46"
C12	81.96	275.00	N70°30'53"W	81.66	41.29	17'04'36"
C13	96.86	325.00	N70°30'53"W	96.51	48.79	17°04'36"
C14	23.56	15.00	N73°01'24"E	21.21	15.00	90°00'00"
C15	23.56	15.00	S16°58'36"E	21.21	15.00	90°00'00"
C16	97.46	525.00	N22*42'18"E	97.32	48.87	10°38'13"
C17	106.75	575.00	N22*42'18"E	106.59	53.53	10°38'13"
C18	136.72	285.00	S75°43'10"E	135.41	69.70	27*29'09"
C19	112.73	235.00	S75°43'10"E	111.66	57.47	27*29'09"
C20	23.56	15.00	S73°01'24"W	21.21	15.00	90'00'00"
C21	23.56	15.00	N16°58'36"W	21.21	15.00	90°00'00"
C22	23.55	25.00	S01°02'22"W	22.69	12.73	53°58'05"

Curve Table						
Curve #	Length	Radius	Chord Direction	Chord Length	Tangent	DELTA
C23	23.55	25.00	N55°00'27"E	22.69	12.73	53 ° 58'05"
C24	301.53	60.00	S61*58'36"E	70.59	43.64	287°56'10"
C25	33.93	825.00	N07°28'47"E	33.93	16.97	2°21'23"
C26	32.96	825.00	N09°48'09"E	32.95	16.48	2°17'20"
C27	65.27	50.00	N00°09'23"E	60.74	38.23	74 ° 47'55"
C28	72.66	50.00	S72°29'33"E	66.43	44.44	83°15'30"
C29	17.14	325.00	S77°32'33"E	17.14	8.57	3°01'17"
C30	79.73	325.00	S69*00'15"E	79.53	40.06	14°03'19"
C31	79.52	235.00	S71°40'12"E	79.14	40.14	19°23'13"
C32	78.32	285.00	N81°35'22 " W	78.08	39.41	15 ° 44'45 "
C33	58.40	285.00	N67*50'48"W	58.29	29.30	11 °44' 24 "
C34	14.63	25.00	S11°15'33"W	14.42	7.53	33°31'42"
C35	8.92	25.00	S15°43'29"E	8.87	4.51	20°26'23"
C36	82.56	60.00	S13°28'29"W	76.20	49.32	78 ° 50'20"
C37	68.20	60.00	S85°27'32"W	64.59	38.32	65°07'45"
C38	68.20	60.00	N29°24'43"W	64.59	38.32	65 ° 07 ' 45"
C39	82.56	60.00	N42°34'19"E	76.20	49.32	78 ° 50'20"
C40	8.92	25.00	N71°46'18"E	8.87	4.51	20°26'23"
C41	14.63	25.00	N44°47'16"E	14.42	7.53	33'31'42"
C42	29.47	275.00	N65*02'46"W	29.45	14.75	6'08'21"
C43	52.50	275.00	N73°35'04"W	52.42	26.33	10°56'14"

Line Table				
Line #	Length	Direction		
L1	28.65	N66°04'40"E		
L2	170.27	S52°26'40"E		
L3	150.00	N10°56'49"E		
L4	50.00	S00°32'15"W		
L5	143.60	S20°09'40"E		
L6	89.15	S06°18'06"W		
L7	50.00	N83°41'54"W		
L8	150.03	N83°41'54"W		
L9	82.82	N79°03'11"W		
L10	76.92	N79°03'11"W		
L11	71.19	N28°01'24"E		
L12	71.19	N28°01'24"E		
L13	69.69	N28°01'24"E		
L14	69.69	N28°01'24"E		

SHEET NO. 2 OF 3



J: AC3D 5567 Survey PLAT - SRR 6-5.dwg

SANTA RITA RANCH PHASE 6, SECTION 5 FINAL PLAT

STATE OF TEXAS

Ş. KNOW ALL MEN BY THESE PRESENTS;

§.

COUNTY OF WILLIAMSON

I, JAMES EDWARD HORNE, VICE PRESIDENT, SANTA RITA KC, LLC, OWNER OF THE CERTAIN CALLED 118.212 ACRE TRACT OF LAND CONVEYED BY DEED IN DOCUMENT NUMBER 2023033961, OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS, OUT OF AND A PART OF THE GREENLEAF FISK SURVEY, ABSTRACT NUMBER 5, SITUATED IN WILLIAMSON COUNTY, TEXAS, AND DO HEREBY SUBDIVIDE SAID TRACT AS SHOWN HEREON, AND DO HEREBY CONSENT TO ALL PLAT NOTE REQUIREMENTS SHOWN HEREON, AND DO HEREBY FOREVER DEDICATE TO THE PUBLIC THE ROADS, ALLEYS, RIGHTS-OF-WAY, EASEMENTS AND PUBLIC PLACES SHOWN HEREON FOR SUCH PUBLIC PURPOSES AS WILLIAMSON COUNTY MAY DEEM APPROPRIATE, AND DO HEREBY STATE THAT ALL PUBLIC ROADWAYS AND EASEMENTS AS SHOWN ON THIS PLAT ARE FREE OF LIENS. THIS SUBDIVISION IS TO BE KNOWN AS:

"SANTA RITA RANCH PHASE 6, SECTION 5 FINAL PLAT"

TO CERTIFY WHICH, WITNESS BY MY HAND THIS ______ DAY OF ______ Jence _____, 20 25

SANTA RITA KC, LLC, A TEXAS LIMITED LIABILITY COMPANY

BY: MREM TEXAS MANAGER, LLC, A DELAWARE LIMITED LIABILITY COMPANY, ITS MANAGER

JAMES EDWARD HORNE **WICE PRESIDENT** 1700 CROSS CREEK LANE, STE, 100 LIBERTY HILL, TX 78642

STATE OF TEXAS:

COUNTY OF WILLIAMSON:

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED JAMES EDWARD HORNE, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT OF WRITING, AND HE ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED.

WITNESS MY HAND AND SEAL OF OFFICE, THIS THE REAL DAY OF TANLARY, 2025, A.D.

Lolley (10/lan Stallo

NOTARY PUBLIC IN AND FOR WILLIAMSON COUNTY, TEXAS

ASHLEY CUELLAR SOUSA ctery Public. State of Texas My Commission Expires May 16, 2026 NOTARY ID 13376154-3

CONSENT OF MORTGAGEE

THE UNDERSIGNED. BEING THE HOLDER OF A DEED OF TRUST LIEN SECURED BY THE PROPERTY, DATED OCTOBER 31, 2013, RECORDED AS DOCUMENT NO. 2013103003 IN THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS, SECURING A NOTE OF EVEN DATE THEREWITH, EXECUTES THIS DECLARATION SOLELY FOR THE PURPOSES OF EVIDENCING ITS CONSENT TO THE TERMS AND PROVISIONS HEREOF.

INTERNATIONAL BANK OF COMMERCE,

A TEXAS BANKING ASSOCIATION

BY:

THIS FLOOD STATEMENT, AS DETERMINED BY A H.U.D.-F.I.A. FLOOD INSURANCE RATE MAP, DOES NOT IMPLY THAT THE PROPERTY OR THE IMPROVEMENTS THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS, GREATER FLOODS CAN AND WILL OCCUR, AND FLOOD HEIGHTS MAY INCREASE BY MAN-MADE OR NATURAL CAUSES.


THIS STATEMENT SHALL NOT CREATE LIABILITY ON THE PART OF ENGINEER OR SURVEYOR.

STATE OF TEXAS:

COUNTY OF TRAVIS:

NO PORTION OF THIS TRACT IS WITHIN THE 100 YEAR FLOOD PLAIN AS SHOWN ON FLOOD INSURANCE RATE COMMUNITY PANEL #48491C0275E, EFFECTIVE SEPTEMBER 26, 2008 FOR WILLIAMSON COUNTY, TEXAS.

I, STEVEN P. CATES, P.E., AM AUTHORIZED UNDER THE LAWS OF THE STATE OF TEXAS, TO PRACTICE THE PROFESSION OF ENGINEERING, AND HEREBY CERTIFY THAT THIS SUBDIVISION PLAT COMPLIES WITH THE REQUIREMENTS OF WILLIAMSON COUNTY.





ID # F3791

STATE OF TEXAS:

COUNTY OF TRAVIS:

I, ERIC J. DANNHEIM, R.P.L.S., AM AUTHORIZED UNDER THE LAWS OF THE STATE OF TEXAS, TO PRACTICE THE PROFESSION OF SURVEYING, AND HEREBY CERTIFY THAT THIS SUBDIVISION PLAT COMPLIES WITH THE WILLIAMSON COUNTY SUBDIVISION ORDINANCE. ALL EASEMENTS OF RECORD AS SHOWN ON THE COMMITMENT FOR TITLE INSURANCE ISSUED BY STEWART TITLE GUARANTY COMPANY, GF NO. 1800327-COM, EFFECTIVE DATE JANUARY 23, 2018, ISSUED DATE JANUARY 31, 2018 ARE SHOWN OR NOTED ON THE PLAT.

28/25

SURVEYED BY: ERIC J. DANNHEIM, R.P.L.S. NO. 6075 CARLSON, BRIGANCE & DOERING, INC. 5501 WEST WILLIAM CANNON DRIVE, AUSTIN, TEXAS 78749 EDANNHEIM@cbdeng.com



MIKE^I ETIENNE, DEPUTY CITY MANAGER CITY OF LIBERTY HILL, TEXAS

ROAD NAME AND ADDRESS ASSIGNMENTS VERIFIED THIS THE 28th Day OF January, 2025A.D.

Jerusa Bak

PRINTED NAME: JASON RANGEL TILE: SEMIOR VICE PRESIDENT

STATE OF TEXAS

BEFORE ME ON THIS DAY PERSONALLY APPEARED, <u>JASON Rangel</u>, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED THE FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATION THEREIN EXPRESSED. __, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS THE 28 DAY OF SANUARY __, A.D., 20<u>25</u> raral. Herrida BY: NOTARY PUBLIC, STATE OF TEXAS ARACELI HERNANDEZ

PRINTED NAME: Araceli Hernandez MY COMMISSION EXPIRES 6-2-2028

Notary Public, State of Texas Commission Expires 06-02-2028 The of The Notary ID 126285198

WILLIAMSON COUNTY ADDRESSING COORDINATOR WIILIAMSON COUNTY, TEXAS

Teresa Baker PRINTED NAME

STATE OF TEXAS COUNTY OF WILLIAMSON

KNOW ALL MEN BY THESE PRESENTS;

DATE

I, BILL GRAVELL, JR., COUNTY JUDGE OF WILLIAMSON COUNTY, TEXAS, DO HEREBY CERTIFY THAT THIS MAP OR PLAT, WITH FIELD NOTES HEREON, FOR A SUBDIVISION HAVING BEEN FULLY PRESENTED TO THE COMMISSIONERS COURT OF WILLIAMSON COUNTY, TEXAS, AND BY THE SAID COURT DULY CONSIDERED, WERE ON THIS DAY APPROVED AND THAT THIS PLAT IS AUTHORIZED TO BE REGISTERED AND RECORDED IN THE PROPER RECORDS OF THE COUNTY CLERK OF WILLIAMSON COUNTY, TEXAS.

BILL GRAVELL, JR., COUNTY JUDGE WILLIAMSON COUNTY, TEXAS

STATE OF TEXAS

KNOW ALL MEN BY THESE PRESENTS; COUNTY OF WILLIAMSON

I, NANCY RISTER, CLERK OF THE COUNTY COURT OF SAID COUNTY, DO HEREBY CERTIFY THAT THE FOREGOING INSTRUMENT IN WRITING, WITH ITS CERTIFICATE OF AUTHENTICATION WAS FILED FOR RECORD IN MY OFFICE ON THE _____DAY OF 20____, A.D., AT ______ O'CLOCK, ____.M., AND DULY RECORDED THIS THE _____ DAY OF _____, 20____, A.D., AT ______ O'CLOCK, ___.M., IN THE OFFICIAL PUBLIC RECORDS OF SAID COUNTY IN INSTRUMENT NO.

TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT THE COUNTY COURT OF SAID COUNTY, AT MY OFFICE IN GEORGETOWN, TEXAS, THE DATE LAST SHOWN ABOVE WRITTEN.

NANCY RISTER, CLERK COUNTY COURT OF WILLIAMSON COUNTY, TEXAS

BY: _____ DEPUTY

