





**Williamson County Road Bond Program**

**CR 255**

**Williamson County Project No. 25IFB9**

**Change Order No. 2**

**Reason for Change**

This Change Order compensates the Contractor for implementing additional safety measures along Ronald Reagan Blvd at CR 255. Due to the high traffic volume and speed at this location, concrete traffic barriers will be installed to protect workers within the work zone. The speed limit will also be reduced to 50 mph during the widening process. Message boards will be placed 8 days prior to the start of construction, to notify the traveling public per Williamson County's request. The Contractor provided signed and sealed Traffic Control Plan (TCP) sheets for this change.

Following is a summary of new items required for this Change Order.

| ITEM     | DESCRIPTION                | QTY | UNIT |
|----------|----------------------------|-----|------|
| 999-WC01 | ADDITIONAL SAFETY MEASURES | 1.0 | LS   |

This Change Order results in a net increase of \$40,644.93 to the Contract amount, for an adjusted Contract total of \$20,874,710.34. The original Contract amount was \$20,847,300.93. As a result of this and all Change Orders to-date, \$27,409.41 has been added to the Contract, resulting in a 0.13% net increase in the Contract cost. No additional days will be added to or deducted from the Contract as a result of this Change Order.

**HNTB Corporation**

Oscar Salazar-Bueno, P.E.

# Change Order Worksheet

|                                 |          |                       |                          |
|---------------------------------|----------|-----------------------|--------------------------|
| <b>Contract Name</b>            | CR 255   | <b>Solicitation #</b> | 25IFB9                   |
| <b>Date awarded</b>             | 1/7/2025 |                       |                          |
| <b>Awarded Contract Amount</b>  |          | \$20,847,300.93       |                          |
|                                 |          |                       | <b>Percentage Change</b> |
| Change order #1                 |          | (\$13,235.52)         | -0.06%                   |
| Change order #2                 |          | \$40,644.93           | 0.19%                    |
| <b>Total changes to date</b>    |          | <hr/>                 | <hr/>                    |
|                                 |          | \$27,409.41           | 0.13%                    |
| <b>Adjusted contract amount</b> |          | \$20,874,710.34       | (Running totals here)    |

# CHANGE ORDER REASON(S) CODE CHART

|   |   |
|---|---|
| <p>1. Design Error or Omission</p>                      | <p>1A. Incorrect PS&amp;E<br/>1B. Other</p>   |
| <p>2. Differing Site Conditions<br/>(unforeseeable)</p> | <p>2A. Dispute resolution (expense caused by conditions and/or resulting delay)<br/>2B. Unavailable material<br/>2C. New development (conditions changing after PS&amp;E completed)<br/>2D. Environmental remediation<br/>2E. Miscellaneous difference in site conditions (unforeseeable)(Item 9)<br/>2F. Site conditions altered by an act of nature<br/>2G. Unadjusted utility (unforeseeable)<br/>2H. Unacquired Right-of-Way (unforeseeable)<br/>2I. Additional safety needs (unforeseeable)<br/>2J. Other</p>  |
| <p>3. County Convenience</p>                            | <p>3A. Dispute resolution (not resulting from error in plans or differing site conditions)<br/>3B. Public relations improvement<br/>3C. Implementation of a Value Engineering finding<br/>3D. Achievement of an early project completion<br/>3E. Reduction of future maintenance<br/>3F. Additional work desired by the County<br/>3G. Compliance requirements of new laws and/or policies<br/>3H. Cost savings opportunity discovered during construction<br/>3I. Implementation of improved technology or better process<br/>3J. Price adjustment on finished work (price reduced in exchange for acceptance)<br/>3K. Addition of stock account or material supplied by state provision<br/>3L. Revising safety work/measures desired by the County<br/>3M. Other</p> |
| <p>4. Third Party Accommodation</p>                     | <p>4A. Failure of a third party to meet commitment<br/>4B. Third party requested work<br/>4C. Compliance requirements of new laws and/or policies (impacting third party)<br/>4D. Other</p>   |
| <p>5. Contractor Convenience</p>                        | <p>5A. Contractor exercises option to change the traffic control plan<br/>5B. Contractor requested change in the sequence and/or method of work<br/>5C. Payment for Partnering workshop<br/>5D. Additional safety work/measures desired by the contractor<br/>5E. Other</p>   |
| <p>6. Untimely ROW/Utilities</p>                        | <p>6A. Right-of-Way not clear (third party responsibility for ROW)<br/>6B. Right-of-Way not clear (County responsibility for ROW)<br/>6C. Utilities not clear<br/>6D. Other</p>   |

July 23, 2025

HNTB Engineers  
101 E. Old Settlers STE 225  
Round Rock, Texas 78664

Reference: **Change Proposal Summary 003.2**  
CR 255  
Project No.: 25IFB9

Dear Mr. Church:

Please see attached the Cost Proposal Summary in the amount of \$40,644.93 for the changes made to the traffic control and phasing plans for the roadway widening construction at Ronald Reagan.

We appreciate your time spent reviewing this request and will look forward to your response. Please call me at (432) 528-1638 if you have any questions or need any additional information regarding this matter.

Sincerely,

**Jordan Foster Construction, LLC**



Shelby Priddy  
Project Manager

Attachments: Cost Proposal Summary 003.2 Revised Traffic Control – Ronald Reagan



**Cost Proposal Summary**

Williamson County  
 Project: CR 255  
 Project No.: 25IFB9

Project: CR 255  
 Job No. 25004  
 Estimator: SP

Change File: 003.2  
 Date: 23-Jul-25

|   |     |                              |     |
|---|-----|------------------------------|-----|
| <b>Brief Scope of Work:</b><br><i>Revised Traffic Control Changes - Ronald Reagan</i> |     |                              |     |
| Does this Change affect the Contract Time?  | TBD | If so, number of days (+/-): | TBD |

| WORK DESCRIPTION                                      | LABOR | MATERIAL | EQUIP. | SUBS     | TOTALS   |
|---|-------|----------|--------|----------|----------|
| <b>LABOR:</b><br>Direct Labor                         | 0.00  |          |        |          | 0.00     |
| <b>MATERIAL:</b><br>Total - Material Costs            |       | 0.00     |        |          | 0.00     |
| <b>EQUIPMENT</b><br>Total - Equipment Costs           |       |          | 0.00   |          | 0.00     |
| <b>SUBCONTRACTORS:</b><br>Total - Subcontractor Costs |       |          |        | 18250.00 | 18250.00 |
| <b>SUBTOTALS:</b>                                     | 0.00  | 0.00     | 0.00   | 18250.00 | 18250.00 |
| Compensation on Direct Labor - 5%                     | 0.00  |          |        |          | 0.00     |
| Compensation on Material - 5%                         |       | 0.00     |        |          | 0.00     |
| Compensation on Equipment - 5%                        |       |          | 0.00   |          | 0.00     |
| Compensation on Subcontracts - 5%                     |       |          |        | 912.50   | 912.50   |
| <b>SUBTOTALS:</b>                                     | 0.00  | 0.00     | 0.00   | 19162.50 | 19162.50 |

| <b>UNIT PRICES:</b>                       |          |         |                 |
|---|----------|---------|-----------------|
| Unit Price Description                    | Quantity | Measure | Unit Price      |
| 662-6063 WK ZN PAV MRK REMOV (W) 4" (SLD) | 12400.00 | LF      | 0.85            |
| 662-6095 WK ZN PAV MRK REMOV (Y) 4" (SLD) | 12400.00 | LF      | 0.85            |
| <b>SUBTOTAL:</b>                          |          |         | <b>21080.00</b> |

|                             |                 |
|-----------------------------|-----------------|
| Estimate Subtotal           | 19162.50        |
| Unit Price Subtotal         | 21080.00        |
| Bond (1%)                   | 402.43          |
| <b>TOTAL COST PROPOSAL:</b> | <b>40644.93</b> |



**JORDAN  
FOSTER**  
INFRASTRUCTURE

Project: 25IFB9  
 Directive #  
 Date: 7/23/25  
 Estimator: SP  
 Change File: 003.2

**Revised Traffic Control Changes - Ronald Reagan**

| Description   |  | Quantity | Unit | Unit Price  | L-M-E-S | Labor       | Material    | Equipment   | Subcontract     | Total           |
|---|--|----------|------|-------------|---------|-------------|-------------|-------------|-----------------|-----------------|
| <b>Additional Mobilizations &amp; Striping Removals (New Item)</b>  |  |          |      |             |         |             |             |             |                 |                 |
| <b>Sub</b>  |  |          |      |             |         |             |             |             |                 |                 |
| Striping Crew Additoinal Mobs - Install PH 1 ST 1, Remove PH 1 ST 1 & Install PH 1 ST 2, Remove PH 1 ST 2 & Final Surface Overlay |  | 3.00     | EA   | \$ 2,500.00 | S       | 0.00        | 0.00        | 0.00        | 7500.00         | 7500.00         |
| Traffic Control Crew Additoinal Mob   |  | 1.00     | EA   | \$ 2,500.00 | S       | 0.00        | 0.00        | 0.00        | 2500.00         | 2500.00         |
| 677-6001 - Elim Ext Pav Mrk & Mrks (4")   |  | 6,200.00 | LF   | \$ 1.25     | S       | 0.00        | 0.00        | 0.00        | 7750.00         | 7750.00         |
| Furnish & Install Added Signs per revised TCP   |  | 2.00     | EA   | \$ 250.00   | S       | 0.00        | 0.00        | 0.00        | 500.00          | 500.00          |
| <b>Subtotal</b>   |  |          |      |             |         | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>18250.00</b> | <b>18250.00</b> |
| <b>COMPENSATION</b>   |  |          |      |             |         | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>     | <b>912.50</b>   |
| <b>TOTAL</b>  |  |          |      |             |         |             |             |             |                 | <b>19162.50</b> |

# TRAFFIC CONTROL PLAN


CR 255  
RONALD REAGAN BLVD  
WILLIAMSON COUNTY

## SHEET INDEX

|  |        |
|--|--------|
| BARRICADING SUMMARY TABLE AND GENERAL NOTES..... | 2      |
| TRAFFIC CONTROL PLAN.....                        | 3 - 4  |
| TRAFFIC CONTROL DETAILS.....                     | 5 - 19 |



SHELBY BRYANT PRIDDY | JORDAN FOSTER CONSTRUCTION  
PROJECT MANAGER | SPRIDDY@JORDANFOSTERCONSTRUCTION.COM  
M: 432-528-1638 F: 512.990.3785 | 15603 NORTH IH 35 | PFLUGERVILLE, TX 78660



VICINITY MAP  
NOT TO SCALE



**SUN STAR SERVICES, LLC**  
400 WIMBERLEY OAKS DRIVE, WIMBERLEY, TX 78676  
PHONE: (512) 618-5150  
EMAIL: LESTELLA@SUNSTARSERVICES.GURU  
TBPE REG. NO. F-17453

SUBMITTED BY Lestella S. Valley DATE AUGUST 19, 2025  
LESTELLA S. VALLEY, P.E.  
SUN STAR SERVICES, L.L.C.

## BARRICADING SUMMARY TABLE

### STREETS

| STREETS | FROM    | TO     | CLASSIFICATION | ALLOWED BARRICADING HOURS     | ESTIMATED START DATE AND DURATION | PLANNED IMPROVEMENTS | TRAFFIC CONTROL PLAN SHEET | COMMENTS |
|---------|---------|--------|----------------|-------------------------------|-----------------------------------|----------------------|----------------------------|----------|
| CR 255  | FM 3405 | CR 289 | TXDOT ROW      | 24 HRS A DAY<br>7 DAYS A WEEK | ***START DATE TO BE DETERMIND***  | WIDENING OF ROADWAY  | 3 & 4                      | NONE     |

START DATE TO BE DETERMINED BY GOVERNING AGENCY & CONTRACTOR  
 ALLOWED BARRICADING HRS TO BE DETERMINED BY GOVERNING AGENCY & CONTRACTOR

**SPECIAL NOTES:**

1. CONTRACTOR MAY USE ANY TEMPORARY TRAFFIC BARRIER THAT MEETS AASHTO MASH REQUIREMENTS. CONTRACTOR SHALL BE RESPONSIBLE TO ENSURE THAT BARRIER SELECTED IS SET IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS, AND ACCORDING WITH CRITERIA IN CHAPTER 5 OF AASHTO ROADSIDE DESIGN GUIDE.
2. CONTRACTOR SHALL COVER ANY CONFLICTING LANE MARKINGS OR ELIMINATE VIA WATER OR ABRASIVE SAND BLASTING.

**TXDOT GENERAL NOTES:**

1. REFER TO TXDOT STANDARD BC-21 AND WZ (RCD)-13 FOR ADDITIONAL NOTES REGARDING TRAFFIC CONTROL REQUIREMENTS.
2. ALL DEVICES SHALL BE SET IN ACCORDANCE WITH THE LATEST EDITION OF THE T.M.U.T.C.D.
3. SANDBAGS SHALL BE USED AS BALLAST ON ALL BARRICADES AND SIGNS.
4. COORDINATION WITH ADJACENT JURISDICTIONS IS REQUIRED PRIOR OF CONSTRUCTION ACTIVITY AND THE INSTALLATION OF TEMPORARY TRAFFIC CONTROL DEVICES.
5. CONTRACTOR RESPONSIBLE FOR DRIVEWAY/LANDOWNER COORDINATION.
6. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ANY PROPOSED CHANGES TO THE TRAFFIC CONTROL PLAN TO THE ENGINEER AND TXDOT FOR APPROVAL.
7. CONTRACTOR SHALL COORDINATE WITH AFFECTED PROPERTY OWNERS PRIOR TO STARTING WORK CONTRACTOR SHALL MAINTAIN ACCESS TO DRIVEWAYS UNLESS PRIOR ARRANGEMENTS HAVE BEEN MADE WITH HOME OWNERS.



08/19/2025



*L. Stella S. Valley*

|              |         |       |                      |           |   |             |       |
|--------------|---------|-------|----------------------|-----------|---|-------------|-------|
| REVISION:    |         | DATE: |                      | DRAWN BY: | MB  | PROJECT NO: | 25155 |
| DESCRIPTION: | CR 255  |       | RONALD REAGAN BLVD   |           | WILLIAMSON COUNTY                           |             |       |
| APPROVED BY: |         |       | TRAFFIC CONTROL PLAN |           | BARRICADING SUMMARY TABLE AND GENERAL NOTES |             |       |
| SHEET NAME:  |         |       |                      |           |   |             |       |
| SHEET:       | 2 OF 19 |       |                      |           |   |             |       |


Move these signs to mirror 50MPH ahead signs will be 55mph for WB traffic approaching FM3405

-1)-18 SHEET 18 WARNING SIGNS


We don't need this sign at all.

Adjust opening to compensate lrg truck traffic at Marcellos

Plus the existing drwy.





Move these signs back to match RWA and BWZ signs



NOTES:  
1. REFER TO SHEET 3 FOR NOTES

LEGEND:

- SIGN STAND
- CHANNELIZING DEVICE ( DRUM )
- EXISTING WORK ZONE
- PROPOSED WORK ZONE
- PRECAST SINGLE SLOPE CONCRETE BARRIER
- SLED TEMP. WORK ZONE ATTENUATOR TL-3



MATCH LINE A SEE THIS SHEET

**SUN STAR SERVICES, LLC**  
 400 WIMBERLEY OAKS DRIVE, WIMBERLEY, TX 78676  
 PHONE: (512) 618-5150  
 EMAIL: LESTELLA@SUNSTARSERVICES.GURU  
 TBPE REG. NO. F-17453

08/19/2025


*Lestella S. Valley*

We will need to bag the existing 65mph sign just south of CR 289 intersection.



Move these signs back to match RWA and BWZ signs

REFER TO TCP (2-1)-18 SHEET 18 FOR ADVANCE WARNING SIGNS

MATCH LINE A SEE THIS SHEET




|               |   |                      |
|---------------|---|----------------------|
| APPROVED BY:  |   |                      |
| DESCRIPTION:  | CR 255                                  |                      |
| PROJECT NAME: | RONALD REAGAN BLVD<br>WILLIAMSON COUNTY |                      |
| SHEET NAME:   | TRAFFIC CONTROL PLAN<br>PHASE 1         |                      |
| DRAWN BY:     | MB                                      | PROJECT NO:<br>25155 |
| DATE:         | CITY JOB NO:                            |                      |
| REVISION:     | SHEET:<br>3 OF 19                       |                      |



NOTES:  
1. REFER TO SHEET 3 FOR NOTES

- LEGEND:
- SIGN STAND
  - CHANNELIZING DEVICE (DRUM)
  - EXISTING WORK ZONE
  - PROPOSED WORK ZONE
  - PRECAST SINGLE SLOPE CONCRETE BARRIER
  - SLED TEMP. WORK ZONE ATTENUATOR TL-3



MATCH LINE A SEE THIS SHEET

MATCH LINE A SEE THIS SHEET

|               |   |             |       |
|---------------|---|-------------|-------|
| APPROVED BY:  | CR 255                                  |             |       |
| DESCRIPTION:  | RONALD REAGAN BLVD<br>WILLIAMSON COUNTY |             |       |
| PROJECT NAME: | TRAFFIC CONTROL PLAN                    |             |       |
| SHEET NAME:   | PHASE 1                                 |             |       |
| DRAWN BY:     | MB                                      | PROJECT NO: | 25155 |
| DATE:         | CITY JOB NO:                            |             |       |
| REVISION:     | SHEET:<br>3 OF 19                       |             |       |

MATCH LINE B SEE THIS SHEET

APPROVED BY:

DESCRIPTION: CR 255

DATE: REVISION:

PROJECT NAME: RONALD REAGAN BLVD  
WILLIAMSON COUNTY

DRAWN BY: MB


SHEET NAME: TRAFFIC CONTROL PLAN

PROJECT NO: 25155


SHEET: 4 OF 19

CITY JOB NO:

PHASE 2




MATCH LINE B SEE THIS SHEET



MATCH LINE B SEE THIS SHEET

08/19/2025



NOTES:  
1. REFER TO SHEET 3 FOR NOTES

- LEGEND:
- SIGN STAND
  - CHANNELIZING DEVICE (DRUM)
  - EXISTING WORK ZONE
  - PROPOSED WORK ZONE
  - PRECAST SINGLE SLOPE CONCRETE BARRIER
  - SLED TEMP. WORK ZONE ATTENUATOR TL-3

MATCH LINE B SEE THIS SHEET

|               |   |                      |
|---------------|---|----------------------|
| APPROVED BY:  |   |                      |
| DESCRIPTION:  | CR 255                                  |                      |
| PROJECT NAME: | RONALD REAGAN BLVD<br>WILLIAMSON COUNTY |                      |
| SHEET NAME:   | TRAFFIC CONTROL PLAN<br>PHASE 2         |                      |
| DRAWN BY:     | MB                                      | PROJECT NO:<br>25155 |
| DATE:         | CITY JOB NO:                            |                      |
| REVISION:     | SHEET:<br>4 OF 19                       |                      |

REFER TO TCP (2-1)-18 SHEET 18 FOR ADVANCE WARNING SIGNS



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for any conversation of this standard to other persons or for incorrect results or damage resulting from its use.  
 DATE: \_\_\_\_\_  
 FILE: \_\_\_\_\_

**BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:**

- The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
- The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
- The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
- Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
- When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
- The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
- All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
- The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
- Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
- Traffic control devices should be in place only while work is actually in progress or a definite need exists.
- The Engineer has the final decision on the location of all traffic control devices.
- Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

**WORKER SAFETY NOTES:**


- Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
- Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

**COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES**

- Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
- Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).

|  |
|--|
| <p align="center">THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT<br/> <a href="http://www.txdot.gov">http://www.txdot.gov</a></p> |
| COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)  |
| DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)   |
| MATERIAL PRODUCER LIST (MPL)   |
| ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS)"   |
| STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)   |
| TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)   |
| TRAFFIC ENGINEERING STANDARD SHEETS  |

SHEET 1 OF 12


|   |   |
|---|---|
| <br>Texas Department of Transportation | <br>Traffic Safety Division Standard |
| <b>BARRICADE AND CONSTRUCTION<br/>         GENERAL NOTES<br/>         AND REQUIREMENTS</b>                                  |   |
| <b>BC (1) - 21</b>  |   |
| FILE: bc-21.dgn<br>TxDOT November 2002<br>4-03 T-13<br>9-07 8-14<br>5-10 5-21   | SHEET NO.<br>25155  |



|               |   |
|---------------|---|
| APPROVED BY:  |   |
| DESCRIPTION:  | CR 255<br>RONALD REAGAN BLVD<br>WILLIAMSON COUNTY         |
| PROJECT NAME: | TRAFFIC CONTROL PLAN<br>TXDOT<br>STANDARD NOTES & DETAILS |
| SHEET NAME:   | 2 OF 15   |
| DRAWN BY:     | MB  |
| PROJECT NO:   | 25155   |
| CITY JOB NO:  |   |
| REVISION:     | SHEET:<br>6 OF 19   |

DISCLAIMER: This standard is approved by the Texas Engineering Practice Act. No part of this standard shall be made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


### TYPICAL LOCATION OF CROSSROAD SIGNS



\*\* May be mounted on back of "ROAD WORK AHEAD" (CW20-10) sign with approval of Engineer. (See note 2 below)

1. The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-10) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
2. The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-10) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
3. Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
4. The "ROAD WORK NEXT X MILES" (G20-1a) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
5. Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
6. When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

### T-INTERSECTION



#### CSJ LIMITS AT T-INTERSECTION

1. The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
2. If construction closes the road at a T-Intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC110) also. The "ROAD WORK NEXT X MILES" (left arrow) (G20-1aTL) and "ROAD WORK NEXT X MILES" (right arrow) (G20-1aTR) signs shall be replaced by the detour signing called for in the plans.

### TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING<sup>TMUTCD</sup>

| Sign Number or Series                 | SIZE              |                    | SPACING          |                                 |
|---------------------------------------|-------------------|--------------------|------------------|---------------------------------|
|                                       | Conventional Road | Expressway/Freeway | Posted Speed MPH | Sign Spacing "X" Feet (Approx.) |
| CW20 <sup>4</sup>                     | 48" x 48"         | 48" x 48"          | 30               | 120                             |
| CW21                                  |                   |                    | 35               | 160                             |
| CW22                                  |                   |                    | 40               | 240                             |
| CW23                                  |                   |                    | 45               | 320                             |
| CW1, CW2, CW7, CW8, CW9, CW11, CW14   | 36" x 36"         | 48" x 48"          | 50               | 400                             |
| CW3, CW4, CW5, CW6, CW8-3, CW10, CW12 | 48" x 48"         | 48" x 48"          | 55               | 500 <sup>2</sup>                |
|                                       |                   |                    | 60               | 600 <sup>2</sup>                |
|                                       |                   |                    | 65               | 700 <sup>2</sup>                |
|                                       |                   |                    | 75               | 900 <sup>2</sup>                |
|                                       |                   |                    | 80               | 1000 <sup>2</sup>               |
|                                       |                   |                    | 80               | 1000 <sup>2</sup>               |


<sup>4</sup> For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

<sup>2</sup> Minimum distance from work area to first advance warning sign nearest the work area and/or distance between each additional sign.

#### GENERAL NOTES


1. Special or larger size signs may be used as necessary.
2. Distance between signs should be increased as required to have 1500 feet advance warning.
3. Distance between signs should be increased as required to have 1/2 mile or more advance warning.
4. 36" x 36" "ROAD WORK AHEAD" (CW20-10) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
5. Only diamond shaped warning sign sizes are indicated.
6. See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

### WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between initial work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-10) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

### SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING AT THE CSJ LIMITS



### SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



#### LEGEND

|       |   |
|-------|---|
| —     | Type 3 Barricade  |
| O O O | Channelizing Devices  |
| X     | Sign  |
| X     | See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements. |

#### NOTES

The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.

The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.

\*\* CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.

◇ Area for placement of "ROAD WORK AHEAD" (CW20-10) sign and other signs or devices as called for on the Traffic Control Plan.

◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

SHEET 2 OF 12

Texas Department of Transportation

BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21

|                     |                    |                   |             |             |
|---------------------|--------------------|-------------------|-------------|-------------|
| DATE: 00-21.dgn     | DESIGNED BY: TxDOT | CHECKED BY: TxDOT | DATE: TxDOT | DATE: TxDOT |
| DATE: November 2002 | DATE: TxDOT        | DATE: TxDOT       | DATE: TxDOT | DATE: TxDOT |
| DATE: 9-07          | DATE: 8-14         | DATE: 7-13        | DATE: 5-21  | DATE: TxDOT |

|               |   |                          |
|---------------|---|--------------------------|
| APPROVED BY:  |   |                          |
| PROJECT NAME: | CR 255<br>RONALD REAGAN BLVD<br>WILLIAMSON COUNTY | TRAFFIC CONTROL PLAN     |
| SHEET NAME:   | TXDOT   | STANDARD NOTES & DETAILS |
| DRAWN BY:     | MB  | PROJECT NO:<br>25155     |
| CITY JOB NO:  |   |                          |
| SHEET:        | 7 OF 19   |                          |

3 OF 15


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the construction of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

### TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



#### GUIDANCE FOR USE:

##### LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/intermediate term work zone speed limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- a) rough road or damaged pavement surface
- b) substantial alteration of roadway geometrics (diversions)
- c) construction detours
- d) grade
- e) width
- f) other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

##### SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

##### GENERAL NOTES

1. Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
2. Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
3. Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
4. Frequency of work zone speed limit signs should be:  
 40 mph and greater: 0.2 to 2 miles  
 35 mph and less: 0.2 to 1 mile
5. Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
6. Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (W20-50P), "WORK ZONE" (G20-50P) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to item 502.
7. Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
8. Techniques that may help reduce traffic speeds include but are not limited to:  
 A. Low enforcement.  
 B. Flagger stationed next to sign.  
 C. Portable changeable message sign (PCMS).  
 D. Low-power (drone) radar transmitter.  
 E. Speed monitor trailers or signs.
9. Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
10. For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

SHEET 3 OF 12

**BARRICADE AND CONSTRUCTION  
WORK ZONE SPEED LIMIT**


**BC (3) - 21**

|       |               |      |      |      |           |
|-------|---------------|------|------|------|-----------|
| FILED | REVISED       | DATE | BY   | JOB  | SHEET NO. |
| TxDOT | November 2002 | 9-07 | 8-14 | 7-13 | 5-21      |

|              |  |               |   |
|--------------|--|---------------|---|
| APPROVED BY: |  | PROJECT NAME: | CR 255<br>RONALD REAGAN BLVD<br>WILLIAMSON COUNTY |
| DATE:        |  | SHEET NAME:   | TRAFFIC CONTROL PLAN                              |
| REVISION:    |  | DRAWN BY:     | MB  |
|              |  | PROJECT NO.:  | 25155   |
|              |  | CITY JOB NO.: |   |
|              |  | SHEET:        | 8 OF 19   |


TXDOT  
STANDARD NOTES & DETAILS  
4 OF 15

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for inaccuracies resulting from the use.




\* When placing skid supports on uneven ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

\*\* When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (width or distance) should not cover the surface of the parent sign.



**STOP/SLOW PADDLES**

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectORIZED when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 8E.03 Hand Signaling Devices in the TMSD.



| SHEETING REQUIREMENTS (WHEN USED AT NIGHT) |        |  |
|--|--------|--|
| USAGE                                      | COLOR  | SIGN FACE MATERIAL                               |
| BACKGROUND                                 | RED    | TYPE B OR C SHEETING                             |
| BACKGROUND                                 | ORANGE | TYPE B <sub>10</sub> OR C <sub>10</sub> SHEETING |
| LEGEND & BORDER                            | WHITE  | TYPE B OR C SHEETING                             |
| LEGEND & BORDER                            | BLACK  | ACRYLIC NON-REFLECTIVE FILM                      |

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better, route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TMSD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC Standard sheets, TLR Standard sheets or the CRZTCO list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.

**GENERAL NOTES FOR WORK ZONE SIGNS**

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMSD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CRZTCO) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

**DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)**

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
  - Long-term stationary - work that occupies a location more than 3 days.
  - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
  - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
  - Short duration - work that occupies a location up to 1 hour.
  - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes).

- SIGN MOUNTING HEIGHT**
- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
  - The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
  - Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
  - Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
  - Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

- SIZE OF SIGNS**
- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

- SIGN SUBSTRATES**
- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CRZTCO lists each substrate that can be used on the different types and models of sign supports.
  - "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
  - All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleats, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

- REFLECTIVE SHEETING**
- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
  - White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
  - Orange sheeting, meeting the requirements of DMS-8300 Type B<sub>10</sub> or Type C<sub>10</sub>, shall be used for rigid signs with orange backgrounds.

- SIGN LETTERS**
- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

- REMOVING OR COVERING**
- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
  - Long-term stationary or Intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
  - Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
  - When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
  - Burlap shall NOT be used to cover signs.
  - Duct tape or other adhesive material shall NOT be affixed to a sign face.
  - Signs and anchor studs shall be removed and holes backfilled upon completion of work.

- SIGN SUPPORT WEIGHTS**
- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
  - The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
  - Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
  - Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
  - Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as fire liner tubes) shall NOT be used.
  - Rubber bolsters designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CRZTCO list.
  - Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
  - Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

- FLAGS ON SIGNS**
- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

SHEET 4 OF 12

Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES**

**BC (4) - 21**

|         |               |      |       |    |       |     |       |       |
|---------|---------------|------|-------|----|-------|-----|-------|-------|
| FILED   | bc-21.dgn     | DATE | 11/07 | BY | 11/07 | APP | 11/07 | 11/07 |
| REVISED | November 2002 | DATE |       | BY |       | APP |       |       |
| 9-07    | 8-14          | DATE |       | BY |       | APP |       |       |
| 7-13    | 5-21          | DATE |       | BY |       | APP |       |       |

**SUN STAR SERVICES, LLC**

400 WIMBERLEY OAKS DRIVE, WIMBERLEY, TX 78676  
PHONE: (512) 618-3150  
EMAIL: LESTELLA@SUNSTARSERVICES.GURU  
TBP REG. NO. F-17453

APPROVED BY:

CR 255

RONALD REAGAN BLVD  
WILLIAMSON COUNTY

TRAFFIC CONTROL PLAN

TXDOT

STANDARD NOTES & DETAILS

5 OF 15

---

DESCRIPTION: PROJECT NAME:


DATE: DRAWN BY: PROJECT NO:

REVISION: MB 25155

CITY JOB NO:


SHEET:  
9 OF 19

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




**SKID MOUNTED WOOD SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



**GROUND MOUNTED SIGN SUPPORTS**

Refer to the CWZTCO and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



**SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS**

\* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

**WEDGE ANCHORS**  
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC111).

**OTHER DESIGNS**  
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCO LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
1. Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
  2. No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCO List.
  3. When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to item 502.
- \* See BC(4) for definition of "Work Duration."
  - \*\* Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
  - See the CWZTCO for the type of sign substrate that can be used for each approved sign support.

SHEET 5 OF 12



**BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT**

BC (5) - 21

|           |               |           |       |           |       |           |       |           |       |
|-----------|---------------|-----------|-------|-----------|-------|-----------|-------|-----------|-------|
| FILED     | bc-21.dgn     | REV       | TxDOT | REV       | TxDOT | REV       | TxDOT | REV       | TxDOT |
| DATE      | November 2002 | DATE      | REV   | DATE      | REV   | DATE      | REV   | DATE      | REV   |
| REVISIONS |               | REVISIONS |       | REVISIONS |       | REVISIONS |       | REVISIONS |       |
| 9-07      | 8-14          | 2007      |       | 2007      |       | 2007      |       | 2007      |       |
| 7-13      | 5-21          |           |       |           |       |           |       |           |       |

DATE: FILE:




|               |   |
|---------------|---|
| APPROVED BY:  | CR 255  |
| PROJECT NAME: | RONALD REAGAN BLVD<br>WILLIAMSON COUNTY                   |
| SHEET NAME:   | TRAFFIC CONTROL PLAN<br>TXDOT<br>STANDARD NOTES & DETAILS |
| DRAWN BY:     | MB  |
| PROJECT NO.:  | 25155   |
| CITY JOB NO.: |   |
| SHEET:        | 10 OF 19  |




DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for inaccuracies resulting from the use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of MHS-8600. A list of pre-qualified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.



CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (B1-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edge line being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.




LOW PROFILE CONCRETE BARRIER (LPCB)

**LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES**

LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

Max. spacing of barrier reflectors is 20 feet. Attach the delineators as per manufacturer's recommendations.




DELINEATION OF END TREATMENTS


**END TREATMENTS FOR CTB'S USED IN WORK ZONES**

End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CRZTCO List for approved end treatments and manufacturers.

**BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS**



Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches.

**WARNING LIGHTS**

- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B<sub>1</sub> or C<sub>1</sub> sheeting meeting the requirements of Departmental Material Specification MGS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

**WARNING LIGHTS MOUNTED ON PLASTIC DRUMS**

- Type A Flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.


**WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS**

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CRZTCO.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for MGS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.

DATE: FILE:

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards shall not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PDM may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

| REQUIREMENTS |              |                               |                             |
|--------------|--------------|-------------------------------|-----------------------------|
| TYPE         | MINIMUM SIZE | MINIMUM NUMBER OF PANEL LAMPS | MINIMUM VISIBILITY DISTANCE |
| B            | 30 x 40      | 13                            | 3/4 mile                    |
| C            | 48 x 96      | 15                            | 1 mile                      |

**ATTENTION**  
Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

**FLASHING ARROW BOARDS**

SHEET 7 OF 12

**TRUCK-MOUNTED ATTENUATORS**

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CRZTCO for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CRZTCO for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.

Texas Department of Transportation  
Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR**

**BC (7) - 21**

|           |            |      |        |      |       |        |             |
|-----------|------------|------|--------|------|-------|--------|-------------|
| FILED     | 02-21, 021 | BY   | TxDOT  | CHK  | TxDOT | DATE   | 02-21, 2002 |
| REVISIONS |            |      |        |      |       |        |             |
| NO.       | DATE       | BY   | REASON | DATE | BY    | REASON |             |
| 1         | 9-02       | 8-14 |        |      |       |        |             |
| 2         | 7-13       | 5-21 |        |      |       |        |             |

**SUN STAR SERVICES, LLC**  
400 WIMBERLEY OAKS DRIVE, WIMBERLEY, TX 78676  
PHONE: (512) 618-5150  
EMAIL: LESTELIA@SUNSTARSERVICES.GURU  
TBPPE REG. NO. F-17453

CR 255  
RONALD REAGAN BLVD  
WILLIAMSON COUNTY

TRAFFIC CONTROL PLAN  
TXDOT  
STANDARD NOTES & DETAILS  
8 OF 15

APPROVED BY: \_\_\_\_\_

DESCRIPTION:

REVISION: \_\_\_\_\_

PROJECT NAME:

DATE: \_\_\_\_\_

SHEET NAME:

DRAWN BY: MB

PROJECT NO:

25155

CITY JOB NO:

SHEET: 12 OF 19

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for inaccuracy resulting from its use.

DATE: FILE:

**GENERAL NOTES**

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

**GENERAL DESIGN REQUIREMENTS**



- Pre-qualified plastic drums shall meet the following requirements:
- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
  - The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 mph or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
  - Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
  - Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
  - The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
  - The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
  - Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footcands of sufficient size to allow base to be held down while separating the drum body from the base.
  - Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
  - Drum body shall have a maximum unballasted weight of 11 lbs.
  - Drum and base shall be marked with manufacturer's name and model number.

**RETROREFLECTIVE SHEETING**

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials," Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


**BALLAST**

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs. minimum and 50 lbs. maximum. The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral drum rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottom so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



**DETECTABLE PEDESTRIAN BARRICADES**

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS)-21 for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



Plywood, Aluminum or Metal sign substrates shall NOT be used on plastic drums

**SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS**

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B<sub>2</sub> or Type C<sub>2</sub> Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch (nominal) nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than one every third drum. A minimum of three (3) should be used on each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12

**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (8) -21**

|                 |            |            |            |             |
|-----------------|------------|------------|------------|-------------|
| FILE: BC-21.dgn | REV: TxDOT | CHK: TxDOT | APP: TxDOT | DATE: TxDOT |
| 4-05 8-14       | 9-07 5-21  | 9-13       |            |             |

**SUN STAR SERVICES, LLC**  
 400 WIMBERLEY OAKS DRIVE, WIMBERLEY, TX 78676  
 PHONE: (512) 618-5150  
 EMAIL: LESTELIA@SUNSTARSERVICES.GURU  
 TBPE REG. NO. F-17453

APPROVED BY: CR 255

PROJECT NAME: RONALD REAGAN BLVD WILLIAMSON COUNTY

SHEET NAME: TRAFFIC CONTROL PLAN

TXDOT STANDARD NOTES & DETAILS

9 OF 15



REVISION: DATE:

DRAWN BY: MB  
 CITY JOB NO:

PROJECT NO: 25155


SHEET: 13 OF 19

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by the State of Texas for any consequences or damages resulting from its use.




- Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
- VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use of VP's for drop-offs.
- VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two-lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
- VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
- Self-righting supports are available with portable bases. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
- Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.

**VERTICAL PANELS (VP's)**




- Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
- The OTLD may be used in combination with 42" cones or VPs.
- Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
- The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B<sub>1</sub> or Type C<sub>1</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.

**OPPOSING TRAFFIC LANE DIVIDERS (OTLD)**



- The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
- Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
- Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
- To be effective, the chevron should be visible for at least 500 feet.
- Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B<sub>1</sub> or Type C<sub>1</sub> conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
- For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

**CHEVRONS**



- LONGITUDINAL CHANNELIZING DEVICES (LCD)**
- LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
  - LCDs may be used instead of a line of cones or drums.
  - LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
  - LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
  - LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
  - LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rolls as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

- WATER BALLASTED SYSTEMS USED AS BARRIERS**
- Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MSHA) crashworthiness requirements based on roadway speed and barrier application.
  - Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
  - Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
  - Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
  - When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

**HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS**

- GENERAL NOTES**
- Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
  - Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
  - Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
  - The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
  - Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
  - Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
  - The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

| Posted Speed | Formula              | Minimum Desirable Taper Lengths (ft.) |            |            | Suggested Maximum Spacing of Channelizing Devices |              |
|--------------|----------------------|---------------------------------------|------------|------------|---|--------------|
|              |                      | 10' Offset                            | 11' Offset | 12' Offset | On a Taper  | On a Tangent |
| 30           | L = $\frac{W^2}{60}$ | 150'                                  | 165'       | 180'       | 30'   | 60'          |
| 35           |                      | 205'                                  | 225'       | 245'       | 35'   | 70'          |
| 40           | L = WS               | 265'                                  | 295'       | 320'       | 40'   | 80'          |
| 45           |                      | 450'                                  | 495'       | 540'       | 45'   | 90'          |
| 50           | L = WS               | 500'                                  | 550'       | 600'       | 50'   | 100'         |
| 55           |                      | 550'                                  | 605'       | 660'       | 55'   | 110'         |
| 60           | L = WS               | 600'                                  | 660'       | 720'       | 60'   | 120'         |
| 65           |                      | 650'                                  | 715'       | 780'       | 65'   | 130'         |
| 70           | L = WS               | 700'                                  | 770'       | 840'       | 70'   | 140'         |
| 75           |                      | 750'                                  | 825'       | 900'       | 75'   | 150'         |
| 80           | L = WS               | 800'                                  | 880'       | 960'       | 80'   | 160'         |
| 85           |                      | 850'                                  | 945'       | 1020'      | 85'   | 170'         |

W=Width of taper (ft.) S=Rate of Offset (ft./s) Posted Speed (MPH)

**SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS**

SHEET 9 OF 12

Texas Department of Transportation Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (9) - 21**

| REV | DATE     | BY | CHK | APP | DESCRIPTION |
|-----|----------|----|-----|-----|-------------|
| 1   | 09-21-09 | MB | MB  | MB  | REVISED     |
| 2   | 09-07-14 | MB | MB  | MB  | REVISED     |
| 3   | 07-13-15 | MB | MB  | MB  | REVISED     |

**SUN STAR SERVICES, LLC**  
 400 WIMBERLEY OAKS DRIVE, WIMBERLEY, TX 78676  
 PHONE: (512) 618-5150  
 EMAIL: LESTELLA@SUNSTARSERVICES.GURU  
 TPPE REG. NO. F-17453

APPROVED BY: \_\_\_\_\_

DESCRIPTION: CR 255

PROJECT NAME: RONALD REAGAN BLVD WILLIAMSON COUNTY

SHEET NAME: TRAFFIC CONTROL PLAN

DATE: \_\_\_\_\_

REVISION: \_\_\_\_\_

DRAWN BY: MB

CITY JOB NO: \_\_\_\_\_

PROJECT NO: 25155

SHEET: 14 OF 19







STANDARD NOTES & DETAILS

TXDOT

10 OF 15

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for inaccuracies or omissions resulting from its use.

- TYPE 3 BARRICADES**
1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCL) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
  2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
  3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn. In detouring, when both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
  4. Striping of rolls, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
  5. Identification markings may be shown only on the back of the barricade rolls. The maximum height of letters and/or company logos used for identification shall be 1".
  6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
  7. Warning lights shall NOT be installed on barricades.
  8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a consistent weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade roll's reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as fire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
  9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.



28" Cones shall have a minimum weight of 9 1/2 lbs.  
42" 2-piece cones shall have a minimum weight of 30 lbs. Including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined in BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.

SHEET 10 OF 12

Texas Department of Transportation  
Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES**

**BC (10) - 21**

|       |               |      |       |      |       |      |       |      |       |
|-------|---------------|------|-------|------|-------|------|-------|------|-------|
| FILED | 06-21-07      | REV  | TxDOT | CHK  | TxDOT | DES  | TxDOT | CON  | TxDOT |
| DATE  | November 2007 | REV  | REV   | DATE | REV   | DATE | REV   | DATE | REV   |
| 9-07  | 8-14          | 7-13 | 5-21  |      |       |      |       |      |       |

**SUN STAR SERVICES, LLC**  
400 WIMBERLEY OAKS DRIVE, WIMBERLEY, TX 78676  
PHONE: (512) 618-5150  
EMAIL: LESTELLA@SUNSTARSERVICES.GURU  
TBBE REG. NO. F-17453

APPROVED BY: \_\_\_\_\_

DESCRIPTION: CR 255

PROJECT NAME: RONALD REAGAN BLVD WILLIAMSON COUNTY

SHEET NAME: TRAFFIC CONTROL PLAN

DATE: \_\_\_\_\_

REVISION: \_\_\_\_\_

DRAWN BY: MB

CITY JOB NO: \_\_\_\_\_

PROJECT NO: 25155

SHEET: 15 OF 19

11 OF 15

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act," no warranty of any kind is made by the State of Texas or any other authority for the accuracy, reliability, or completeness of information of this standard to other formats or for incorrect results or damage resulting from its use.

DATE: FILE:

### WORK ZONE PAVEMENT MARKINGS

#### GENERAL

- The Contractor shall be responsible for maintaining work zone and existing pavement markings, in accordance with the standard specifications and special provisions, on all roadways open to traffic within the CSJ limits unless otherwise stated in the plans.
- Color, patterns and dimensions shall be in conformance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
- Additional supplemental pavement marking details may be found in the plans or specifications.
- Pavement markings shall be installed in accordance with the TMUTCD and as shown on the plans.
- When short term markings are required on the plans, short term markings shall conform with the TMUTCD, the plans and details as shown on the Standard Plan Sheet RZ15PM.
- When standard pavement markings are not in place and the roadway is opened to traffic, DO NOT PASS signs shall be erected to mark the beginning of the sections where passing is prohibited and PASS WITH CARE signs at the beginning of sections where passing is permitted.
- All work zone pavement markings shall be installed in accordance with Item 662, "Work Zone Pavement Markings."

#### RAISED PAVEMENT MARKERS

- Raised pavement markers are to be placed according to the patterns on BC(12).
- All raised pavement markers used for work zone markings shall meet the requirements of Item 672, "RAISED PAVEMENT MARKERS" and Departmental Material Specification DMS-4200 or DMS-4300.

#### PREFABRICATED PAVEMENT MARKINGS

- Removable prefabricated pavement markings shall meet the requirements of DMS-8241.
- Non-removable prefabricated pavement markings (foli back) shall meet the requirements of DMS-8240.


#### MAINTAINING WORK ZONE PAVEMENT MARKINGS

- The Contractor will be responsible for maintaining work zone pavement markings within the work limits.
- Work zone pavement markings shall be inspected in accordance with the frequency and reporting requirements of work zone traffic control device inspections as required by Form 598.
- The markings should provide a visible reference for a minimum distance of 300 feet during normal daylight hours and 160 feet when illuminated by automobile low-beam headlights at night, unless sight distance is restricted by roadway geometrics.
- Markings failing to meet this criteria within the first 30 days after placement shall be replaced at the expense of the Contractor as per Specification Item 662.

#### REMOVAL OF PAVEMENT MARKINGS

- Pavement markings that are no longer applicable, could create confusion or direct a motorist toward or into the closed portion of the roadway shall be removed or obliterated before the roadway is opened to traffic.
- The above shall not apply to detours in place for less than three days, where flaggers and/or sufficient channelizing devices are used in lieu of markings to outline the detour route.
- Pavement markings shall be removed to the fullest extent possible, so as not to leave a discernable marking. This shall be by any method approved by TxDOT Specification Item 677 for "Eliminating Existing Pavement Markings and Markers".
- The removal of pavement markings may require resurfacing or seal coating portions of the roadway as described in Item 677.
- Subject to the approval of the Engineer, any method that proves to be successful on a particular type pavement may be used.
- Blast cleaning may be used but will not be required unless specifically shown in the plans.
- Over-painting of the markings SHALL NOT BE permitted.
- Removal of raised pavement markers shall be as directed by the Engineer.
- Removal of existing pavement markings and markers will be paid for directly in accordance with Item 677, "ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS," unless otherwise stated in the plans.
- Black-out marking tape may be used to cover conflicting existing markings for periods less than two weeks when approved by the Engineer.

### Temporary Flexible-Reflective Roadway Marker Tabs



**STAPLES OR NAILS SHALL NOT BE USED TO SECURE TEMPORARY FLEXIBLE-REFLECTIVE ROADWAY MARKER TABS TO THE PAVEMENT SURFACE**

- Temporary flexible-reflective roadway marker tabs used as guidemarks shall meet the requirements of DMS-8242.
- Tabs detailed on this sheet are to be inspected and accepted by the Engineer or designated representative. Sampling and testing is not normally required, however at the option of the Engineer, either "A" or "B" below may be imposed to assure quality before placement on the roadway.
  - Select five (5) or more tabs at random from each lot or shipment and submit to the Construction Division, Materials and Pavement Section to determine specification compliance.
  - Select five (5) tabs and perform the following test. Affix five (5) tabs at 24 inch intervals on an asphaltic pavement in a straight line, using a medium size passenger vehicle or pickup, run over the markers with the front and rear tires at a speed of 35 to 40 miles per hour, four (4) times in each direction. No more than one (1) out of the five (5) reflective surfaces shall be lost or displaced as a result of this test.
- Small design variances may be noted between tab manufacturers.
- See Standard Sheet RZ15PM for tab placement on new pavements. See Standard Sheet TCF17-11 for tab placement on seal coat work.

#### RAISED PAVEMENT MARKERS USED AS GUIDEMARKS

- Raised pavement markers used as guidemarks shall be from the approved product list, and meet the requirements of DMS-4200.
- All temporary construction raised pavement markers provided on a project shall be of the same manufacturer.
- Adhesive for guidemarks shall be bituminous material hot applied or butyl rubber pad for all surfaces, or thermoplastic for concrete surfaces.

Guidemarks shall be designated as:  
 YELLOW - two amber reflective surfaces with yellow body.  
 WHITE - one silver reflective surface with white body.

| DEPARTMENTAL MATERIAL SPECIFICATIONS                 |          |
|--|----------|
| PAVEMENT MARKERS (REFLECTORIZED)                     | DMS-4200 |
| TRAFFIC BUTTONS                                      | DMS-4300 |
| EPOXY AND ADHESIVES                                  | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS             | DMS-6130 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS            | DMS-8240 |
| TEMPORARY REMOVABLE, PREFABRICATED PAVEMENT MARKINGS | DMS-8241 |
| TEMPORARY FLEXIBLE, REFLECTIVE ROADWAY MARKER TABS   | DMS-8242 |

A list of prequalified reflective raised pavement markers, non-reflective traffic buttons, roadway marker tabs and other pavement markings can be found at the Material Producer List web address shown on BC(1).

SHEET 11 OF 12

|   |            |              |  |
|---|------------|--------------|--|
|   |            |              |  |
| <b>BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS</b> |            |              |  |
| <b>BC(11)-21</b>                                    |            |              |  |
| File:   | bc-21.dgn  | Rev:         | 1  |
| Author:   | TxDOT      | Checked:     | TxDOT  |
| Drawn:  | TxDOT      | Design:      | TxDOT  |
| Checked:  | TxDOT      | Reviewed:    | TxDOT  |
| Date:   | 9-07 5-27  | Scale:       | AS SHOWN                                     |
| Project:  | 1-07 7-13  | Sheet No.:   | 11 OF 12                                     |
| Client:   | 11-07 8-14 | Sheet Title: | BARRICADE AND CONSTRUCTION PAVEMENT MARKINGS |




|               |   |
|---------------|---|
| APPROVED BY:  | CR 255  |
| PROJECT NAME: | RONALD REAGAN BLVD<br>WILLIAMSON COUNTY                   |
| SHEET NAME:   | TRAFFIC CONTROL PLAN<br>TXDOT<br>STANDARD NOTES & DETAILS |
| DRAWN BY:     | MB  |
| PROJECT NO.:  | 25155   |
| CITY JOB NO.: |   |
| REVISION:     | SHEET:<br>16 OF 19  |

DISCLAIMER: This standard is derived by the Texas Engineering Practices Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:

**PAVEMENT MARKING PATTERNS**




Pattern A is the TxDOT Standard, however Pattern B may be used if approved by the Engineer. Prefabricated markings may be substituted for reflectORIZED pavement markings.

**CENTER LINE & NO-PASSING ZONE BARRIER LINES FOR TWO-LANE, TWO-WAY HIGHWAYS**




Prefabricated markings may be substituted for reflectORIZED pavement markings.

**EDGE & LANE LINES FOR DIVIDED HIGHWAY**



Prefabricated markings may be substituted for reflectORIZED pavement markings.


**LANE & CENTER LINES FOR MULTILANE UNDIVIDED HIGHWAYS**



Prefabricated markings may be substituted for reflectORIZED pavement markings.

**TWO-WAY LEFT TURN LANE**

**STANDARD WORK ZONE PAVEMENT MARKINGS DETAILS**



**SHEET 12 OF 12**

Texas Department of Transportation  
Traffic Safety Division Standard

**BARRICADE AND CONSTRUCTION PAVEMENT MARKING PATTERNS**

**BC (12) - 21**









|          |               |       |       |        |        |
|----------|---------------|-------|-------|--------|--------|
| FILE:    | bc-21.dgn     | DATE: | TxDOT | DATE:  | TxDOT  |
| REVISED: | February 1998 | COMP: | SAE1  | JOB:   | HSDMA1 |
| 1-97     | 9-07 5-21     | BY:   |       | CHECK: |        |
| 2-98     | 7-13          | DATE: |       | DATE:  |        |
| 11-02    | 8-14          |       |       |        |        |

Noted: Raised pavement markers used as standard pavement markings shall be from the approved products list and meet the requirements of Item 672 "RAISED PAVEMENT MARKERS."



|               |   |
|---------------|---|
| APPROVED BY:  | CR 255                                  |
| PROJECT NAME: | RONALD REAGAN BLVD<br>WILLIAMSON COUNTY |
| SHEET NAME:   | TRAFFIC CONTROL PLAN                    |
|               | TxDOT                                   |
|               | STANDARD NOTES & DETAILS                |
|               | 13 OF 15                                |
| DRAWN BY:     | MB                                      |
| PROJECT NO.:  | 25155                                   |
| CITY JOB NO.: |   |
| REVISION:     | SHEET:<br>17 OF 19                      |

DISCLAIMER: This standard is developed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the completion of this standard to other formats or for incorrect results or damages resulting from its use.  
  
 DATE: FILE:



- NOTES**
- Where divided highways are separated by median widths at the median opening itself of 30 feet or more, median openings shall be signed as two separate intersections. Each median opening has two width measurements, with one measurement for each approach. The narrow median width will be the controlling width to determine if signs are required. Yield signs are the typical intersection control. Stop signs and stop bars are optional as determined by the Engineer.
  - Install median striping (double yellow centerlines and stop lines/yield lines) when a 50' or greater median centerline can be placed. Stop lines shall only be used with stop signs. Yield lines shall only be used with yield signs.
  - Length of turn bays, including taper, deceleration, and storage lengths shall be as shown on the plans or as directed by the Engineer.


**GENERAL NOTES**

- Edge line striping shall be as shown in the plans or as directed by the Engineer. The edge line should not be placed less than 6 inches from the edge of pavement. This distance may vary due to pavement raveling or other conditions. Edge lines are not required in curb and gutter sections of roadways.
- The traveled way includes only that portion of the roadway used for vehicular travel. It does not include the parking lanes, sidewalks, berms and shoulders. The traveled ways shall be measured from the center of edge line to the center of edge line of a two lane roadway.


**MATERIAL SPECIFICATIONS**

| PAVEMENT MARKERS (REFLECTORIZED)          | DMS-4200 |
|---|----------|
| EPOXY AND ADHESIVES                       | DMS-6100 |
| BITUMINOUS ADHESIVE FOR PAVEMENT MARKERS  | DMS-6130 |
| TRAFFIC PAINT                             | DMS-8200 |
| HOT APPLIED THERMOPLASTIC                 | DMS-8220 |
| PERMANENT PREFABRICATED PAVEMENT MARKINGS | DMS-8240 |

All pavement marking materials shall meet the required Departmental Material Specifications as specified by the plans.



**GUIDE FOR PLACEMENT OF STOP LINES, EDGE LINE & CENTERLINE**  
Based on Traveled Way and Pavement Widths for Undivided Roadways



 Traffic Safety Division Standard

**TYPICAL STANDARD PAVEMENT MARKINGS**

**PM(1)-22**

| FILE  | DATE | BY    | CHK | APP | REV |
|-------|------|-------|-----|-----|-----|
| 11-78 | 8-03 | 6-30  |     |     |     |
| 8-95  | 3-03 | 12-22 |     |     |     |
| 5-00  | 2-12 |       |     |     |     |

|               |   |
|---------------|---|
| APPROVED BY:  | CR 255                                  |
| DESCRIPTION:  | RONALD REAGAN BLVD<br>WILLIAMSON COUNTY |
| PROJECT NAME: | TRAFFIC CONTROL PLAN                    |
| SHEET NAME:   | TxDOT<br>STANDARD NOTES & DETAILS       |
| DRAWN BY:     | PROJECT NO:                             |
| MB            | 25155                                   |
| CITY JOB NO:  |   |
| REVISION:     | SHEET:<br>18 OF 19                      |



|           |       |  |                      |
|-----------|-------|--|----------------------|
| REVISION: | DATE: | DESCRIPTION:   | APPROVED BY:         |
|           |       | PROJECT NAME:<br>RONALD REAGAN BLVD<br>WILLIAMSON COUNTY                 | CR 255               |
|           |       | SHEET NAME:<br>TRAFFIC CONTROL PLAN<br>TXDOT<br>STANDARD NOTES & DETAILS |                      |
|           |       | DRAWN BY:<br>MB  | PROJECT NO:<br>25155 |
|           |       | CITY JOB NO:   |                      |
|           |       | SHEET:<br>19 OF 19   | 15 OF 15             |