

# WILLIAMSON COUNTY, TEXAS CHANGE ORDER NUMBER: 4

DEC 1 1 20

HNTB Corps Round Ro

1. CONTRACTOR: Chasco Constructors		Project: 10WC822
2. Change Order Work Limits: Sta. 1+15 to	Sta. 212+20	Roadway: Chandler 3A
3. Type of Change(on federal-aid non-exempt projects):	Minor (Major/Minor)	Purchase Order Receiv
4. Reasons: 2E, 3F (3 Max In order of	of importance - Primary first)	
5. Describe the work being revised:		DEC 1 2
New or revised plan sheet(s) are attached and numbered     New Special Provisions to the contract are attached:	re runoff from the adjacent field addway due to slopes steeper the ventence. Additional work destricted by the County Engine unity. The new seed mix contais sutilized by the adjacent farmer e Attached to the steep of the steep	s drains into the ROW, adds HNTB COTP an 3:1, and adds a driveway culvert estred by the County. This Change er and changes the application ns a higher concentration of s.
<ol> <li>New Special Provisions to Item N/A No. N/A Special Provisions to Item N/A No. N/A Special Provisions to Item N/A No. N/A N/A No. N/A N/A No. N/A N/A N/A N/A N/A N/A N/A N/A N/A N/A</li></ol>		
The contractor must sign the Change Order and, by doing so, agrees to waive any and all claims for additional compensation due to any and all other expenses, additional changes for time, overhead and profit; or loss of compensation as a result of this change.		ntion must be provided  Days added on this CO: 0
THE CONTRACTOR pate 12/6/12  By Typed/Printed Name CHUCK GLACE  Typed/Printed Title PRES IDENT		
RECOMMENDED FOR EXECUTION:		
Project Manager Date Construction Observer	County Commissi  APPROVED	oner Precinct 1 Date  REQUEST APPROVAL
N/A Design Engineer Date	County Commissi  APPROVED	ioner Precinct 2 Date  REQUEST APPROVAL
Program Manager Date	County Commissi  APPROVED	ioner Precinct 3 Date  REQUEST APPROVAL
Design Engineer's Seal:  N/A	County Commiss  APPROVED	ioner Precinct 4 Date  □ REQUEST APPROVAL
-	2 k	12.19-2012
	APPROVED County	

## WILLIAMSON COUNTY, TEXAS

CHANGE ORDER NUMBER: 4	Project # 10WC822
TARLE A. Form Assessed Miles and Malasinia Discording Chart.	

TABLE A. TOICE	NOODAIN TTOIR AIM MIDIEILAS PLACED IIID STOCK			
	LABOR	HOURLY RATE		HOURLY RATE

LABOR HOURLY RATE		HOURLY RAT

TABLE B:	Contract	Items
----------	----------	-------

				ORIGINAL + PRE	VIOUSLY REVISED	ADD or (DEDUCT)	N	EW	
ITEM	DESCRIPTION	TINU	UNIT PRICE	QUANTITY	ITEM COST	QUANTITY	QUANTITY	ITEM COST	OVERRUN/ UNDERRUN
164-2023	CELL FBR MLCH SEED (PERM)(RURAL)(CLAY)	SY	\$0,45	394,128.00	\$177,357.60	(394,128.00)	0,00	\$0.00	(\$177,357.
164-WC01	DRILL SEEDING (PERM)(RURAL)(CLAY) (WILCO MIX)	SY	\$0,43	0.00	\$0.00	394,128,00	394,128.00	\$169,475.04	\$169,475.
432-2002	RIPRAP (CONC) (5 IN)	CY	\$270.00	0.00	\$0.00	100,00	100.00	\$27,000,00	\$27,000.
432-2044	RIPRAP (STONE COMMON) (DRY) (15 IN)	CY	\$50,00	500,00	\$25,000.00	200,00	700.00	\$35,000,00	\$10,000.
432-2078	RIPRAP (MOW STRIP) (5IN) (CL A) (FIBER)	CY	\$270,00	92.00	\$24,840,00	30,00	122,00	\$32,940,00	\$8,100.
464-2005	RC PIPE (CL III) (24 IN)	LF	\$40.00	0,00	\$0.00	66,00	66,00	\$2,640.00	\$2,640.
467-2288	SET (TY II) (24 IN) (RCP) (6:1) (P)	EA	\$800,00	0.00	\$0.00	2,00	2.00	\$1,600,00	\$1,600.
500-XXX	BARRICADES, SIGNS & TRAFFIC HANDLING	MO	\$1,600.00	18,00	\$28,800.00	1.00	19.00	\$30,400.00	\$1,600.
540-2001	MTL W-BEAM GD FEN (TIM POST)	LF	\$17.00	1,702.50	\$28,942,50	427.00	2,129,50	\$35,201.50	\$7,259.
540-2025	TERM ANCHOR SECTION (DRVY) (SPCL)	EA	\$568.00	0,00	\$0.00	1.00	1.00	\$568.00	\$568.
544-2004	SINGLE GDRAIL TERM (TY 1)	EA	\$1,750.00	10,00	\$17,500.00	1,00	11.00	\$19,250,00	\$1,750
=									
	TOTA	ALS			\$302,440.10			\$355,074,54	\$52,634

## CHANGE ORDER REASON(S) CODE CHART

Design Error or Omission	1A. Incorrect PS&E 1B. Other
2. Differing Site Conditions	2A. Dispute resolution (expense caused by conditions and/or resulting delay)
(unforeseeable)	2B. Unavailable material
1.7×10.1×10×10.1×10×10×10.1×10×4	2C. New development (conditions changing after PS&E completed)
	2D. Environmental remediation
	2E. Miscellaneous difference in site conditions (unforeseeable)(Item 9)
	2F. Site conditions aftered by an act of nature
	2G. Unadjusted utility (unforeseeable)
	2H. Unacquired Right-of-Way (unforeseeable)
	21. Additional safety needs (unforeseeable)
	2J. Other
3. County Convenience	3A. Dispute resolution (not resulting from error in plans or differing site conditions)
	3B. Public relations improvement
	3C. Implementation of a Value Engineering finding
	3D. Achievement of an early project completion
	3E. Reduction of future maintenance
	3F. Additional work desired by the County
	3G. Compliance requirements of new laws and/or policies
	3H. Cost savings opportunity discovered during construction
	31. Implementation of improved technology or better process
	3J. Price adjustment on finished work (price reduced in exchange for acceptance)
	3K. Addition of stock account or material supplied by state provision
	3L. Revising safety work/measures desired by the County
	3M. Other
4. Third Party Accommodation	4A. Failure of a third party to meet commitment
54	4B. Third party requested work
	4C. Compliance requirements of new laws and/or policies (impacting third party)
	4D. Other
5. Contractor Convenience	5A. Contractor exercises option to change the traffic control plan
	5B. Contractor requested change in the sequence and/or method of work
	5C. Payment for Partnering workshop
	5D. Additional safety work/measures desired by the contractor
	5E. Other
6. Untimely ROW/Utilities	6A. Right-of-Way not clear (third party responsibility for ROW)
	6B. Right-of-Way not clear (County responsibility for ROW)
	6C. Utilities not clear
	6D. Other

#### Williamson County Road Bond Program

#### Chandler Road, Phase 3A Williamson County Project No. 10WC822

#### Change Order No. 4

#### Reason for Change

This Change Order adds erosion control measures, guardrail and a driveway culvert pipe due to miscellaneous differences in site conditions and revises the seed mixture and application method to be used on the project.

Additional erosion control measures are needed to address locations where runoff from the adjacent field drains into the County ROW. The additional measures include both rock and concrete riprap protection to minimize erosion and reduce future maintenance. Also, additional guardrail is required from Sta. 63+50 to 68+20 along the north side of the roadway to protect from side slopes steeper than 3:1. The addition of guardrail requires adding a concrete riprap mow strip, a single guardrail terminal and a driveway terminal anchor. A culvert pipe will also be added under Driveway O at Sta. 205+96 to minimize ponding at this location.

The seed mixture type and application method has been revised per direction of the County Engineer to a custom County seed mix and will be drilled seeded, generating a cost savings to the County. The new County seed mixture will include a higher concentration of Bermuda grass seed and is much more resistant to the herbicides utilized by the adjacent famers. Drill seeding tills the seed into the soil and will prevent the seed from drying out as quickly during establishment.

Following is a summary of new items required for this Change Order:

Item	Description	Unit	Qty
164-WC01	DRILL SEEDING (PERM) (RURAL) (CLAY) (WILCO MIX)	SY	394,128
432-2002	RIPRAP(CONC) (5IN)	CY	100
464-2005	RC PIPE (CL III) (24IN)	LF	66
467-2288	SET (TY II) (24 IN) (RCP) (6:1) (P)	EA	2
540-2025	TERMINAL ANCHOR SECTION (DRWY) (SPCL)	EA	1

This Change Order results in a net increase of \$51,034.44 to the Contract amount, for an adjusted Contract amount of \$7,015,901.05. The original contract amount was \$6,654,874.15. As a result of this and all Change Orders to-date, \$451,026.90 has been added to the Contract resulting in a 6.8% net increase in the contract cost. No

additional days will be added to or deducted from the Contract as a result of this Change Order.

### **HNTB** Corporation

James Klotz, P.E.




# Change Proposal Unit Cost Pricing Sheet Chandler Rd 3A Chasco Project No:10182 13 September 2012

Chasco CP No:	CP 005 - Drill Seed		
		Prepared by:	Kellin Neiman
Description:	Deduct for Drill Seed with new County specified mix in lieu of txdot appro	oved hydromulch mlx.	

ITEM	Cost code		QTY	UNIT	UNIT PRICE	TOTAL
10	164-2023	CELL FBR MLCH SEED (PERM) (RURAL) (CLAY) DRILL SEED	(394,128.00) 394,128.00	SY	\$0.45 \$0.43	\$169,475.04
					TOTAL	(\$7,882.56)

Exclusions: Anything not specifically listed above.

Qualifications: This a unit price proposal. Final billing will be based on installed quantities. Mix includes 24lbs/acre oats, 34lbs/acre of wheat, 25lbs/acre un-hulled bermuda, 25lbs/acre hulled bermuda as specified by County. Price includes fertilizer placed at a rate of 605LBS/ACRE per the job manual, subgrade prep and watering.



**VPPROVED**