

REQ 110238



Proposal

[Phone: 512.929.7090 | 1720 Royston Lane, Round Rock, TX 78664 | TACLA021308C | TACLA0020760C | M-18971 | TECL 29725]

Date: October 6, 2016

Proposal Number: 2016-11876

TXMAS-15-03FAC01

Customer: Williamson County

Attention: Toby Bonnet

Location: Williamson Jail House
306 W 4th Street
Georgetown, TX

Email: tbonnet@wilco.org
Phone: 512-654-1495

Project Name: Water Leak Repair and Mixing Valve Install

Scope of Work:

- Mtech will replace approximately 10' of 4" copper to repair a leak on a 4" 90 in boiler room
- WE WILL ISOLATE LINE AT BUTTERFLY VALVES, CUT OUT A SECTION BEFORE HANGERS AND INSTALL TWO PRO PRESS COUPLINGS AND A NEW PRO PRESS 90
- This price also includes an additional thermostat for the second boiler
- We will install (owner provided) 2" Leonard valve with bypass
- This is a high low flow system has to be installed to the manufacturer spec with balancing valves
- Once it installed we have to set the valve in both low flow and high flow solutions
- To check low flow we will probably have to do that after hours when low flow conditions exist

Includes:

- Tstat, valves, pipes, fittings and labor
- Some of the labor is built in for after hours

Exclusions: Existing condition of pipe and valves

Quoted Price **\$16,750.00 (excluding tax)**

Prepared by:

Paul Wilson

Email: paul.wilson@csusa.us

Phone: 512-680-2878