WILLIAMSON COUNTY, TEXAS CHANGE ORDER NUMBER: 2

1. CONTRACTOR: Champion Infrastructure		Project:	1907-333
2. Change Order Work Limits: Sta. N/A to	Sta. N/A	Roadway:	O'Connor Traffic
2. Change Order Work Limits. Sta. N/A IC	Sta. N/A	Roadway.	Signals
Type of Change(on federal-aid non-exempt projects):	Minor (Major/Minor)	CSJ Number:	1
4. Reasons: 2E (3 Max In order	of importance - Primary first)	, vaniber:	
Describe the work being revised:			
2E: Differing Site Conditions (unforeseeable). Miscellaned Order changes the method of construction from directional boring roadway for the signals at the intersection of O'Connor Drive are the designer changed the conduit from 2 - 3 inch and 1 - 2 inch Force Account item to pay for off-duty police officers and vehicle Oaks and Morgan Hill intersections.	ng to open trenching for the ins and Great Oaks Drive. To accort conduits to 4 - 2 inch conduits	tallation of condu nmodate the ope . This Change O	its under the existing on cut trench method, order also adds a new
Work to be performed in accordance with Items: Se	ee attached.		
 New or revised plan sheet(s) are attached and numbere 	d: N/A		
8. New Special Provisions/Specifications to the contract ar		s 🗵 N	0
9. New Special Provisions to Item_N/A_No. No. N/A_, Special Sp	pecification Item N/A are attac	ched.	
Each signatory hereby warrants that each has the authority	to execute this Change Ord	er (CO).	
The contractor must sign the Change Order and, by doing so, agrees to waive	The following Inform	ation must be	provided
any and all claims for additional compensation due to any and all other expenses; additional changes for time, overhead and profit; or loss of compensation as a result of this change.	Time Ext. #: N/A	Days added o	n this CO:0
THE CONTRACTOR Date 9/27/2020	Amount added by this cha	inge order:	\$33,656.00
Maury Digitally signed			
By Milliorn Date: 2020.09.28 Oscillation Date: 2020.09.28			
Maury Milliorn			
Typed/Printed Name			
Typed/Printed Title Project Manager			
Typed Title			
RECOMMENDED FOR EXECUTION:			
	County Commiss	ioner Precinct	l Date
185 DE 9/28/20	□ APPROVED		JEST APPROVAL
Project Manager Date	L AFFROVED	L REQU	DEST AFFROVAL
	County Commiss	ioner Precinct 2	2 Date
N/A	□ APPROVED		JEST APPROVAL
Design Engineer Date			
11/11/			
9/29/2020	County Commiss		
Program M nager Date	□ APPROVED	□ REQU	JEST APPROVAL
Program Whager Date			
Design Engineer's Seal:			
	County Commiss		
	□ APPROVED	□ REQU	JEST APPROVAL
	Bill It	Hur	10/6/202
	County APPROVED	Judge	Date

WILLIAMSON COUNTY, TEXAS

	CHANGE ORDER NUMBER:	2	Project #	1907-333
--	----------------------	---	-----------	----------

TABLE A: Force Account Work and Materials Placed into Stock

LABOR	HOURLY RATE		HOURLY RATE	

TABLE B: Contract Items:

				ORIGINAL + PREVIOUSLY REVISED		ADD or (DEDUCT)	NEW		
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	ITEM COST	QUANTITY	QUANTITY	ITEM COST	OVERRUN/ UNDERRUN
618-6047	CONDT (PVC) (SCH 80) (2")(BORE)	LF	\$30.00	710.00	\$21,300.00	(300.00)	410.00	\$12,300.00	(\$9,000.00)
618-6054	CONDT (PVC) (SCH 80) (3")(BORE)	LF	\$40.00	1,250.00	\$50,000.00	(600.00)	650.00	\$26,000.00	(\$24,000.00)
618-WC01	CONDT (PVC) (SCH 80) (2")(OPEN CUT) FOR GREAT OAKS (INCL. TRAFFIC CONTROL)	LF	\$48.88	0.00	\$0.00	1,200.00	1,200.00	\$58,656.00	\$58,656.00
999-WC03	FORCE ACCOUNT - OFF DUTY POLICE OFFICER	DOL	\$1.00	0.00	\$0.00	8,000.00	8,000.00	\$8,000.00	\$8,000.00
		1							
		1							
	TOTALS	1			\$71,300.00			\$104,956.00	\$33,656.00

CHANGE ORDER REASON(S) CODE CHART

Design Error or Omission	1A. Incorrect PS&E 1B. Other
Differing Site Conditions (unforeseeable)	2A. Dispute resolution (expense caused by conditions and/or resulting delay) 2B. Unavailable material 2C. New development (conditions changing after PS&E completed) 2D. Environmental remediation 2E. Miscellaneous difference in site conditions (unforeseeable)(Item 9) 2F. Site conditions altered by an act of nature 2G. Unadjusted utility (unforeseeable) 2H. Unacquired Right-of-Way (unforeseeable) 2I. Additional safety needs (unforeseeable) 2J. Other
3. County Convenience	3A. Dispute resolution (not resulting from error in plans or differing site conditions) 3B. Public relations improvement 3C. Implementation of a Value Engineering finding 3D. Achievement of an early project completion 3E. Reduction of future maintenance 3F. Additional work desired by the County 3G. Compliance requirements of new laws and/or policies 3H. Cost savings opportunity discovered during construction 3I. Implementation of improved technology or better process 3J. Price adjustment on finished work (price reduced in exchange for acceptance) 3K. Addition of stock account or material supplied by state provision 3L. Revising safety work/measures desired by the County 3M. Other
4. Third Party Accommodation	 4A. Failure of a third party to meet commitment 4B. Third party requested work 4C. Compliance requirements of new laws and/or policies (impacting third party) 4D. Other
5. Contractor Convenience	 5A. Contractor exercises option to change the traffic control plan 5B. Contractor requested change in the sequence and/or method of work 5C. Payment for Partnering workshop 5D. Additional safety work/measures desired by the contractor 5E. Other
6. Untimely ROW/Utilities	 6A. Right-of-Way not clear (third party responsibility for ROW) 6B. Right-of-Way not clear (County responsibility for ROW) 6C. Utilities not clear 6D. Other

Williamson County Road Bond Program

O'Connor Traffic Signals Williamson County Project No. 1907-333

Change Order No. 2

Reason for Change

This Change Order changes method of construction from directional boring to open trenching for the installation of conduits under the existing roadway at the intersection of O'Connor Drive and Great Oaks Drive. This change in the method of construction was necessary due to the location of existing utilities within the right of way and in the roadway. To accommodate the open trenching method, the designer changed the conduit from 2-3 inch and 1-2 inch conduits to 4-2 inch conduits. The conduit run equals approximately 300 feet and this change order adds an additional 2 inch run to the project, totally 1,200 linear feet.

This Change Order also adds a new Force Account item to pay for off-duty police officers and vehicles used for traffic control during open trenching operations at the intersections of O'Connor Drive and Great Oaks Drive and O'Connor Drive and Morgan Hill Drive.

Following is a summary of the new item required for this Change Order:

ITEM	DESCRIPTION	QTY	UNIT
618-WC01	CONDT (PVC) (SCH 80) (2") (OPEN CUT) FOR GREAT OAKS (INCL. TRAFFIC CONTROL)	1,200	LF
999-WC03	FORCE ACCOUNT - OFF DUTY POLICE OFFICER	8,000	DOL

This Change Order results in an increase of \$33,656.00 to the Contract amount, for an adjusted Contract total of \$906,842.54. The original Contract amount was \$853,503.50. Because of this and all other Change Orders, a total of \$53,339.04 has been added to the Contract, resulting in a 6.25% net increase in the Contract cost. No additional days will be added to or deducted from the Contract as a result of this Change Order.

HNTB Corporation

James Klotz, P.E.



COUNTY: WILLIAMSON PROJECT: 1907-333

C-S-J:

HWY: O'CONNOR DRIVE

JOB #: 190814

FIELD CHANGE: CONDUIT - ROADWAY TRENCH (Great Oaks Dr)

ITEM #	DESCRIPTION	UNIT	ORIGINAL QUANTITY	FC QUANTITY	NEW TOTAL QUANTITY	UNIT PRICE	AMOUNT
618-6047	CONDUIT (PVC) SCH 80 (2") BORE	LF	300.00	-300.00	0.00	\$30.00	-9,000.00
618-6054	CONDUIT (PVC) SCH 80 (3") BORE	LF	600.00	-600.00	0.00	\$40.00	-24,000.00
618-xxxx	CONDUIT (PVC) SCH 80 (2") ROADWAY	LF		1,200.00	1,200.00	\$48.88	58,656.00
							-

FIELD CHANGE AMOUNT:	25,656.00

DATE:

16-Sep-20

NOTES:

INCLUDES:

Removal of existing Sidewalk and Concrete Curb & Gutter as necessary for Conduit Installation.

Stabilized Trench Backfill with "temporary" surface treatment.

Traffic Control

EXCLUDES:

Off-Duty Officers for Traffic Control Assistance.

Replacement of Sidewalk and Concrete Curb & Gutter.

Permanent surface treatment repairs (HMAC).

Striping.



 COUNTY:
 WILLIAMSON
 DATE:
 16-Sep-20

 PROJECT:
 1907-333
 ITEM:
 618

 CSJ NO:
 QTY:
 1

CHAMPION JOB NO: 190814 DESC: CONDUIT - ROADWAY TRENCH

FIELD CHANGE: OPEN TRENCH CONDUIT - ROADWAY (O'Connor Dr @ Great Oaks Dr)

PR	ICING BREAKDOWN	1				
MATERIAL	QUANTITY	UNIT		COST		AMOUNT
Attached Sheet	1	LS	\$	4,063.32	\$	4,063.32
Subtotal					\$	4,063.32
15% Compensation Total Material					\$	609.50
Total Material					\$	4,672.82
LABOR	HOURS	REG/OT		ER. RATE		AMOUNT
Foreman	136	REG	\$	27.00	\$	3,672.00
Foreman Utility Laborer/Operator	34	OT	\$	40.50	\$	1,377.00 2.584.00
Utility Laborer/Operator	136 34	REG OT	\$	19.00 28.50	\$	2,584.00
Utility Laborer/Operator	136	REG	\$	13.00	\$	1,768.00
Utility Laborer/Operator	34	OT	\$	19.50	\$	663.00
Common Laborer (1)	136	REG	\$	10.50	\$	1,428.00
Common Laborer (1)	34	OT	\$	15.75	\$	535.50
, ,	<u> </u>	<u> </u>	Ť		_	
Raw Labor					\$	12,996.50
55% Insur. & Taxes					\$	7,148.08
Labor Sub-Total					\$	20,144.58
15% Compensation					\$	3,021.69
Total Labor					\$	23,166.26
EQUIPMENT			A۱	/ER RATE		AMOUNT
Pickup (1-Ton) - Diesel	136	HRS	\$	22.33	\$	3,036.88
Pickup (1-Ton) - Diesel	136	HRS	\$	22.33	\$	3,036.88
Trailer (14 K-GVWR)	40	HRS	\$	2.97	\$	118.80
Trailer (7 K-GVWR), W/Water Tank	136	HRS	\$	2.73	\$	371.28
Skid Steer (Bobcat) - (Cat-Trax Rental) - Weekly Rate	3	WKS	\$	1,050.52	\$	3,151.56
Rocksaw (Cat-Trax Rental) - Weekly Rate	2	WKS	\$	1,638.46	\$	3,276.92
Excavator & Hammer (Cat-Trax Rental) - Weekly Rate	3	WKS	\$	1,618.93	\$	4,856.79
Dump Trailer (14K-GVWR)	136	HRS	\$	2.97	\$	403.92
Cut-Off Saw (14") - (Gas Powered) - Daily Rate	17	DAY	\$	30.00	\$	510.00
Traffic Control (Signs, Stands, Cones, Barricades)	17	DAY	\$	150.00	\$	2,550.00
Traffic Control (Arrowboards - 2) Miscellaneous (Generator, Pavement Breaker, Etc)	10 17	DAY	\$	151.55 75.00	\$	1,515.50 1,275.00
		D/(I	Ť	70.00	Ψ	,
Sub Total					\$	24,103.53
15% Compensation Total Equipment					\$	3,615.53 27,719.06
Total Equipment					φ	27,719.00
SUBCONTRACTORS			۱U	NIT PRICE		AMOUNT
					\$	-
Sub Total	+	+	1		\$	-
15% Compensation		1			\$	-
Total Subcontractor					\$	-
MICOSTILANISOLIO						
MISCELLANEOUS Lodging	0	DAV	\$	150.00	¢.	1,200.00
Per Diem	8 11	DAY DAY	\$	90.00	\$	990.00
i or blotti	11	אלו	Ψ	30.00	Ψ	990.00
Sub Total					\$	2,190.00
15% Compensation					\$	328.50
Total Miscellaneous			1		\$	2,518.50
ITEM SUB-TOTAL	1		1		\$	58,076.64
BOND PREMIUM					\$	580.77
FIELD CHANGE ITEM TOTAL	 	1			\$	58,657.41
ITEM	QUANTITY	UNIT	1.16	NIT PRICE	φ	58,657.41 AMOUNT
CONDUIT - ROADWAY TRENCH	QUANTITY 1	UNIT	\$	58,657.41	\$	58,657.41

TAKE-OFF DETAIL

OPEN TRENCH - GREAT OAKS DR

LOCATION:	Mobilize Equip	Mobilize Material	Discovery & Pot-Hole	Remove Curb/Gutter	Traffic Control	Roadway Trench	Extend Conduits	Clean-Up Spoils	Travel	Task Days
O'Connor @ Great Oaks Drive	0.5	0.5	2	1.5	2	6	3	1	0.5	17
	0.5 CREW DAYS	0.5 CREW DAYS	2 CREW DAYS	1.5 CREW DAYS	2 CREW DAYS	6 CREW DAYS	3 CREW DAYS	1 CREW DAYS	0.5 CREW DAYS	

CREW DAYS 17



 COUNTY:
 Williamson
 DATE:
 16-Sep-20

 PROJECT:
 1907-333
 ITEM:
 999-WC01

 CSJ NO:
 1907-333
 QTY:
 1 LS

CHAMPION JOB NO: 190814 DESC: CONDUIT - ROADWAY TRENCH

MATERIALS:

PRICING BREAKDOWN									
MATERIAL DESCRIPTION	QUANTITY	UNIT		COST		AMOUNT			
Stabilized Backfill - Temporary (Granite Gravel)	3	CY	\$	49.31	\$	147.93			
Fill Sand	12	CY	\$	47.50	\$	570.00			
Concrete Backfill - Quikrete Mix	180	BAG	\$	4.23	\$	761.40			
Asphalt Repair - Temporary	40	BAG	\$	14.89	\$	595.60			
Topsoil	3	CY	\$	28.20	\$	84.60			
Conduit, 2" Sch 80	1320	LF	\$	0.91	\$	1,201.20			
90 Degree Bend, 2" Sch 80	32	EA	\$	3.79	\$	121.28			
45 Degree Bend, 2" Sch 80	13	EA	\$	3.09	\$	40.17			
Coupling, 2"	90	EA	\$	0.46	\$	41.40			
Bell End, 2"	32	EA	\$	2.07	\$	66.24			
Solvent/Cement	6	QT	\$	7.00	\$	42.00			
Duct Tape	2	ROLL	\$	7.00	\$	14.00			
Plywood (4' x 8' x 3/4") Sheets	8	EA	\$	25.00	\$	200.00			
Sand Bags (Filled)	50	EA	\$	3.55	\$	177.50			
			М	ATERIALS	\$	4,063.32			

