



Guaranteed Maximum Price Proposal

For



- **Wilco Headquarters**
- **Bid Package #3 - Revision 3**
- **Project Number P577**
- **August 1st, 2024**



Guaranteed Maximum Price Proposal

Wilco HQ

Bid Package #3

Revision #3

For



August 1st, 2024

TABLE OF CONTENTS

Tab 1:	Exhibit A – GMP Proposal	Pg.1-3
Tab 2:	Executive Project Summary	Pg.4
Tab 3:	Project Team	Pg.5-22
Tab 4:	List of Documents	Pg.23-47
Tab 5:	Qualifications and Value Engineering	Pg.48-174
Tab 6:	GMP Proposal Cost Breakdown	Pg.175-244
Tab 7:	Master Project Schedule (Summary Level)	Pg.245-252



Exhibit A – GMP Proposal

GUARANTEED MAXIMUM PRICE PROPOSAL
Williamson County Headquarters Project
Bid Package 3 – Building

Chasco Constructors, Ltd. L.L.P. (“CMAR”) hereby submits to Williamson County, Texas (“County”) for the use and benefit County pursuant to the provisions of the Contract for Construction Manager-at-Risk Project Delivery dated 12/14/2022 (“Contract”), a Guaranteed Maximum Price (“GMP”) proposal for Bid Package 3 – Building for the **Williamson County Headquarters Project** (“Project”), based on the Contract Documents (as defined by the Contract) developed for the Project, as follows:

Cost of the Work.

A not-to-exceed amount for the Cost of the Work for Bid Package 3 – Building pursuant to the Contract:

Sixty-Three Million Thirty-Eight Thousand Two Hundred Twenty-Four Dollars
(\$ 63,038,224.00)

CMAR’s Fee.

A fixed sum fee for CMAR’s Fee for Bid Package 3 – Building pursuant to the Contract:

Five Million Six Hundred Twenty-Three Thousand and Ten Dollars
(\$ 5,623,010.00)

Total GMP.

The total sum of the above **Items 1 through 2**, as set forth below, is the GMP which the CMAR hereby guarantees to County for providing Bid Package 3 – Building complete, in place and operational in accordance with the Contract Documents (All attached breakdowns shall total this GMP amount).

Sixty-Eight Million Six Hundred Sixty-One Thousand Two Hundred Thirty-Four Dollars
(\$ 68,661,234.00)

CMAR hereby guarantees to County not to exceed the above referenced GMP amount, subject to additions or deductions as provided in the Contract Documents. Except for additions or deductions as provided in the Contract Documents, costs which would cause such GMP to be exceeded shall be paid by CMAR without reimbursement by County.

Contract Time.

The date for achieving Substantial Completion of Bid Package 3 – Building shall be **Three Hundred Thirty (330) calendar days** from the Notice to Proceed with construction.

Withdrawal of GMP Proposal.

This GMP Proposal may not be withdrawn for a period of **ninety (90) calendar days** from the date of receipt by County.

Liquidated Damages.

CMAR further agrees to pay, as Liquidated Damages, to County the sum of **Seven Hundred Fifty (\$750.00) per calendar day** for failure to complete the work for the Bid Package 3 – Building within the Contract Time in accordance with the Contract.

Owner's Contingency.

A not-to-exceed amount for the Owner's Contingency stated herein for reference:

Three Million Four Hundred Thirty-Three Thousand and Sixty-Two Dollars
(\$ 3,433,062.00)

CMAR and County have agreed to separately phase out various scopes of the construction services of Project and execute this Guaranteed Maximum Price Proposal as to only the Bid Package 3 – Building phase of construction services so that such phase of construction can be commenced and completed on or before the Substantial Completion date set out in this Guaranteed Maximum Price Proposal. CMAR and County hereby acknowledge that Bid Package 3 – Building includes the remainder of scope of construction services for the entire Project following execution of this Guaranteed Maximum Price Proposal. CMAR acknowledges and agrees that the remainder scope of construction for the Project shall not constitute changes in the Work and there should be no adjustment under Sections 5.1.2 or 5.1.3 of the Contract to increase CMAR's Fee percentage that is set forth under Section 5.1.1 of the Contract. Furthermore, the preconstruction phase compensation set forth under Section 4.1.1 of the Contract shall not be changed or modified due to any phasing of the construction services.

All terms and conditions of the Contract are hereby adopted and incorporated into this GMP Proposal. Any exceptions to, or modifications of, the terms and conditions of the Contract shall not be effective unless they are expressly stated and conspicuously identified in this GMP Proposal and are specifically accepted and approved by County.

Otherwise, proposed revisions or modifications to the language, terms, or conditions of the Contract will not be accepted.

BY SIGNING BELOW, CMAR and County have executed and bound themselves to this Guaranteed Maximum Price (GMP) Proposal for Bid Package 3 – Building.

CMAR:

Chasco Constructors, Ltd., L.L.P.

By: _____

Signature

Charles King

Printed Name

Vice President and CFO

Title

COUNTY:

Williamson County, Texas

By: Bill Gravell (Aug 6, 2024 10:25 CDT)

Signature

Bill Gravell

Printed Name

County Judge

Title

Date Signed: August 01, 2024

Date Signed: Aug 6, 2024, 20



Executive Project Summary

TAB 2 - Executive Project Summary

Project Summary

The project consists of a new 120,224 sf 3-story Class A headquarters facility which will consolidate county administrative and business operations in a single modern facility that will support county governance for the foreseeable future. The Structure will have a cast in place concrete foundation and structural steel with a glass curtain wall and masonry exterior for floors one, two and three, a PVC roof, state of the art MEP and Special Systems, high level interior finishes and all associated site work and utilities. The project will be located in Georgetown, Texas.

Schedule

Notice to Proceed is expected to be issued on or about August 6th, 2024.

Substantial Completion of this Bid Package #3 is expected by December 1st, 2025 and Final Completion December 31st, 2025.





Project Team

TAB 3 – Project Team

Chasco's project team is as follows:

Bill Bambrick – Vice President, Sr. Project Manager – Primary Management Contact
Office: 512-244-0600 x 122
Cell: 512-848-3327
Email: bill@chasco.com

Bill Paetznick – Sr. Project Manager
Office: 512-244-0600
Cell: 512-948-1830
Email: bill.p@chasco.com

Mark Lee – Project Superintendent
Office: N/A
Cell: 512-992-5863
Email: mark.lee@chasco.com

Scott Badgett – Vice President, Pre-Construction Manager/Estimating Support
Office: 512-244-0600 x 111
Cell: 512-844-6395
Email: scott@chasco.com

Rick Risener – Chief Civil Estimator/Estimating Support
Office: 512-244-0600 x 134
Cell: 512-848-3342
Email: rick@chasco.com

Jonathan Escalante – Safety Director
Office: 512-244-0600 x 135
Cell: 512-848-3636
Email: jonathan@chasco.com

Chuck Glace – President/Executive Support
Office: 512-244-0600 x 118
Cell: 512-848-3315
Email: chuck@chasco.com

Charles King – Vice President/CFO/Executive Support
Office: 512-244-0600 x 132
Cell: 512-431-6343
Email: charlesk@chasco.com

Craig Hunter, CPA – Controller/Accounting Support
Office: 512-244-0600 x 114
Cell: 512-964-8447
Email: craig.hunter@chasco.com

Resumes are attached



Wilco Headquarters Project

Project Design Team
GarzaEMC, LLC. – Engineer
MarmonMok - Architect

Construction Manager
Chasco Constructors
Round Rock, TX

Executive Support
Chuck Glace, President
Charles King, Vice President & CFO
Craig Hunter, CPA Controller

Pre-Construction Team
Manager of Pre-Construction Services
Building Estimator
Scott Badgett
Civil Estimator
Rick Risener

- Estimates
- Budget
- Schedule
- Value Management
- Staging / Logistics
- Identify / Purchase Long-lead Items
- Pre-qualify Subcontractors
- Evaluate Constructability Issues

Construction Team
Project Manager
Bill Bambrick
Bill Paetznick
Project Superintendent
Mark Lee
Safety Director
Jonathan Escalante

Subcontractors / Suppliers

- Site Management
- Schedule
- Cost Control
- Safety
- Punch List



RESUMÉ



Bill Bambrick

VP & Senior Project Manager

Education

Drake University 1976

University of Houston 1977

Austin Community College 1987

Work History and Background

Bill has over 45 years in the construction industry spending the last 34 years with Chasco Constructors. As Vice President and Senior Project Manager Bill has extensive experience in all areas of construction including commercial and industrial buildings, Class A office, site work, utilities, bridges, roads & heavy/highway and airport work. He is very experienced with alternative delivery methods including CMR and Design/Build.

Project Experience

- The Wilco Annex is a two story 60,000 SF office building for Williamson County, TX. The building is situated on a sloping site of very fat clay, so the slab was constructed as a structural pan slab with drilled piers with a perimeter grade beam to provide a voided crawl space. The two-story building is structural steel, the second floor is concrete on metal decking. The exterior of the building is finished with several different types of materials. There are two machine room-less elevators. The JP courtroom includes the judge's bench, jury seating, court reporter and witness stand along with full gallery seating. Included in the building are many areas that required high security with a wide assortment of protection, identification, surveillance and detection devices to ensure the safety of County employees and visitors. Chasco self-performed all site work, utilities and concrete work and the project was completed on schedule and under budget.



- Celebration Church is a new 90,000 SF church recently constructed in Georgetown, TX. The facility has large childcare wing of 60,000 SF. The remaining 30,000 SF of the building includes the narthex (entry/ vestibule) and a "bistro style" coffee service area that also serves premade snack items. The sanctuary accommodates seating for over 2,600 guests and incorporates a state-of-the-art audio/visual system. The project had a 13-month schedule, but was completed early, in 12 months, despite having over 40 rain days.



- Lexus of Lakeway, Austin, TX - The Lexus of Lakeway project was an extremely high-end car dealership built in Lakeway, Texas. This is the first car dealership allowed to be built within the City of Lakeway. The \$21 million project consisted of a three-level main building of 86,000 SF, an 11,000 SF carwash/make ready building and all the associated site work.



RESUMÉ (continued)

Bill Bambrick, VP & Senior Project Manager

- Chasco Family YMCA, Round Rock: 18,160 sf masonry and structural steel facility including an eight-lane junior Olympic indoor pool, therapy pool, hot tub, lazy river, vortex pool, water slide, splash pad, sauna, locker rooms with showers, family changing rooms and a 2,800-sf operable skylight. The project included demolition of a portion of the existing building while the remaining facility was operational.



- Georgetown Recreation Center, Georgetown, TX: 67,952 SF of new construction and renovation to the exiting occupied and fully operational Rec. Center. Scope of work included a gymnasium, multi-purpose & meeting rooms, elevated track, indoor & outdoor pools with water features, restroom & shower facilities, site utilities, detention pond and concrete construction. CM-at-Risk delivery.



- Round Rock YMCA Gymnasium, Round Rock, TX: A 7,437 sf masonry and structural steel facility including full court and half court basketball goals, volleyball court and elevator. Total estimated project cost is \$1.2 Million. CM-at-Risk delivery.



- Twin Lakes YMCA, Cedar Park: A 36,400 sf tilt wall and structural steel facility including a gymnasium, work out facilities, locker rooms with showers, daycare, administrative offices and meeting rooms. The project also included an outdoor “fun pool” with many water features and a pool house. Parking facilities for the YMCA were simultaneously constructed under a separate contract with Williamson County. Combined project cost was \$5.3 Million. CM-at-Risk delivery.



- Hutto Family YMCA, Hutto, Texas: Chasco Constructors was the Construction Manager for the construction of the 30,000 sf Hutto Family YMCA facility in Hutto, Texas. The project consists of a natatorium, locker rooms, work out and aerobics areas as well as offices. Chasco provided a complete pre-construction program for this project to assist the YMCA and the City of Hutto with budgeting and constructability management in order to maximize the City's budget while allowing the project to achieve all of the original programming goals for both the City and the YMCA.



References

Mr. Jeff Andresen, CEO
YMCA of Greater Williamson County
512-801-7736

Ms. Susan McFarland, AIA
Susan McFarland, Architect
512-288-3001

Ms. Barbara Garrett
Garrett Consulting Services
615-394-4977

Tony Prete, PE
Waeltz & Prete, Inc.
512-505-8953

RESUMÉ



Bill Paetznick

Senior Project Manager

Education

BYU - Business

Work History and Background

Bill has over 30 years in the construction industry and has served in multiple roles throughout his career including Sr. Vice President for a National General Contractor, President of a local Development and Contracting firm and multiple management positions within the construction industry. Bill has extensive experience in commercial construction in the Retail, Class A office, Specialty Restaurant, and Industrial Sectors. He spent 10 years with a National Shopping Mall developer managing large mall renovations and new construction projects across the US.

Highlight Project Experience

Wolf Crossing - Georgetown Texas - a 250,000sf retail center on Interstate 35 at University Avenue that includes restaurants, medical facilities, neighborhood services, a hotel, and a grocery store. This was a large multi building Tiltwall project spread across 31 acres anchored by several national tenants. This project was delivered on time in spite of an unseasonable amount of rain that caused multiple delays with the tiltwall erection. Utilities were complex due to the large overall site conditions, spacing of the buildings and location of existing utility tie ins. Extensive landscaping encompassed the entire site upon completion.



Cubesmart Storage - Parmer Lane Austin Texas - the 110,505-square-foot building houses all climate-controlled units along with retail and office space for operations. The five-story property is outfitted with 1,152 storage units. Due to being 5 story, intumescent fireproofing was required on all vertical and horizontal structural steel. Project was delivered on time and within budget despite the City of Austin jurisdictional challenges and extremely challenging utility work performed in the right of way. Detention pond was built on site and required to be semi functional prior to the start of construction.



Mission Viejo Mall – Mission Viejo California – Managed the 150 million dollar construction renovations of this super regional shopping mall which features over 1 million sf of retail space. Renovations included relocation and expansion of various major anchor tenants, a completely relocated food court anchored by The Cheesecake Factory and an extensive parking garage expansion. This project also featured major lighting and visual improvements to brighten up the interior of the mall. The renovation required additional chiller units as well as major mechanical and electrical system upgrades throughout the facility.



RESUMÉ (continued)

Bill Paetznick, Senior Project Manager

Cube Smart Sacsche, Texas – This 135,00 sf 3 story building was constructed on just 2 acres. This site was bounded by a wet weather pond that resulted in extremely high PVR soil conditions. The entire site including the building pad was lime stabilized to minimize the expansion of the soil. Despite the engineered design, the building still experienced substantial vertical movement in the building and parking area. Stormwater was sheet drained and diverted to a common area detention and filtration pond. Utility connection points were extremely long runs and ground water was encountered throughout the trenching for the utilities.



Central Texas Harley Davidson I35 Round Rock Texas – This dealership relocated from a small facility in Austin and transitioned into this 6-acre site featuring a 45,000sf Tiltwall building that included a 15,000sf State of the Art Service Dept and 27,000sf of showroom and retail space. The building also featured 3,000sf of mezzanine offices. The site also featured large outside exterior entertainment spaces for hosting various activities. This project was designed by a Wisconsin based Architect which proved to be difficult in the understanding of the Texas climate.



Truluck's – The Woodlands - This 25,000sf Tenant Improvement transformed a completely cold dark shell into a high-end fine dining restaurant with custom black walnut millwork and level 5 finishes throughout. Custom underlit Onyx bar tops and curved millwork were the first of its kind and we developed several construction methods for use in future locations. The site was incredibly challenging due to the limited space and close proximity of Lake Woodlands which required the use of helicopters to hoist the Mechanical systems on the roof.



Hat Creek Burgers - Georgetown, Texas – This unique one off, non prototypical store was one of the first locations for this new chain that expanded rapidly in the Austin Area. Located right off the San Gabriel River Greenbelt, the 3,400sf building features a large outdoor space and a spacious play area. The historic site was unique due to being close to a former Indian site filled with arrow heads and historical items. Upon excavation, an abandoned swimming pool was discovered that was unreported on the surveys. Careful planning and construction of uniquely linked filtration ponds were built in the parking lot islands which treated the runoff prior to entry to the San Gabriel River.



References

Ryan Hansanawat
Mode Design & Architecture
512-733-1150

Jayson Riche, PE
GTX Engineering
254-279-3423

Morgan McLaughlin
Novak Commercial Construction
512-864-4656

Philip Wanke, AIA
Place Designers
512-238-8912



Mark Lee

Superintendent

Education

University of Oregon
1981

Work History and Background

Mark has a 37-year record of success overseeing all phases of commercial and residential construction projects. Projects have included churches, restaurants, office buildings and medical facilities. Mark works well with architects, subcontractors, suppliers and building officials to satisfy the expectations of the most discerning clients. He is dedicated to delivering the best in construction quality while adhering to all deadlines, specifications and budgets. Mark resides in Georgetown, Texas.

Project Experience

The Wilco Annex is a two story 64,000 SF office building for Williamson County, TX. The two-story building is structural steel, the second floor is concrete on metal decking. The exterior of the building is finished with several different types of materials. There are two machine room-less elevators. The JP courtroom includes the judge's bench, jury seating, court reporter and witness stand along with full gallery seating. Included in the building are many areas that required high security with a wide assortment of protection, identification, surveillance and detection devices to ensure the safety of County employees and visitors. Chasco self-performed all site work, utilities and concrete work and the project was completed on schedule and under budget.



Celebration Church is a 90,000 SF Church recently constructed in Georgetown, TX. The facility has large childcare wing of 30,000 SF. The remaining 60,000 SF of the building includes the narthex (entry/ vestibule) and sanctuary. The narthex includes a bookstore and the "Blend", a "bistro style" coffee service area that also serves premade snack items. The sanctuary accommodates seating for over 2,900 guests and incorporates a state-of-the-art audio/visual system. The project had a 13-month schedule, but was completed early, in 12 months, in spite of having over 36 rain days. 2017 Outstanding Construction Award – Austin Chapter AGC.



R E S U M É (continued)

Mark Lee
Superintendent

Lexus of Lakeway, Austin, TX - The Lexus of Lakeway project was an extremely high-end car dealership built in Lakeway, Texas. This is the first car dealership allowed to be built within the City of Lakeway. The \$21 million project consisted of a three-level main building of 86,000 SF, including a showroom, offices, café, boutique, parts department, 52-bay service shop and a 72-space rooftop parking deck. An 11,000 SF carwash/make ready building and all the associated site work. 2015 Outstanding Construction Award – Austin Chapter AGC.



Bartholomew Municipal Pool, Austin, TX – This project consisted of 3 bathhouses, a separate mechanical building and pump house an “L” shaped lap pool with a diving well, a mid-depth recreation pool, a zero-entry activity pool, and two slides. The site itself was over excavated and filled with 7’ of engineered fill material. 2014 Outstanding Construction Award – Austin Chapter AGC.



Don Hewlett Chevrolet, Georgetown TX – Multiple projects including a 4,815 SF Service Building constructed as a PEMB with stucco and split face CMU exterior. Containing service writers and waiting areas and a museum containing some of the iconic first model year vehicles Chevrolet produced. A 9,964 SF Parts Warehouse expansion. Also, a PEMB with elevated foundation challenges, due to the sloping site. These projects were both completed ahead of schedule and under budget. The challenge was in completing the work amidst a thriving and busy business that was open 6 days a week.

References

Jim Kuykendall, Executive Pastor
Celebration Church
(512) 763-3000 x 126

Mr. Steven Walker, Franchise Counselor
True Car
(512) 970-6760

Mr. Tom Stevens, Vice President
Stevens-Hemingway-Stevens, Inc.
(510) 787-1148

RESUMÉ



Scott Badgett

Vice President – Building Estimating / Pre-Construction Services

Education

University of Texas
BS, Civil Engineering

Work History and Background

Scott has over 45 years of solid construction management experience in commercial, institutional and industrial projects. His diverse background includes construction of high security and high-tech facilities, renovation and construction of healthcare facilities, churches, schools, office buildings, manufacturing and retail facilities. Experience includes Design/Build and fast-track projects, cast-in-place frame structures, pre-cast structures and tilt wall buildings. Scott's key responsibility is the coordination and management of the entire process from pre-construction through close-out. Scott has been with Chasco for nineteen years.

Project Experience

- Texas A&M Health Science Center – Phase I Texas A&M Health Science Center and Medical School Round Rock, TX – a \$42.3 million 164,000 SF 4-story building containing classrooms, lecture halls, administration areas, public clinics, laboratories, and a simulated hospital training floor. Chasco performed, all site work, utilities, and site/building concrete. CM-at-Risk delivery.
- The Wilco Georgetown Annex is a two story 60,000 SF office building for Williamson County, TX. The two-story building is structural steel, the second floor is concrete on metal decking. The exterior of the building is finished with several different types of materials. Chasco performed, all site work, utilities, and site/building concrete. CM-at-Risk delivery.
- Chasco Family YMCA, Round Rock: 18,160 sf masonry and structural steel facility including an eight-lane junior Olympic indoor pool, therapy pool, hot tub, lazy river, vortex pool, water slide, splash pad, sauna, locker rooms with showers, family changing rooms and a 2,800-sf operable skylight. The project included demolition of a portion of the existing building while the remaining facility was operational. Parking facilities for the YMCA were simultaneously constructed under the same contract. CM-at-Risk delivery.
- Williamson County Precinct 1 Annex and EMS Building – construction of 2 buildings with E.I.F.S. and stone veneer with complete interior finish out. Annex building was 27,660 SF and the EMS building was 6,470 SF. Project was completed early and under budget. (\$6.3 million CM-at-Risk delivery.



R E S U M É (continued)

Scott Badgett

Vice President – Building Estimating / Pre-Construction Services

- City of Round Rock Sports Center – Round Rock, TX – 80,000 square foot sports center with 6 basketball/12 volleyball courts and 9 multi-purpose rooms with seating for up to 1,700 fans. Chasco self-performed all site work, utilities, site concrete, building concrete and tilt wall panels for this project.



- Georgetown Recreation Center – Georgetown, TX – 67,952 SF of new construction and renovation to the exiting occupied and fully operational Rec. Center. Scope of work included a gymnasium, multi-purpose & meeting rooms, elevated track, indoor & outdoor pools with water features, restroom & shower facilities, site utilities, detention pond and concrete construction. CM-at-Risk delivery.



- Great Oaks Elementary School, Round Rock, Texas – 6.0 million, 70,000 SF elementary school for RRISD. Project included all site development, utilities and detention pond.
- Westwood High School Science Wing Addition, Round Rock, Texas – 5.5 million two-story addition to existing high school. Included pre-cast wall panels to match existing facility. Project was constructed in the middle of the occupied campus with minimal impact to ongoing operations.
- Lampasas Middle School, Lampasas, TX – \$6.0 million two-story middle school. Full cafeteria, gymnasiums and all related site facilities.

References

Mr. Bo Spencer, AIA
Spencer-Pierce Architecture, Inc.
512-388-0677

Mr. Dale Butler, Facilities Director
Williamson County, TX
512-943-1609

Mr. Jeff Andresen, President and CEO
YMCA Greater Williamson County
512-615-5530

R É S U M É



Rick Risener

Chief Civil Estimator

Education

Abilene Christian University

Work History and Background

Rick has over 20 years of experience in residential, commercial, airport, heavy highway and civil construction. Rick has worked on projects that vary from pedestrian, vehicular, and railway bridges, public and private roadways, concrete and earthen dams, public parks and trail systems, subdivision infrastructure, site and pipeline utilities, site grading and site concrete work, single building and strip retail, multi-story office and medical buildings, pre-cast and cast-in-place concrete garages, and custom home building. Rick has been with Chasco for thirteen years.

Project Experience

- Celebration Church is a new 90,000 SF church recently constructed in Georgetown, TX. The facility has large child care wing of 60,000 SF. The remaining 30,000 SF of the building includes the narthex (entry/ vestibule) and sanctuary. The narthex includes a book store and the "Blend", a "bistro style" coffee service area that also serves premade snack items. The sanctuary accommodates seating for over 2,600 guests and incorporates a state of the art audio/visual system.



- Lexus of Lakeway, Austin, TX - The Lexus of Lakeway project was an extremely high-end car dealership built in Lakeway, Texas. This is the first car dealership allowed to be built within the City of Lakeway. The \$21 million project consisted of a three-level main building of 86,000 SF, an 11,000 SF carwash/make ready building and all the associated site work.




- Twin Lakes YMCA Natatorium, Teen Center & Aerobics Room – Owner – The YMCA of Greater Williamson County – CM at Risk contract. This expansion is the second phase of a project initially built in 2004 and made possible by a partnership between Williamson County and the YMCA of Greater Williamson County. This phase added a natatorium, a teen center, an aerobics room and a Cardio Theater. The natatorium houses multiple indoor pools, including a main pool with lap lanes, a splash pad area for small children and a two-story waterslide for the larger kids. Additionally, a warm water therapy pool, a hot tub/spa and a dry sauna were installed for the adults to relax in.



R É S U M É (continued)

Rick Risener
Chief Civil Estimator

- Cedar Park Events Center, Cedar Park, TX – A 100,000 SF Multi-Function Sporting and Events Center. This project included the concrete foundation, upper level concrete slabs, equipment footings and foundations, and approximately 40 acres of site concrete with many areas that required special finishes. 
- Barton Creek Section 101 ACFT Treated Effluent Storage Pond, Austin, TX – This project included ten acres of construction within an environmentally sensitive area. A 2,350 LF all weather access road was built to the pond site. 35,000 CY of rock and over burden were excavated. Approximately 8,000 CY of the material was resized through a crushing operation and reused as select fill across the entire pond floor and behind the pond walls. The walls, ranging from 9' to 35' tall, surrounded the entire pond perimeter.
- Samsung T-Star Facility Operations Building, Austin, TX – This project consisted of constructing a new two-story concrete frame office and warehouse building with loading dock at the Samsung Semiconductor site in Austin, TX. Strict background checks and training are required for all Samsung projects.
- ABIA New Employee Parking Lot, Austin, TX – This \$7 million + project included construction of 703,800 SF of new parking lots at the existing Austin Bergstrom International Airport consisting of demolition of old Air Force structures, installation of 8" of lime treated subgrade, flex base and asphalt on the entire area, installation of 5 new Bus Shelters and 2 new Bench Canopy structures. Existing underground conditions created challenges on a daily basis.
- Kenney Fort Blvd., Round Rock, TX – In design for over 10 years, this project consisted of a 1.3-mile-long new section of roadway from Joe DiMaggio Blvd. to Forest Creek Blvd. in Round Rock. The project featured three bridges: an 800' long bridge over Brushy Creek, a shorter bridge over Chandler Creek, and a new railroad bridge for the Union Pacific Railroad. Some of the project challenges involved moving the Union Pacific mainline rail traffic to a shoofly detour. This allowed a new railroad bridge to be built on the mainline. Once the new railroad bridge was completed rail traffic was moved back onto the mainline and the shoofly detour was removed. Excavation then began under two existing bridges on Hwy 79. This was needed to extend the new Kenney Fort Blvd. under the highway and under the new rail bridge. The 24-month project was finished over two months ahead of schedule and was one of the largest road & bridge projects ever constructed by the City of Round Rock.

City of Residence: Austin, Texas

References

Mr. Antonio Prete
Waeltz & Prete, Inc.
(512) 505-8953
tony@w-pinc.com

Mr. Troy Jamail
HWA Parking/Strickland-Jamail
(512) 592-3277
troy.jamil@hwaparking.com

Mr. James Heironimus
NXP Semiconductors, Inc.
(512) 933-2104
james.heironimus@nxp.com

RESUMÉ



Jonathan Escalante, CSHO, CHST

Director of Health and Safety

Education

Universidad Valle Del Bravo, Mexico 2005

Work History and Background

Jonathan has over 10 years of Construction Safety Experience including road and building construction. As a Safety Specialist at Chasco, Jonathan has been responsible for updating, implementing and overseeing the company's safety and training program. Since beginning with Chasco, he has made revisions and updates to the Safety Manual, including: a new Accident Prevention Program, a new Substance Abuse Program & improved Accident Investigation procedures. He has also updated the SDS Manual, to merge the new GHS program and implemented a new Virtual Risk Manager Program that uses software for driver training & vehicle loss prevention. Employee training is a major concern at Chasco. Jonathan has created new training programs for new hire safety orientation, traffic control safety awareness, qualified signal & rigging training and general safety awareness for all of Chasco's employees. Due to all of these improvements, Chasco has seen lower Recordable Rates and an overall increase in safety awareness amongst its employees. Jonathan has been with Chasco for all ten years of his construction experience.

Training

CSHO (Certified Safety and Health Official)
500 OSHA Train the Trainers
510 OSH Standards
OSH311 Fall Protection
OSH521 Industrial Hygiene
PRT260 Cranes and Material Handling
OSH301 Excavation, Trenching and Soil Mechanics
CPR/FA Certified Trainer
PRT123 Scaffold Training
Flagger Training (Train the trainer)
OSH755 Accident Investigation
OSH301 Excavation, Trenching and Soil Mechanics

Project Experience

SH 130 - Lone Star Infrastructure. Hutto, Tx. (10/2005-8/2009)

Position: Safety Supervisor / HR Assistant Project Value: 1.6 Billion USD

Main activities:

- Responsible for day to day environmental health and safety related activity with a specific focus on reducing incident rates and workers comp.
- Develop and implement required Safety Programs and progressive disciplinary actions.

R E S U M É (continued)

Jonathan Escalante

Safety Director

- Develop Safety incentive program
- Implement accident prevention program
- Field Safety Inspections
- Provide monthly reports to the Fluor Corporate Office, including accident investigations, injury summary reports (man-hours included) and project close out-forms.
- Accident investigation / Case manager
- Conduct Mass meetings, Safety talks.
- New Hire Safety Orientation
- Training such as: Fall Protection, Confined Space, Haz-Mat, Traffic Awareness
- Responsible for OSHA compliance and record keeping, Worker's Comp Issues
- Random Drug testing coordinator (DOT and Non-DOT)
- HR New hire orientation
- Minor HR duties such as: Terminations, spreadsheet, employee benefits.
- Coordinate office management and special projects with a high degree of efficiency.
- Manage capital purchases, direct vendor relations, generate and maintain equipment tracking records.

Construcciones del Panuco. Mexico (06/2002-09/2005)

Position: Safety Apprentice

Main activities:

- Protect Health and Safety of the employees as well as the company.
- Follow Safety Standards set by the Social Security Safety Regulation of the Mexican Institute.
- Safety inspections / investigations.
- Medical Case Management
- Safety Training to employees (adapted by OSHA 1926)
- Report all data of incidents / accidents to CEO monthly.

City of Residence: Leander, Texas

References

Mr. Ignacio Guerra
Fluor Daniel Ent.
(210) 273-1774

Brayan Loya
Fluor Daniel Ent.
(512) 769-4339

Larry Connelly
AGC of Austin
(512) 748-1830

RESUMÉ



Charles J. (Chuck) Glace, Jr.

President

Education

Central Michigan University / U.T. Austin

Work History and Background

Chuck has over 30 years of diversified construction experience. He has extensive background in concrete flatwork, structural concrete, tilt-wall, decorative concrete, excavation, and utility work. Chuck has complete responsibility for overall coordination of Chasco's operation. To him, the retention and advancement of individuals speaks directly to Chasco's success. Chuck is a driving force in the organization and training of Chasco's talent in both the office and the field. He provides ongoing leadership to the management team and to the self-perform operations, helping Chasco to provide better control and exceptional service to its customers. Chuck serves on the Board of the YMCA of Round Rock. He is also a board member of the American Concrete Institute, a member of the Construction Specifications Institute, the American Society of Concrete Construction, and the Associated General Contractors of America, and a Board member of The Round Rock Community Foundation.

Project Experience

- Texas A&M Health Science Center – Phase I Texas A&M Health Science Center and Medical School Round Rock, TX – a \$42.3 million 164,000 SF 4-story building containing classrooms, lecture halls, administration areas, public clinics, laboratories, and a simulated hospital training floor.



- Kenney Fort Blvd.



Owner - City of Round Rock, TX – Stipulated Sum/Unit Price contract. This project consisted of a 1.3-mile-long new section of roadway from Joe DiMaggio Blvd. to Forest Creek Blvd. in Round Rock, TX. The project featured three bridges, an 800' long bridge over Brushy Creek, a shorter bridge over Chandler Creek and a new



railroad bridge for the Union Pacific Railroad. The 24-month project was finished over two months ahead of schedule and was one of the largest road & bridge projects ever constructed by the City of Round Rock.

RESUMÉ (continued)

Charles J. (Chuck) Glace
President

- AMP Packaging Office and Manufacturing Facility, Round Rock, TX – Design/Build Contract for 58,000 SF tiltwall computer manufacturing facility. 
- Emergency Vehicles Operations Course –
Owner - Texas Department of Public Safety – CM-at-Risk contract. Over 1,000,000 SF of concrete skills pads and 6.2 mile asphalt/concrete road track for vehicle skills and training. During construction of the original \$23.8 million-dollar project a \$3.7 million dollar change order was issued to construct a vehicle maintenance building. The project won the Gold Award for Industrial and Special Paving from the American Concrete Paving Association for 2010. Total project cost was \$27.5 Million. 
- Tellabs Operations, Round Rock, TX – 48,000 SF tiltwall manufacturing addition to the existing facility.
- Classic Toyota, Round Rock, TX – Construction of a new car sales building, body shop, parking, drives, new car display, and detention / filtration structures.
- Austin VA Hospital / Clinic, Austin, TX – 45,000 SF slab on grade with related site work.
- St. Philips Family Life Center, Round Rock, TX – 11,000 SF church facility, including worship areas, classrooms, elevated altar / stage, commercial food preparation, and childcare.
- Shoal Creek Bridge, Austin, TX – New 2-span bridge over Shoal Creek including channel work and slope protection to flood prone creek.
- Expo Business Park, Austin, TX – Two 124,000 SF concrete tiltwall buildings, including all site development and utility construction.

References

Mr. Mark Remmert
Chief Building Inspector
City of Round Rock
512-218-6600

Mr. Brent Jones, P.E.
Civil Engineer
Randall Jones Engineering
(512) 415-3012

Mr. Chad McDowell
General Services Director
City of Round Rock
(512) 671-2890

RESUMÉ



Charles R. King

CFO, Vice President, Secretary and Treasurer

Education

BBA in Accounting – Lamar University

CPA Certification – Texas Society of CPA's

Work History and Background

Charles has over 40 years experience as an entrepreneurial financial accountant. He began his career with a national accounting firm prior to joining a local CPA firm. As a partner in this firm, he was responsible for a wide array of tax and financial accounting engagements for small businesses and individuals. Subsequently, he spent 15 years as CFO of a multi-location, multi-franchise car dealership conglomerate. In this role he was responsible for the financial, treasury and IT functions.

At Chasco, Charles is responsible for the financial function, as well as strategic planning, tax issues and cash management.

References

Mr. Troy Voelker
McNery & Voelker
512-255-6940

Mr. Jeff Anderson
RSM Austin, CPA's
512-476-0717

RESUMÉ



Craig Hunter, CPA

Controller

Education

BA in Accounting, California State University, Stanislaus, 1985

Work History and Background

Craig has over 30 years of experience in various industries. He has been a Controller at a publishing company, a lodging company, a wholesale/retail company with over 800 locations, a national health food company, where he was a key member of starting the manufacturing subsidiary. He has over 20 years of experience in the construction industry as a Consultant and Controller. He has worked with companies ranging in size from \$12 million to well over \$100 million. Craig's duties at Chasco include overseeing the Accounting and Human Resources departments. He has been with Chasco for five years.

City of Residence: Austin, Texas



List of Documents

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A001	SITE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
A002	SITE DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
A003	SITE DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
A004	SITE DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
A005	UNDERFLOOR GRADING PLAN	<input checked="" type="checkbox"/>	
A006	UNDERFLOOR GRADING DETAILS	<input checked="" type="checkbox"/>	
A007	UNDERFLOOR GRADING DETAILS	<input checked="" type="checkbox"/>	
A008	UNDERFLOOR GRADING DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
A009	UNDERFLOOR GRADING DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
A010	MOCK UP ELEVATIONS	<input checked="" type="checkbox"/>	
A101	LEVEL 1 - OVERALL SLAB PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
A102	LEVEL 2 - OVERALL SLAB PLAN	<input checked="" type="checkbox"/>	
A103	LEVEL 3 - OVERALL SLAB PLAN	<input checked="" type="checkbox"/>	
A110	LEVEL 1 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
A111	LEVEL 1 - ENLARGED AREA A FLOOR PLAN	<input checked="" type="checkbox"/>	
A112	LEVEL 1 - ENLARGED AREA B FLOOR PLAN	<input checked="" type="checkbox"/>	
A113	LEVEL 1 - ENLARGED AREA C FLOOR PLAN	<input checked="" type="checkbox"/>	
A114	LEVEL 1 - ENLARGED AREA D FLOOR PLAN	<input checked="" type="checkbox"/>	
A120	LEVEL 2 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
A121	LEVEL 2 - ENLARGED AREA A FLOOR PLAN	<input checked="" type="checkbox"/>	
A122	LEVEL 2 - ENLARGED AREA B FLOOR PLAN	<input checked="" type="checkbox"/>	
A123	LEVEL 2 - ENLARGED AREA C FLOOR PLAN	<input checked="" type="checkbox"/>	
A124	LEVEL 2 - ENLARGED AREA D FLOOR PLAN	<input checked="" type="checkbox"/>	
A130	LEVEL 3 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
A131	LEVEL 3 - ENLARGED AREA A FLOOR PLAN	<input checked="" type="checkbox"/>	
A132	LEVEL 3 - ENLARGED AREA B FLOOR PLAN	<input checked="" type="checkbox"/>	
A133	LEVEL 3 - ENLARGED AREA C FLOOR PLAN	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A134	LEVEL 3 - ENLARGED AREA D FLOOR PLAN	<input checked="" type="checkbox"/>	
A140	OVERALL ROOF PLAN	<input checked="" type="checkbox"/>	
A141	ROOF PLAN AREA A	<input checked="" type="checkbox"/>	
A142	ROOF PLAN AREA B	<input checked="" type="checkbox"/>	
A143	ROOF PLAN AREA C	<input checked="" type="checkbox"/>	
A144	ROOF PLAN AREA D	<input checked="" type="checkbox"/>	
A146	ROOF DETAILS	<input checked="" type="checkbox"/>	
A150	BALCONY - ENLARGED PLANS	<input checked="" type="checkbox"/>	
A151	BALCONY RAILING - ELEVATIONS	<input checked="" type="checkbox"/>	
A152	BALCONY RAILING - ELEV. & DETAILS	<input checked="" type="checkbox"/>	
A201	DOOR SCHEDULES	<input checked="" type="checkbox"/>	
A202	DOOR SCHEDULES	<input checked="" type="checkbox"/>	
A203	WINDOW TYPES - EXTERIOR	<input checked="" type="checkbox"/>	
A204	WINDOW TYPES - EXTERIOR	<input checked="" type="checkbox"/>	
A205	WINDOW TYPES - EXTERIOR	<input checked="" type="checkbox"/>	
A206	STOREFRONT - INTERIOR	<input checked="" type="checkbox"/>	
A210	DOOR DETAILS	<input checked="" type="checkbox"/>	
A211	DOOR DETAILS	<input checked="" type="checkbox"/>	
A212	DOOR DETAILS	<input checked="" type="checkbox"/>	
A213	WINDOW & STOREFRONT DETAILS	<input checked="" type="checkbox"/>	
A214	WINDOW & STOREFRONT DETAILS	<input checked="" type="checkbox"/>	
A215	WINDOW & STOREFRONT DETAILS	<input checked="" type="checkbox"/>	
A301	OVERALL EXTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A302	ENLARGED EXT. ELEVATIONS - NORTH WEST	<input checked="" type="checkbox"/>	
A303	ENLARGED EXT. ELEVATIONS - NORTH EAST	<input checked="" type="checkbox"/>	
A304	ENLARGED EXT. ELEVATIONS - SOUTH WEST	<input checked="" type="checkbox"/>	
A305	ENLARGED EXT. ELEVATIONS - SOUTH EAST	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A306	ENLARGED EXT. ELEVATIONS - EAST	<input checked="" type="checkbox"/>	
A307	ENLARGED EXT. ELEVATIONS - WEST	<input checked="" type="checkbox"/>	
A310	BUILDING SECTIONS	<input checked="" type="checkbox"/>	
A311	BUILDING SECTIONS	<input checked="" type="checkbox"/>	
A312	BUILDING SECTIONS	<input checked="" type="checkbox"/>	
A313	BUILDING SECTIONS	<input checked="" type="checkbox"/>	
A314	BUILDING SECTIONS	<input checked="" type="checkbox"/>	
A315	BUILDING SECTIONS	<input checked="" type="checkbox"/>	
A316	BUILDING SECTIONS	<input checked="" type="checkbox"/>	
A401	ENLARGED PLANS - LEVEL 1	<input checked="" type="checkbox"/>	
A402	ENLARGED PLANS - LEVEL 1	<input checked="" type="checkbox"/>	
A403	ENLARGED PLANS - LEVEL 2	<input checked="" type="checkbox"/>	
A404	ENLARGED PLANS - LEVEL 2 & 3	<input checked="" type="checkbox"/>	
A405	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A406	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A407	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A408	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A409	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A410	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A411	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A412	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A413	INTERIOR ELEVATIONS	<input checked="" type="checkbox"/>	
A414	INTERIOR ELEVATIONS - LOGOS	<input checked="" type="checkbox"/>	
A415	DEMOUNTABLE WALL ELEVATIONS	<input checked="" type="checkbox"/>	
A416	DEMOUNTABLE WALL ELEVATIONS	<input checked="" type="checkbox"/>	
A417	DEMOUNTABLE WALL ELEVATIONS	<input checked="" type="checkbox"/>	
A418	DEMOUNTABLE WALL ELEVATIONS	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A419	DEMOUNTABLE WALL ELEVATIONS	<input checked="" type="checkbox"/>	
A420	DEMOUNTABLE WALL ELEVATIONS	<input checked="" type="checkbox"/>	
A421	MILLWORK DETAILS	<input checked="" type="checkbox"/>	
A422	MILLWORK DETAILS	<input checked="" type="checkbox"/>	
A423	MILLWORK DETAILS	<input checked="" type="checkbox"/>	
A424	MILLWORK DETAILS	<input checked="" type="checkbox"/>	
A425	MILLWORK DETAILS	<input checked="" type="checkbox"/>	
A430	EQUIPMENT SCHEDULES	<input checked="" type="checkbox"/>	
A431	LEVEL 1 EQUIPMENT PLAN	<input checked="" type="checkbox"/>	
A432	LEVEL 2 EQUIPMENT PLAN	<input checked="" type="checkbox"/>	
A433	LEVEL 3 EQUIPMENT PLAN	<input checked="" type="checkbox"/>	
A510	LEVEL 1 - OVERALL RCP	<input checked="" type="checkbox"/>	
A511	LEVEL 1 - AREA A RCP	<input checked="" type="checkbox"/>	
A512	LEVEL 1 - AREA B RCP	<input checked="" type="checkbox"/>	
A513	LEVEL 1 - AREA C RCP	<input checked="" type="checkbox"/>	
A514	LEVEL 1 - AREA D RCP	<input checked="" type="checkbox"/>	
A520	LEVEL 2 - OVERALL RCP	<input checked="" type="checkbox"/>	
A521	LEVEL 2 - AREA A RCP	<input checked="" type="checkbox"/>	
A522	LEVEL 2 - AREA B RCP	<input checked="" type="checkbox"/>	
A523	LEVEL 2 - AREA C RCP	<input checked="" type="checkbox"/>	
A524	LEVEL 2 - AREA D RCP	<input checked="" type="checkbox"/>	
A530	LEVEL 3 - OVERALL RCP	<input checked="" type="checkbox"/>	
A531	LEVEL 3 - AREA A RCP	<input checked="" type="checkbox"/>	
A532	LEVEL 3 - AREA B RCP	<input checked="" type="checkbox"/>	
A533	LEVEL 3 - AREA C RCP	<input checked="" type="checkbox"/>	
A534	LEVEL 3 - AREA D RCP	<input checked="" type="checkbox"/>	
A540	ENLARGED RCP	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A541	ENLARGED RCP	<input checked="" type="checkbox"/>	
A542	ENLARGED RCP	<input checked="" type="checkbox"/>	
A543	ENLARGED RCP	<input checked="" type="checkbox"/>	
A550	RCP DETAILS	<input checked="" type="checkbox"/>	
A551	RCP DETAILS	<input checked="" type="checkbox"/>	
A552	RCP DETAILS	<input checked="" type="checkbox"/>	
A553	RCP DETAILS	<input checked="" type="checkbox"/>	
A554	RCP DETAILS	<input checked="" type="checkbox"/>	
A601	ELEVATOR PLANS	<input checked="" type="checkbox"/>	
A602	STAIR PLANS	<input checked="" type="checkbox"/>	
A603	STAIR PLANS	<input checked="" type="checkbox"/>	
A604	ELEVATOR SECTIONS	<input checked="" type="checkbox"/>	
A605	STAIR SECTIONS	<input checked="" type="checkbox"/>	
A606	STAIR SECTIONS	<input checked="" type="checkbox"/>	
A607	STAIR SECTIONS	<input checked="" type="checkbox"/>	
A608	STAIR SECTIONS	<input checked="" type="checkbox"/>	
A609	STAIR SECTIONS	<input checked="" type="checkbox"/>	
A610	STAIR SECTIONS	<input checked="" type="checkbox"/>	
A611	STAIR + RAMP DAIS	<input checked="" type="checkbox"/>	
A615	ELEVATOR/STAIR DETAILS	<input checked="" type="checkbox"/>	
A616	ELEVATOR/STAIR DETAILS	<input checked="" type="checkbox"/>	
A617	ELEVATOR/STAIR DETAILS	<input checked="" type="checkbox"/>	
A618	MAIN LOBBY STAIR	<input checked="" type="checkbox"/>	
A619	MAIN LOBBY STAIR	<input checked="" type="checkbox"/>	
A620	MAIN LOBBY STAIR	<input checked="" type="checkbox"/>	
A621	MAIN LOBBY STAIR	<input checked="" type="checkbox"/>	
A622	MAIN LOBBY STAIR	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A623	MAIN LOBBY STAIR	<input checked="" type="checkbox"/>	
A624	MAIN LOBBY WALL SECTIONS	<input checked="" type="checkbox"/>	
A625	MAIN LOBBY WALL DETAILS	<input checked="" type="checkbox"/>	
A701	WALL SECTIONS	<input checked="" type="checkbox"/>	
A702	WALL SECTIONS	<input checked="" type="checkbox"/>	
A703	WALL SECTIONS	<input checked="" type="checkbox"/>	
A704	WALL SECTIONS	<input checked="" type="checkbox"/>	
A705	WALL SECTIONS	<input checked="" type="checkbox"/>	
A706	WALL SECTIONS	<input checked="" type="checkbox"/>	
A707	WALL SECTIONS	<input checked="" type="checkbox"/>	
A708	WALL SECTIONS	<input checked="" type="checkbox"/>	
A710	WALL SECTIONS DETAILS	<input checked="" type="checkbox"/>	
A711	WALL SECTIONS DETAILS	<input checked="" type="checkbox"/>	
A712	WALL SECTIONS DETAILS	<input checked="" type="checkbox"/>	
A713	WALL SECTIONS DETAILS	<input checked="" type="checkbox"/>	
A714	WALL SECTIONS DETAILS	<input checked="" type="checkbox"/>	
A715	WALL SECTIONS DETAILS	<input checked="" type="checkbox"/>	
A716	V-COLUMN DETAILS	<input checked="" type="checkbox"/>	
A717	V-COLUMN DETAILS	<input checked="" type="checkbox"/>	
A718	FIRESTOPPING DETAILS	<input checked="" type="checkbox"/>	
A800	FIRE PROOFING	<input checked="" type="checkbox"/>	
A801	FIRE PROOFING	<input checked="" type="checkbox"/>	
A802	PLAN DETAILS	<input checked="" type="checkbox"/>	
A803	PLAN DETAILS	<input checked="" type="checkbox"/>	
A804	PLAN DETAILS	<input checked="" type="checkbox"/>	
A805	PLAN DETAILS	<input checked="" type="checkbox"/>	
A806	PLAN DETAILS	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A807	PLAN DETAILS	<input checked="" type="checkbox"/>	
A808	PLAN DETAILS	<input checked="" type="checkbox"/>	
A900	FINISH LEGEND - FLOORS, WALLS & BASE	<input checked="" type="checkbox"/>	
A901	FINISH LEGEND - MILLWORK & CEILINGS	<input checked="" type="checkbox"/>	
A910	LEVEL 1 - OVERALL FINISH FLOOR PLAN	<input checked="" type="checkbox"/>	
A911	LEVEL 1 - ENLARGED AREA A - FINISH PLAN	<input checked="" type="checkbox"/>	
A912	LEVEL 1 - ENLARGED AREA B - FINISH PLAN	<input checked="" type="checkbox"/>	
A913	LEVEL 1 - ENLARGED AREA C - FINISH PLAN	<input checked="" type="checkbox"/>	
A914	LEVEL 1 - ENLARGED AREA D - FINISH PLAN	<input checked="" type="checkbox"/>	
A920	LEVEL 2 - OVERALL FINISH PLAN	<input checked="" type="checkbox"/>	
A921	LEVEL 2 - ENLARGED AREA A - FINISH PLAN	<input checked="" type="checkbox"/>	
A922	LEVEL 2 - ENLARGED AREA B - FINISH PLAN	<input checked="" type="checkbox"/>	
A923	LEVEL 2 - ENLARGED AREA C - FINISH PLAN	<input checked="" type="checkbox"/>	
A924	LEVEL 2 - ENLARGED AREA D - FINISH PLAN	<input checked="" type="checkbox"/>	
A930	LEVEL 3 - OVERALL FINISH PLAN	<input checked="" type="checkbox"/>	
A931	LEVEL 3 - ENLARGED AREA A - FINISH PLAN	<input checked="" type="checkbox"/>	
A932	LEVEL 3 - ENLARGED AREA B - FINISH PLAN	<input checked="" type="checkbox"/>	
A933	LEVEL 3 - ENLARGED AREA C - FINISH PLAN	<input checked="" type="checkbox"/>	
A934	LEVEL 3 - ENLARGED AREA D - FINISH PLAN	<input checked="" type="checkbox"/>	
A936	INTERIOR DETAILS	<input checked="" type="checkbox"/>	
A1100	SIGNAGE SCHEDULES & DETAILS	<input checked="" type="checkbox"/>	
A1110	LEVEL 1 - OVERALL SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1111	LEVEL 1 - AREA A - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1112	LEVEL 1 - AREA B - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1113	LEVEL 1 - AREA C - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1114	LEVEL 1 - AREA D - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1120	LEVEL 2 - OVERALL SIGNAGE PLAN	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
A1121	LEVEL 2 - AREA A - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1122	LEVEL 2 - AREA B - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1123	LEVEL 2 - AREA C - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1124	LEVEL 2 - AREA D - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1130	LEVEL 3 - OVERALL SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1131	LEVEL 3 - AREA A - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1132	LEVEL 3 - AREA B - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1133	LEVEL 3 - AREA C - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1134	LEVEL 3 - AREA D - SIGNAGE PLAN	<input checked="" type="checkbox"/>	
A1136	SIGN TYPES	<input checked="" type="checkbox"/>	
A1137	SIGN TYPES	<input checked="" type="checkbox"/>	
A1138	SIGN TYPES	<input checked="" type="checkbox"/>	
A1140	EXTERIOR WALL SIGNAGE	<input checked="" type="checkbox"/>	
A1141	EXTERIOR WALL SIGNAGE	<input checked="" type="checkbox"/>	
A1142	EXTERIOR WALL SIGNAGE	<input checked="" type="checkbox"/>	
AD101	SITE DEMOLITION	<input checked="" type="checkbox"/>	
Cover Sheet	Cover Sheet	<input checked="" type="checkbox"/>	
Cover Sheet 2	KISTNER Cameron Rd, B-150 Tx. 78754		
E000	ELECTRICAL SYMBOLS & ABBREVIATIONS	<input checked="" type="checkbox"/>	
E001	ELECTRICAL SITE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
E002	ELECTRICAL GROUNDING PLAN	<input checked="" type="checkbox"/>	
E003	ELECTRICAL PHOTOMETRIC PLAN	<input checked="" type="checkbox"/>	
E004	ENLARGED DRIVE THRU	<input checked="" type="checkbox"/>	
E005	ENLARGED SITE PLAN	<input checked="" type="checkbox"/>	
E101	UNDERFLOOR LIGHTING PLAN - AREA A	<input checked="" type="checkbox"/>	
E102	UNDERFLOOR LIGHTING PLAN - AREA B	<input checked="" type="checkbox"/>	
E103	UNDERFLOOR LIGHTING PLAN - AREA C	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
E104	UNDERFLOOR LIGHTING PLAN - AREA D	<input checked="" type="checkbox"/>	
E110	ELECTRICAL LIGHTING PLAN - LVL 1 - OVERALL	<input checked="" type="checkbox"/>	
E111	ELECTRICAL LIGHTING PLAN - LEVEL 1 - AREA A	<input checked="" type="checkbox"/>	
E112	ELECTRICAL LIGHTING PLAN - LEVEL 1 - AREA B	<input checked="" type="checkbox"/>	
E113	ELECTRICAL LIGHTING PLAN - LEVEL 1 - AREA C	<input checked="" type="checkbox"/>	
E114	ELECTRICAL LIGHTING PLAN - LEVEL 1 - AREA D	<input checked="" type="checkbox"/>	
E120	ELECTRICAL LIGHTING PLAN - LVL 2 - OVERALL	<input checked="" type="checkbox"/>	
E121	ELECTRICAL LIGHTING PLAN - LEVEL 2 AREA A	<input checked="" type="checkbox"/>	
E122	ELECTRICAL LIGHTING PLAN LEVEL 2- AREA B	<input checked="" type="checkbox"/>	
E122A	LIGHTING PLAN LEVEL 2- AREA B ALTERNATE	<input checked="" type="checkbox"/>	
E123	ELECTRICAL LIGHTING PLAN - LEVEL 2 AREA C	<input checked="" type="checkbox"/>	
E124	ELECTRICAL LIGHTING PLAN - LEVEL 2 AREA D	<input checked="" type="checkbox"/>	
E130	ELECTRICAL LIGHTING PLAN - LEVEL 3 - OVERALL	<input checked="" type="checkbox"/>	
E131	ELECTRICAL LIGHTING PLAN - LEVEL 3 - AREA A	<input checked="" type="checkbox"/>	
E132	ELECTRICAL LIGHTING PLAN - LEVEL 3 - AREA B	<input checked="" type="checkbox"/>	
E133	ELECTRICAL LIGHTING PLAN - LEVEL 3 - AREA C	<input checked="" type="checkbox"/>	
E134	ELECTRICAL LIGHTING PLAN - LEVEL 3 - AREA D	<input checked="" type="checkbox"/>	
E201	UNDERFLOOR POWER PLAN - AREA A	<input checked="" type="checkbox"/>	
E202	UNDERFLOOR POWER PLAN - AREA B	<input checked="" type="checkbox"/>	
E203	UNDERFLOOR POWER PLAN - AREA C	<input checked="" type="checkbox"/>	
E204	UNDERFLOOR POWER PLAN - AREA D	<input checked="" type="checkbox"/>	
E210	ELECTRICAL POWER PLAN - LVL 1 - OVERALL	<input checked="" type="checkbox"/>	
E211	ELECTRICAL POWER PLAN - LEVEL 1 - AREA A	<input checked="" type="checkbox"/>	
E211M	ELECTRICAL EQUIP PWR PLAN - LVL 1 - AREA A	<input checked="" type="checkbox"/>	
E212	ELECTRICAL POWER PLAN - LEVEL 1 - AREA B	<input checked="" type="checkbox"/>	
E212M	ELECTRICAL EQUIP PWR PLAN - LVL 1 - AREA B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
E213	ELECTRICAL POWER PLAN - LEVEL 1 - AREA C	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
E213M	ELECTRICAL EQUIP PWR PLAN - LVL 1 - AREA C	<input checked="" type="checkbox"/>	
E214	ELECTRICAL POWER PLAN - LEVEL 1 - AREA D	<input checked="" type="checkbox"/>	
E214M	ELECTRICAL EQUIP PWR PLAN - LVL 1 - AREA D	<input checked="" type="checkbox"/>	
E220	ELECTRICAL POWER PLAN - LVL 2 - OVERALL	<input checked="" type="checkbox"/>	
E221	ELECTRICAL POWER PLAN - LEVEL 2 - AREA A	<input checked="" type="checkbox"/>	
E221M	ELECTRICAL EQUIP PWR PLAN - LVL 2 - AREA A	<input checked="" type="checkbox"/>	
E222	ELECTRICAL POWER PLAN - LEVEL 2 - AREA B	<input checked="" type="checkbox"/>	
E222A	POWER PLAN - LEVEL 2 - AREA B ALTERNATE	<input checked="" type="checkbox"/>	
E222M	ELECTRICAL EQUIP PWR PLAN - LVL 2 - AREA B	<input checked="" type="checkbox"/>	
E223	ELECTRICAL POWER PLAN - LEVEL 2 - AREA C	<input checked="" type="checkbox"/>	
E223M	ELECTRICAL EQUIP PWR PLAN - LVL 2 - AREA C	<input checked="" type="checkbox"/>	
E224	ELECTRICAL POWER PLAN - LEVEL 2 - AREA D	<input checked="" type="checkbox"/>	
E224M	ELECTRICAL EQUIP PWR PLAN - LVL 2 - AREA D	<input checked="" type="checkbox"/>	
E230	ELECTRICAL POWER PLAN - LVL 3 - OVERALL	<input checked="" type="checkbox"/>	
E231	ELECTRICAL POWER PLAN - LEVEL 3 - AREA A	<input checked="" type="checkbox"/>	
E231M	ELECTRICAL EQUIP PWR PLAN - LVL 3 - AREA A	<input checked="" type="checkbox"/>	
E232	ELECTRICAL POWER PLAN - LEVEL 3 - AREA B	<input checked="" type="checkbox"/>	
E232M	ELECTRICAL EQUIP PWR PLAN - LVL 3 - AREA B	<input checked="" type="checkbox"/>	
E233	ELECTRICAL POWER PLAN - LEVEL 3 - AREA C	<input checked="" type="checkbox"/>	
E233M	ELECTRICAL EQUIP PWR PLAN - LVL 3 - AREA C	<input checked="" type="checkbox"/>	
E234	ELECTRICAL POWER PLAN - LEVEL 3 - AREA D	<input checked="" type="checkbox"/>	
E234M	ELECTRICAL EQUIP PWR PLAN - LVL 3 - AREA D	<input checked="" type="checkbox"/>	
E240	ELECTRICAL POWER PLAN - ROOF - OVERALL	<input checked="" type="checkbox"/>	
E250	ELECTRICAL ENLARGED POWER PLANS	<input checked="" type="checkbox"/>	
E251	ELECTRICAL ENLARGED POWER PLANS	<input checked="" type="checkbox"/>	
E401	ELECTRICAL ONE LINE DIAGRAM	<input checked="" type="checkbox"/>	
E501	ELECTRICAL PANEL SCHEDULES	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
E502	ELECTRICAL PANEL SCHEDULES	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
E503	ELECTRICAL PANEL SCHEDULES	<input checked="" type="checkbox"/>	
E504	ELECTRICAL PANEL SCHEDULES	<input checked="" type="checkbox"/>	
E505	ELECTRICAL PANEL SCHEDULES	<input checked="" type="checkbox"/>	
E506	ELECTRICAL PANEL SCHEDULES	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
E507	ELECTRICAL SCHEDULES	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
E508	ELECTRICAL SCHEDULES	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
E601	ELECTRICAL DETAILS	<input checked="" type="checkbox"/>	
E602	ELECTRICAL DETAILS	<input checked="" type="checkbox"/>	
E603	ELECTRICAL DETAILS	<input checked="" type="checkbox"/>	
ER100	ERCES NOTES AND DETAILS SHEET NO.	<input checked="" type="checkbox"/>	
ER101	LEVEL 1 ERCES PLAN SHEET NO.	<input checked="" type="checkbox"/>	
ER102	LEVEL 2 ERCES PLAN SHEET NO.	<input checked="" type="checkbox"/>	
ER103	LEVEL 3 ERCES PLAN SHEET NO.	<input checked="" type="checkbox"/>	
ER104	ROOF ERCES PLAN SHEET NO.	<input checked="" type="checkbox"/>	
ER200	ERCES RISER DETAILS SHEET NO.	<input checked="" type="checkbox"/>	
ES001	ELECTRICAL- EARLY SITE PACKAGE PLAN	<input checked="" type="checkbox"/>	
FA001	FIRE ALARM NOTES	<input checked="" type="checkbox"/>	
FA100.A	LEVEL 1 AREA A FIRE ALARM SYSTEM	<input checked="" type="checkbox"/>	
FA100.B	LEVEL 1 AREA B FIRE ALARM SYSTEM	<input checked="" type="checkbox"/>	
FA101.A	LEVEL 2 AREA A FIRE ALARM SYSTEM	<input checked="" type="checkbox"/>	
FA101.B	LEVEL 2 AREA B FIRE ALARM SYSTEM	<input checked="" type="checkbox"/>	
FA102.A	LEVEL 3 AREA A FIRE ALARM SYSTEM	<input checked="" type="checkbox"/>	
FA102.B	LEVEL 3 AREA B FIRE ALARM SYSTEM	<input checked="" type="checkbox"/>	
FA200	RISER & MATRIX	<input checked="" type="checkbox"/>	
FP001	FIRE SPRINKLER NOTES	<input checked="" type="checkbox"/>	
FP100	OCCUPANCY HAZARD CLASSIFICATION	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
FP101	OCCUPANCY HAZARD CLASSIFICATION	<input checked="" type="checkbox"/>	
FP102	OCCUPANCY HAZARD CLASSIFICATION	<input checked="" type="checkbox"/>	
FP200	FIRE PROT. LEVEL 1-AREA A	<input checked="" type="checkbox"/>	
FP201	FIRE PROT. LEVEL 1-AREA B	<input checked="" type="checkbox"/>	
FP202	FIRE PROT. LEVEL 2-AREA A	<input checked="" type="checkbox"/>	
FP203	FIRE PROT. LEVEL 2-AREA B	<input checked="" type="checkbox"/>	
FP204	FIRE PROT. LEVEL 3-AREA A	<input checked="" type="checkbox"/>	
FP205	FIRE PROT. LEVEL 3-AREA B	<input checked="" type="checkbox"/>	
FP300	FIRE PROT. SECTIONS	<input checked="" type="checkbox"/>	
FP301	FIRE PROTECTION DETAILS	<input checked="" type="checkbox"/>	
FP301.1	FIRE PROTECTION DETAILS	<input checked="" type="checkbox"/>	
I101	INFORMATION	<input checked="" type="checkbox"/>	
I102	TAS ACCESSIBILITY REQUIREMENTS	<input checked="" type="checkbox"/>	
I103	TAS ACCESSIBILITY REQUIREMENTS	<input checked="" type="checkbox"/>	
I104	PARTITION TYPES	<input checked="" type="checkbox"/>	
I105	PARTITION TYPES	<input checked="" type="checkbox"/>	
L0.01	VEGETATION PRESERVATION & CLEARING PLAN	<input checked="" type="checkbox"/>	
L0.02	IRRIGATION SLEEVING PLAN	<input checked="" type="checkbox"/>	
L0.03	IRRIGATION SLEEVING PLAN	<input checked="" type="checkbox"/>	
L1.00	REFERENCE PLAN & NOTES	<input checked="" type="checkbox"/>	
L1.01	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.02	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.03	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.04	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.05	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.06	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.06A	GRADING PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
L1.07	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.08	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.09	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.10	HARDSCAPE ENLARGEMENT	<input checked="" type="checkbox"/>	
L1.11	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.12	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.13	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.14	HARDSCAPE PLAN	<input checked="" type="checkbox"/>	
L1.15	HARDSCAPE DETAILS	<input checked="" type="checkbox"/>	
L1.16	HARDSCAPE DETAILS	<input checked="" type="checkbox"/>	
L1.17	HARDSCAPE DETAILS	<input checked="" type="checkbox"/>	
L1.18	HARDSCAPE DETAILS	<input checked="" type="checkbox"/>	
L1.19	HARDSCAPE DETAILS	<input checked="" type="checkbox"/>	
L1.20	PAVER ENLARGEMENTS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.21	PAVER ENLARGEMENTS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.22	PAVER ENLARGEMENTS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.23	PAVER ENLARGEMENTS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.24	PAVER ENLARGEMENTS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L1.25	PAVER ENLARGEMENTS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L2.01	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.02	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.03	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.04	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.05	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L2.06	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.07	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.08	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
L2.09	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.10	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.11	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.12	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.13	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.14	LIGHTING & SITE FURNISHING PLAN	<input checked="" type="checkbox"/>	
L2.15	LIGHTING & SITE FURNISHING DETAILS	<input checked="" type="checkbox"/>	
L2.16	LIGHTING & SITE FURNISHING DETAILS	<input checked="" type="checkbox"/>	
L2.17	LIGHTING & SITE FURNISHING DETAILS	<input checked="" type="checkbox"/>	
L2.18	LIGHTING & SITE FURNISHING DETAILS	<input checked="" type="checkbox"/>	
L3.01	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.02	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L3.03	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.04	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L3.05	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.06	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.07	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L3.08	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.09	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L3.10	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.11	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.12	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.13	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.14	LANDSCAPE PLAN	<input checked="" type="checkbox"/>	
L3.15	LANDSCAPE SCHEDULE	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
L3.16	LANDSCAPE DETAILS	<input checked="" type="checkbox"/>	
L4.00	OVERALL IRRIGATION PLAN	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
L4.01	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.02	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.03	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.04	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.05	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.06	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.07	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.08	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.09	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.10	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.11	IRRIGATION PLAN	<input checked="" type="checkbox"/>	
L4.12	IRRIGATION NOTES	<input checked="" type="checkbox"/>	
L4.13	IRRIGATION DETAILS	<input checked="" type="checkbox"/>	
LS100	LIFE SAFETY NOTES	<input checked="" type="checkbox"/>	
LS101	LEVEL 1 LIFE SAFETY PLAN	<input checked="" type="checkbox"/>	
LS102	LEVEL 2 LIFE SAFETY PLAN	<input checked="" type="checkbox"/>	
LS103	LEVEL 3 LIFE SAFETY PLAN	<input checked="" type="checkbox"/>	
M000	MECHANICAL SYMBOLS & ABBREVIATIONS	<input checked="" type="checkbox"/>	
M100	CRAWLSPACE MECHANICAL PLAN - OVERALL	<input checked="" type="checkbox"/>	
M110	LEVEL 1 MECHANICAL PLAN - OVERALL	<input checked="" type="checkbox"/>	
M111	LEVEL 1 MECHANICAL PLAN - AREA A	<input checked="" type="checkbox"/>	
M112	LEVEL 1 MECHANICAL PLAN - AREA B	<input checked="" type="checkbox"/>	
M113	LEVEL 1 MECHANICAL PLAN - AREA C	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
M114	LEVEL 1 MECHANICAL PLAN - AREA D	<input checked="" type="checkbox"/>	
M120	LEVEL 2 MECHANICAL PLAN - OVERALL	<input checked="" type="checkbox"/>	
M121	LEVEL 2 MECHANICAL PLAN - AREA A	<input checked="" type="checkbox"/>	
M122	LEVEL 2 MECHANICAL PLAN - AREA B	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
M122A	LEVEL 2 MECH PLAN - AREA B ALTERNATE	<input checked="" type="checkbox"/>	
M123	LEVEL 2 MECHANICAL PLAN - AREA C	<input checked="" type="checkbox"/>	
M124	LEVEL 2 MECHANICAL PLAN - AREA D	<input checked="" type="checkbox"/>	
M130	LEVEL 3 MECHANICAL PLAN - OVERALL	<input checked="" type="checkbox"/>	
M131	LEVEL 3 MECHANICAL PLAN - AREA A	<input checked="" type="checkbox"/>	
M132	LEVEL 3 MECHANICAL PLAN - AREA B	<input checked="" type="checkbox"/>	
M133	LEVEL 3 MECHANICAL PLAN - AREA C	<input checked="" type="checkbox"/>	
M134	LEVEL 3 MECHANICAL PLAN - AREA D	<input checked="" type="checkbox"/>	
M140	ROOF MECHANICAL PLAN - OVERALL	<input checked="" type="checkbox"/>	
M201	ENLARGED MECHANICAL PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
M202	ENLARGED MECHANICAL PLAN	<input checked="" type="checkbox"/>	
M203	ENLARGED MECHANICAL PLAN	<input checked="" type="checkbox"/>	
M301	MECHANICAL SCHEDULES	<input checked="" type="checkbox"/>	
M302	MECHANICAL SCHEDULES	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
M303	MECHANICAL SCHEDULES	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
M304	MECHANICAL SCHEDULES	<input checked="" type="checkbox"/>	
M305	MECHANICAL SCHEDULES	<input checked="" type="checkbox"/>	
M306	MECHANICAL SCHEDULES	<input checked="" type="checkbox"/>	
M307	MECHANICAL SCHEDULES	<input checked="" type="checkbox"/>	
M401	MECHANICAL CONTROLS	<input checked="" type="checkbox"/>	
M402	MECHANICAL CONTROLS	<input checked="" type="checkbox"/>	
M403	MECHANICAL CONTROLS	<input checked="" type="checkbox"/>	
M404	MECHANICAL CONTROLS	<input checked="" type="checkbox"/>	
M405	MECHANICAL CONTROLS	<input checked="" type="checkbox"/>	
M406	MECHANICAL CONTROLS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
M501	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	
M502	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
M503	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	
M504	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	
M505	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	
M506	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	
M507	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	
M508	MECHANICAL DETAILS	<input checked="" type="checkbox"/>	
MH110	LEVEL 1 HYDRONICS PLAN - OVERALL	<input checked="" type="checkbox"/>	
MH111	LEVEL 1 HYDRONICS PLAN - AREA A	<input checked="" type="checkbox"/>	
MH112	LEVEL 1 HYDRONICS PLAN - AREA B	<input checked="" type="checkbox"/>	
MH113	LEVEL 1 HYDRONICS PLAN - AREA C	<input checked="" type="checkbox"/>	
MH114	LEVEL 1 HYDRONICS PLAN - AREA D	<input checked="" type="checkbox"/>	
MH120	LEVEL 2 HYDRONICS PLAN - OVERALL	<input checked="" type="checkbox"/>	
MH121	LEVEL 2 HYDRONICS PLAN - AREA A	<input checked="" type="checkbox"/>	
MH122	LEVEL 2 HYDRONICS PLAN - AREA B	<input checked="" type="checkbox"/>	
MH123	LEVEL 2 HYDRONICS PLAN - AREA C	<input checked="" type="checkbox"/>	
MH124	LEVEL 2 HYDRONICS PLAN - AREA D	<input checked="" type="checkbox"/>	
MH130	LEVEL 3 HYDRONICS PLAN - OVERALL	<input checked="" type="checkbox"/>	
MH131	LEVEL 3 HYDRONICS PLAN - AREA A	<input checked="" type="checkbox"/>	
MH132	LEVEL 3 HYDRONICS PLAN - AREA B	<input checked="" type="checkbox"/>	
MH133	LEVEL 3 HYDRONICS PLAN - AREA C	<input checked="" type="checkbox"/>	
MH134	LEVEL 3 HYDRONICS PLAN - AREA D	<input checked="" type="checkbox"/>	
P000	PLUMBING SYMBOLS & ABBREVIATIONS	<input checked="" type="checkbox"/>	
P001	PLUMBING SITE PLAN	<input checked="" type="checkbox"/>	
P101	UNDERFLOOR PLUMBING PLAN - AREA A	<input checked="" type="checkbox"/>	
P101C	CRAWLSPACE PLUMBING PLAN - AREA A	<input checked="" type="checkbox"/>	
P102	UNDERFLOOR PLUMBING PLAN - AREA B	<input checked="" type="checkbox"/>	
P102C	CRAWLSPACE PLUMBING PLAN - AREA B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
P103	UNDERFLOOR PLUMBING PLAN - AREA C	<input checked="" type="checkbox"/>	
P103C	CRAWLSPACE PLUMBING PLAN - AREA C	<input checked="" type="checkbox"/>	
P104	UNDERFLOOR PLUMBING PLAN - AREA D	<input checked="" type="checkbox"/>	
P104C	CRAWLSPACE PLUMBING PLAN - AREA D	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
P111	LEVEL 1 PLUMBING PLAN - AREA A	<input checked="" type="checkbox"/>	
P112	LEVEL 1 PLUMBING PLAN - AREA B	<input checked="" type="checkbox"/>	
P113	LEVEL 1 PLUMBING PLAN - AREA C	<input checked="" type="checkbox"/>	
P114	LEVEL 1 PLUMBING PLAN - AREA D	<input checked="" type="checkbox"/>	
P121	LEVEL 2 PLUMBING PLAN - AREA A	<input checked="" type="checkbox"/>	
P122	LEVEL 2 PLUMBING PLAN - AREA B	<input checked="" type="checkbox"/>	
P123	LEVEL 2 PLUMBING PLAN - AREA C	<input checked="" type="checkbox"/>	
P124	LEVEL 2 PLUMBING PLAN - AREA D	<input checked="" type="checkbox"/>	
P131	LEVEL 3 PLUMBING PLAN - AREA A	<input checked="" type="checkbox"/>	
P132	LEVEL 3 PLUMBING PLAN - AREA B	<input checked="" type="checkbox"/>	
P133	LEVEL 3 PLUMBING PLAN - AREA C	<input checked="" type="checkbox"/>	
P134	LEVEL 3 PLUMBING PLAN - AREA D	<input checked="" type="checkbox"/>	
P140	ROOF PLUMBING PLAN - OVERALL	<input checked="" type="checkbox"/>	
P201	PLUMBING ENLARGED PLANS	<input checked="" type="checkbox"/>	
P202	PLUMBING ENLARGED PLANS	<input checked="" type="checkbox"/>	
P203	PLUMBING ENLARGED PLANS	<input checked="" type="checkbox"/>	
P204	PLUMBING ENLARGED PLANS	<input checked="" type="checkbox"/>	
P301	PLUMBING SCHEDULES	<input checked="" type="checkbox"/>	
P400	PLUMBING RISERS - DOMESTIC	<input checked="" type="checkbox"/>	
P401	PLUMBING RISERS - WASTE	<input checked="" type="checkbox"/>	
P402	PLUMBING RISERS - STORM	<input checked="" type="checkbox"/>	
P501	PLUMBING DETAILS	<input checked="" type="checkbox"/>	
P502	PLUMBING DETAILS	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
P503	PLUMBING DETAILS	<input checked="" type="checkbox"/>	
P504	PLUMBING DETAILS	<input checked="" type="checkbox"/>	
P505	PLUMBING DETAILS	<input checked="" type="checkbox"/>	
P506	PLUMBING DETAILS	<input checked="" type="checkbox"/>	
R101	LEVEL 1 - OVERALL FIREPROOFING PLAN	<input checked="" type="checkbox"/>	
R102	LEVEL 2 - OVERALL FIREPROOFING PLAN	<input checked="" type="checkbox"/>	
S010	ABBREVIATIONS, SYMBOLS AND GENERAL NOTES	<input checked="" type="checkbox"/>	
S011	GENERAL NOTES	<input checked="" type="checkbox"/>	
S012	GENERAL NOTES	<input checked="" type="checkbox"/>	
S013	GENERAL NOTES	<input checked="" type="checkbox"/>	
S101	LEVEL 1 - OVERALL LOAD MAP	<input checked="" type="checkbox"/>	
S102	LEVEL 2 - OVERALL LOAD MAP	<input checked="" type="checkbox"/>	
S103	LEVEL 3 - OVERALL LOAD MAP	<input checked="" type="checkbox"/>	
S104	ROOF - OVERALL LOAD MAP	<input checked="" type="checkbox"/>	
S110	FOUNDATION PLAN- OVERALL	<input checked="" type="checkbox"/>	
S111	FOUNDATION PLAN - AREA A	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S112	FOUNDATION PLAN - AREA B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S113	FOUNDATION PLAN - AREA C	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S114	FOUNDATION PLAN - AREA D	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S115	CHILLER YARD FOUNDATION - PLAN & DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S120	LEVEL 2 FRAMING PLAN - OVERALL	<input checked="" type="checkbox"/>	
S121	LEVEL 2 FRAMING PLAN - AREA A	<input checked="" type="checkbox"/>	
S122	LEVEL 2 FRAMING PLAN - AREA B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S123	LEVEL 2 FRAMING PLAN - AREA C	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S124	LEVEL 2 FRAMING PLAN - AREA D	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S130	LEVEL 3 FRAMING PLAN - OVERALL	<input checked="" type="checkbox"/>	
S131	LEVEL 3 FRAMING PLAN - AREA A	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
S132	LEVEL 3 FRAMING PLAN - AREA B	<input checked="" type="checkbox"/>	
S133	LEVEL 3 FRAMING PLAN - AREA C	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S134	LEVEL 3 FRAMING PLAN - AREA D	<input checked="" type="checkbox"/>	
S140	ROOF FRAMING PLAN - OVERALL	<input checked="" type="checkbox"/>	
S141	ROOF FRAMING PLAN - AREA A	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S142	ROOF FRAMING PLAN - AREA B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S143	ROOF FRAMING PLAN - AREA C	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S144	ROOF FRAMING PLAN - AREA D	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S150	DRIVE THRU FRAMING PLANS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S151	TUNNEL DETAILS	<input checked="" type="checkbox"/>	
S301	DRILLED PIER SCHEDULE, NOTES& TYPICAL DETAIL	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S302	DRILLED PIER TYPICAL DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S303	EXPANSIVE CLAY SOIL DETAILS	<input checked="" type="checkbox"/>	
S304	TYPICAL FOUNDATION DETAILS	<input checked="" type="checkbox"/>	
S305	TYPICAL FOUNDATION DETAILS	<input checked="" type="checkbox"/>	
S306	TYPICAL FOUNDATION DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S310	CONCRETE SECTIONS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S401	STEEL COLUMN DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S402			<input checked="" type="checkbox"/>
S403	TYPICAL STEEL BEAM CONNECTION DETAILS	<input checked="" type="checkbox"/>	
S404	TYPICAL STEEL BEAM CONNECTION DETAILS	<input checked="" type="checkbox"/>	
S405	TYPICAL COMPOSITE STEEL DETAILS	<input checked="" type="checkbox"/>	
S406	TYPICAL COMPOSITE STEEL DETAILS	<input checked="" type="checkbox"/>	
S407	TYPICAL STEEL CONNECTION DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S408	TYPICAL STEEL DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S409	STEEL DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S410	STEEL DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
S411	STEEL DETAILS	<input checked="" type="checkbox"/>	
S501	TYPICAL STEEL ROOF DETAILS	<input checked="" type="checkbox"/>	
S502	TYPICAL STEEL ROOF DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S503	TYPICAL STEEL ROOF DETAILS	<input checked="" type="checkbox"/>	
S504	STEEL ROOF DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S505			<input checked="" type="checkbox"/>
S506	ENTRY CANOPY	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S507	STEEL ROOF DETAILS	<input checked="" type="checkbox"/>	
S601	WIND BRACE ELEVATIONS	<input checked="" type="checkbox"/>	
S602	WIND BRACE TYPICAL DETAILS	<input checked="" type="checkbox"/>	
S603	FRAMING ELEVATIONS	<input checked="" type="checkbox"/>	
S701	LOBBY STAIR	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
S702	LOBBY STAIR	<input checked="" type="checkbox"/>	
T000	TECHNOLOGY SYMBOLS & LEGEND	<input checked="" type="checkbox"/>	
T100	TECHNOLOGY SITE PLAN	<input checked="" type="checkbox"/>	
T110	TECHNOLOGY LEVEL 1 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
T111	TECHNOLOGY LEVEL 1 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
T112	TECHNOLOGY LEVEL 1 - FLOOR PLAN B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
T113	TECHNOLOGY LEVEL 1 - FLOOR PLAN C	<input checked="" type="checkbox"/>	
T114	TECHNOLOGY LEVEL 1 - FLOOR PLAN D	<input checked="" type="checkbox"/>	
T120	TECHNOLOGY LEVEL 2 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
T121	TECHNOLOGY LEVEL 2 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
T122	TECHNOLOGY LEVEL 2 - FLOOR PLAN B	<input checked="" type="checkbox"/>	
T123	TECHNOLOGY LEVEL 2 - FLOOR PLAN C & D	<input checked="" type="checkbox"/>	
T130	TECHNOLOGY LEVEL 3 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
T131	TECHNOLOGY LEVEL 3 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
T132	TECHNOLOGY LEVEL 3 - FLOOR PLAN B	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
T133	TECHNOLOGY LEVEL 3 - FLOOR PLAN C	<input checked="" type="checkbox"/>	
T134	TECHNOLOGY LEVEL 3 - FLOOR PLAN D	<input checked="" type="checkbox"/>	
T300	TECHNOLOGY ENLARGED VIEWS	<input checked="" type="checkbox"/>	
T301	TECHNOLOGY ENLARGED VIEWS	<input checked="" type="checkbox"/>	
T302	TECHNOLOGY ENLARGED VIEWS	<input checked="" type="checkbox"/>	
T400	TECHNOLOGY TYPICAL DETAILS	<input checked="" type="checkbox"/>	
T401	TECHNOLOGY TYPICAL DETAILS	<input checked="" type="checkbox"/>	
TA000	AUDIOVISUAL SYMBOLS & LEGEND	<input checked="" type="checkbox"/>	
TA110	AUDIOVISUAL LEVEL 1 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
TA111	AUDIOVISUAL LEVEL 1 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
TA112	AUDIOVISUAL LEVEL 1 - FLOOR PLAN B	<input checked="" type="checkbox"/>	
TA113	AUDIOVISUAL LEVEL 1 - FLOOR PLAN C	<input checked="" type="checkbox"/>	
TA114	AUDIOVISUAL LEVEL 1 - FLOOR PLAN D	<input checked="" type="checkbox"/>	
TA115	AUDIOVISUAL LEVEL 1 - CEILING PLAN A & B	<input checked="" type="checkbox"/>	
TA116	AUDIOVISUAL LEVEL 1 - CEILING PLAN C & D	<input checked="" type="checkbox"/>	
TA120	AUDIOVISUAL LEVEL 2 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
TA121	AUDIOVISUAL LEVEL 2 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
TA122	AUDIOVISUAL LEVEL 2 - FLOOR PLAN B	<input checked="" type="checkbox"/>	
TA123	AUDIOVISUAL LEVEL 2 - FLOOR PLAN C & D	<input checked="" type="checkbox"/>	
TA124	AUDIOVISUAL LEVEL 2 - CEILING PLAN A & B	<input checked="" type="checkbox"/>	
TA125	AUDIOVISUAL LEVEL 2 - CEILING PLAN C & D	<input checked="" type="checkbox"/>	
TA130	AUDIOVISUAL LEVEL 3 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
TA131	AUDIOVISUAL LEVEL 3 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
TA132	AUDIOVISUAL LEVEL 3 - FLOOR PLAN B	<input checked="" type="checkbox"/>	
TA133	AUDIOVISUAL LEVEL 3 - FLOOR PLAN C	<input checked="" type="checkbox"/>	
TA135	AUDIOVISUAL LEVEL 3 - CEILING FLOOR PLAN A & B	<input checked="" type="checkbox"/>	
TA136	AUDIOVISUAL LEVEL 3 - CEILING FLOOR PLAN C & D	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
TA300	ENLARGED ELEVATION	<input checked="" type="checkbox"/>	
TA301	ENLARGED ELEVATION	<input checked="" type="checkbox"/>	
TA302	ENLARGED ELEVATION	<input checked="" type="checkbox"/>	
TA303	ENLARGED ELEVATION	<input checked="" type="checkbox"/>	
TA400	AUDIOVISUAL TYPICAL DETAILS	<input checked="" type="checkbox"/>	
TS000	SECURITY SYMBOLS & LEGEND	<input checked="" type="checkbox"/>	
TS100	SECURITY SITE PLAN	<input checked="" type="checkbox"/>	
TS110	SECURITY LEVEL 1 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
TS111	SECURITY LEVEL 1 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
TS112	SECURITY LEVEL 1 - FLOOR PLAN B	<input checked="" type="checkbox"/>	
TS113	SECURITY LEVEL 1 - FLOOR PLAN C	<input checked="" type="checkbox"/>	
TS114	SECURITY LEVEL 1 - FLOOR PLAN D	<input checked="" type="checkbox"/>	
TS120	SECURITY LEVEL 2 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
TS121	SECURITY LEVEL 2 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
TS122	SECURITY LEVEL 2 - FLOOR PLAN B	<input checked="" type="checkbox"/>	
TS123	SECURITY LEVEL 2 - FLOOR PLAN C	<input checked="" type="checkbox"/>	
TS124	SECURITY LEVEL 2 - FLOOR PLAN D	<input checked="" type="checkbox"/>	
TS130	SECURITY LEVEL 3 - OVERALL FLOOR PLAN	<input checked="" type="checkbox"/>	
TS131	SECURITY LEVEL 3 - FLOOR PLAN A	<input checked="" type="checkbox"/>	
TS132	SECURITY LEVEL 3 - FLOOR PLAN B	<input checked="" type="checkbox"/>	
TS133	SECURITY LEVEL 3 - FLOOR PLAN C	<input checked="" type="checkbox"/>	
TS134	SECURITY LEVEL 3 - FLOOR PLAN D	<input checked="" type="checkbox"/>	
TS400	SECURITY TYPICAL DETAILS	<input checked="" type="checkbox"/>	
TS401	SECURITY TYPICAL DETAILS	<input checked="" type="checkbox"/>	
TS500	SECURITY SCHEDULES	<input checked="" type="checkbox"/>	
TS501	SECURITY SCHEDULES	<input checked="" type="checkbox"/>	
001	VOL1- DRAWING INDEX	<input checked="" type="checkbox"/>	

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
01	Site Development Cover Sheet	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
001A	SITE PLAN	<input checked="" type="checkbox"/>	
001B	Cover Sheet	<input checked="" type="checkbox"/>	
002	VOL 2 - DRAWING INDEX	<input checked="" type="checkbox"/>	
02	GENERAL NOTES	<input checked="" type="checkbox"/>	
03	EXISTING CONDITIONS AND DEMOLITION PLAN	<input checked="" type="checkbox"/>	
04	EROSION & SEDIMENTATION PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
05	EROSION& SEDIMENTATION CONTROL PLAN DETAIL	<input checked="" type="checkbox"/>	
06	OVERALL SITE AND PAVING PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
07	SITE PLAN - A	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
08	SHEET TITLE SITE PLAN - B	<input checked="" type="checkbox"/>	
09	SITE PLAN - C	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
10	SITE PLAN - D	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
11	SITE PLAN DETAILS	<input checked="" type="checkbox"/>	
12	EXISTING DRAINAGE AREA MAP	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
13	EXISTING OFFSITE DRAINAGE AREA MAP	<input checked="" type="checkbox"/>	
14	PROPOSED DRAINAGE AREA MAP	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
15	MASTER GRADING PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
16	GRADING PLAN - A	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
17	GRADING PLAN - B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
18	GRADING PLAN - C	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
19	GRADING PLAN - D	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
20	MASTER DRAINAGE PLAN	<input checked="" type="checkbox"/>	
21	DRAINAGE PLAN - A	<input checked="" type="checkbox"/>	
22	SHEET TITLE DRAINAGE PLAN - B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
23	DRAINAGE PLAN - C	<input checked="" type="checkbox"/>	
24	DRAINAGE PLAN - D	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Number	Title	May 24, 2024	Jun 27, 2024
		Addendum 3	Addendum 4
25	GRADING AND DRAINAGE DETAILS 1	<input checked="" type="checkbox"/>	
26	GRADING AND DRAINAGE DETAILS 2	<input checked="" type="checkbox"/>	
27	GRADING AND DRAINAGE DETAILS 3	<input checked="" type="checkbox"/>	
28	WATER QUALITY DRAINAGE AREA MAP	<input checked="" type="checkbox"/>	
29	WATER QUALITY POND & VEGETATIVE FILTER STRIP	<input checked="" type="checkbox"/>	
30	POND DETAILS 1	<input checked="" type="checkbox"/>	
31	POND DETAILS 2	<input checked="" type="checkbox"/>	
32	WATER & WASTEWATER PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
33	FIRE PROTECTION PLAN	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
34	UTILITY DETAILS	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
35	CRAWLSPACE DRAINAGE AND GRADING PLAN	<input checked="" type="checkbox"/>	
22020	COVER SHEET	<input checked="" type="checkbox"/>	

Specifications Dated 5.23.24
 Specifications Dated 6.20.24 (Addendum #4)
 Geotechnical Report 11.2.23



Qualifications & Clarifications



General Project Description

The project consists of a new 120,224 sf 3-story Class A headquarters facility which will consolidate county administrative and business operations in a single modern facility that will support county governance for the foreseeable future. The Structure will have a cast in place concrete foundation and structural steel with a glass curtain wall and masonry exterior for floors one, two and three, a PVC roof, state of the art MEP and Special Systems, high level interior finishes and all associated site work and utilities. The project will be located in Georgetown, Texas.

Clarifications, Assumptions and Qualifications

- Design Services
- Architectural and Engineering design services are excluded
- Geotechnical Engineering and soils analysis reports are excluded

General Requirements

- **Supervision and Administration**
 - Project supervision includes Project Superintendents with Project Management, Safety Coordinator, Estimating, and Administrative Assistants as necessary to complete the project as scheduled.
- **Temporary Facilities**
 - Project field office
 - Project storage containers as required
 - Project office supplies
 - Project office equipment as required
 - Project sign and safety signs
 - Temporary toilets
 - Site fencing and gates
 - Barricades and guard rails as required
- **Project Services**
 - Field engineering and layout
 - General cleanup and haul away trash
 - Final cleaning
 - After hours or weekend job site security are not included in our price
- **Personnel Hoisting**
 - Material and Personnel hoist as required
- **Temporary Utilities**
 - Field telephone service
 - Price includes electrical power consumption and temporary lighting required for construction up until permanent power is hooked up and operational. Once permanent power is connected, all subsequent electrical service costs shall be the responsibility of the Owner.
- **Equipment**
 - Transportation for supervisory personnel (rental of company owned vehicles)
 - Expendable tools
 - Small equipment rental

Permits, Bonds and Insurance

- The cost of all site and building permits are excluded
- Mechanical, Electrical & Plumbing trade permits are included
- Plan review Fees are excluded
- Price Excludes Utility Connection Fees, Recovery Fees, City Improvement & Aid Fees, Impact Fees and Assessment Fees
- General Liability, Auto, Worker Compensation, and Builders Risk Insurance are included
- The price includes the cost of performance and payment bonds

Project Schedule, Weather, and Work Hours

- Schedule
 - The Project Schedule will include pre-construction and construction activities and when fully developed will serve as the basis for the time required to complete the project
- Work Hours
 - Normal working days are Monday through Friday, excluding holidays. Work may take place at night or on weekends as coordinated with the Owner.

Environmental

- We have assumed that all environmental investigations and permits will be accomplished and paid for by the Owner if required
- The handling or abatement of hazardous materials are not included in this estimate

Building Inspections

- Inspections will be provided as required by local jurisdiction

Layout & Engineering

- Layout and engineering as required

**Materials Testing**

- Materials Testing is by Owner

Jobsite Equipment - 01-5430

- Crane/Lifts 10 mo
- Temporary Shoring 1 LS

Mechanical Screen Fence - 02-0440

- Material & Install 1 LS
- Condensing Unit 35'-0" x 8'-0" 1 1 LS
- Condensing Unit 7'-2" x 8'-0" 1, Double Swing 1 LS
- Chiller Pad 94'-0" x 10'-0 1 1 LS
- Chiller Pad 3'-9" x 10'-0" 1, Single Swing 1 LS
- Chiller Pad 11'-0" x 10'-0" 1 1 LS
- Dumpster Enclosure 16'-0" x 9'-0" 1, Double Swing 1 LS
- Install 1 LS

Miscellaneous - 03-0300

- **Temporary Fall Protection** 1 LS
- **RFI #17**
 - 18" Rcp Ssl (7) LF
 - 24" Rcp Ssl 24 LF
 - Upgrade Rcp Bends To 24" 1 EA
- **RFI #32**
 - Deduct 4" Domestic Waterline (505) LF
 - Add 2" Domestic Waterline 505 LF
- **Addendum #3- Sitework**
 - Revised Grading At Trail Near Slope 1 LS
- **Addendum #3- Water**
 - Upgrade RPA Enclosure- Hubble HB- 10E 1 EA
 - Deduct 4" Meter Assembly W/Vault (1) EA
 - Deduct 4" Backflow Preventer W/ Vault (1) EA
 - Deduct 2" Irrigation Meter W/ RPZ (1) EA
 - Add 4" Copper Waterline 40 LF
 - Add 3" Ultrasonic Meter Assembly W/ Vault- DOM 1 EA
 - Add 3" Backflow Preventer W/ Vault- DOM 1 EA
 - Add 3" Ultrasonic Meter Assembly W/ Vault- Irrigation 1 EA
 - Add 2" Zurn Backflow Preventer Assembly- Irrigation 1 EA
 - Add Additional 12" Bends 2 EA
- **Addendum #3- Gas**
 - Gas Trench And Backfill 880 LF
 - 2" Poly Gas Line 880 LF
 - 2" Service Riser 1 EA
 - Hot Tap Tie-In 1 EA
- **Electric Ductbank- Rev Per Gus**
 - Deduct 4" Conduit (1,470) LF
 - Add 2" Conduit Per Gus 1,960 LF
 - Add Transformer Pad 1 EA
 - Add Flow Fill At Screenwall Footing 10 CY
- **Addendum #3- Telecom Changes**
 - Trench Bed And Backfill 1,373 LF
 - 2" Conduit And Fittings 373 LF
 - 4" Conduit And Fittings 2,000 LF
 - 36"X36" Telecom Manhole 3 EA
 - Pull Tape And Proofing 2,373 LF
- **Revised Onsite Telecom**
 - Trench Bed and Backfill 1,373 LF
 - 2" Conduit & Fittings 373 LF
 - 4" Conduit & Fittings 2,000 LF
 - 36" x 36" Telcom Manhole 3 EA
 - Pull tape and Proofing 2,373 EA
 - 3PH Transformer 1
 - 2" Conduits & Fittings 490 LF

**Site Concrete - 03-5100**

• 6" Concrete Paving	7,810	SF
• Integral Curb	290	LF
• Curb & Gutter	915	LF
• Site Sidewalk	3,980	SF
• HC Ramps- Large	4	EA
• Sidewalk- Roadway	14,535	SF
• Sidewalk- Building	8,550	SF
• Sidewalk Heavy Duty- Building	1,465	SF
• Sidewalk- Acid Etch	3,205	SF
• Sidewalk Steps- Acid Etch	330	TRFT
• Concrete Wall @ Landing- Sidewalk	4	CY
• Island Concrete Cap	400	SF
• Drive Thru Maintenance Pad	45	SF
• Site Bollard	22	EA
• Collapsible Bollard	22	EA
• Light Pole Base	42	EA
• Light Column Base	112	EA
• Bollard Light Pad	45	EA
• Flagpole Base	2	EA
• Light Pole Base Collar	31	EA
• Light Column Base- Collar	112	EA
• Site Concrete- Addendum #4		
• 6" Concrete Paving	195	SF
• Concrete Flume Curb	10	LF
• Concrete Flume	30	SF
• Sidewalk - Building	45	SF

Building Concrete - 03-5300

• Elevator Pit	30	CY
• 3,5" Slab on Metal Deck- FI 1,2, & 3	124,384	SF
• Concrete- Pan Stairs	12	FLGT
• Interior MEP Pads	1,272	SF
• Exterior MEP Pads	588	SF
• Drive Thru Foundations	13	CY
• Drive Thru- Tunnel Complete	93	LF
• Screen Wall Footing	198	LF
• Building Concrete- Addendum #4	1	LS
• Columns/ Slab on Void Added Rebar	1	LS
• Slab on Grade Added Embeds	4	EA
• 18" Pier at Screenwall Add	5	EA

**Masonry - 04-0200**

• Standard Grey CMU At CMU Vault/Research/Storage of Building	1 LS
• Standard Grey CMU At Site Walls	1 LS
• Interior Cream Limestone Panels On Honeycomb Backing	1 LS
• Exterior Cream Limestone Panels (Typ. 48" Tall X 16" Long)	1 LS
• Cream Limestone Cut Stone Sills, and Copings	1 LS
• Site Landscape Cream Limestone Veneer (W1, W2, W3, W4) (9X20 Veneer & 4X20 Bands)	1 LS
• Site Landscape Cream Limestone Caps (W1, W2,W3, W4)	1 LS
• Split Face CMU at Service Yard/ Dumpster Screen Wall with Stone Veneer & Stone Cap	1 LS
• Rebar Reinforcing For CMU Walls (No Dowels)	1 LS
• Typical Rebar Shop Drawings	1 LS
• Setting of Hollow Metal Door Frames in CMU Walls	1 LS
• Stone At Drive Through Canopy A002, A003	1 LS
• Site Stair Wall A005, A009	1 LS
• Shop Drawings For Stone Veneer and Caps	1 LS
• Labor, Labor-Related Taxes & Insurance	1 LS
• Equipment (For Bricklayers' Use Only)	1 LS
• Wash-Down @ New Masonry (Not Grey CMU)	1 LS
• Masonry At Mock-Up Wall & Mock-Up At V Column Per A010	1 LS
• Two (2) Mobilization and Set-Ups	1 LS
• Regularly Scheduled Visits From Our Full-Time Corp. Safety Director	1 LS
• Certified Competent-Person Scaffold Erection Supervision	1 LS
• Licensed Forklift Operators	1 LS
• Wire, Ties, and Accessories	1 LS
• Grout Fill @ Masonry	1 LS
• Temporary Bracing of New CMU Walls to Slab Per industry Standard	1 LS
• Installation of Loose Lintels (Supplied By Others) Up to 100 Lbs	1 LS
• Additional mobilizations (beyond 2 included in base bid)	2 LS
• Proposal is contingent upon the use of an Engineered anchor Allowance of \$197,800	1 LS
• Includes the exterior stone panels with the high hat/ channels and stone anchors, the standard stone anchors at the stone sills and caps, & the standard stainless steel wall ties with polymer coated screws at the site landscape veneer	
• Proposal is made contingent upon the portion of the service yard screen wall that is Split face CMU on both sides to be installed as doubled wythe 4" CMU split face- not a 8" split face CMU.	
• Proposal is made contingent upon the 8" CMU 4-hr walls of the Vault/ Research/ Storage walls vertical reinforcing being based on 1-#5 @48" OC typical and the walls being grouted solid for the 4-hr rating requirement.	
• Proposal is contingent upon the cream limestone being provided from an alternate stone manufacturer than those listed in the specs. (044313-2,1&2.2) Cream limestone provided will be either a Texas Cream or Cordova Cream, not the Austin Crème due larger piece sizes producing much more waste of material from the Austin Crème.	
• Grey CMU will have a range of color and texture that is present from the manufacturer. This pricing is made contingent upon all exposed Grey CMU being painted or covered by others. Brazos Masonry is not responsible for color or texture ranges found in exposed Grey CMU walls.	
• The interior stone on honey comb backing will be from a separate manufacturer than the rest of the cream limestone and is not guaranteed to match the exterior stone.	
• Bond	1 LS

Structural Steel - 05-0000

• 10 Ton Allowance	1 LS
• Misc Steel	1 LS
• Bond	1 LS
• Fabricated Miscellaneous Steel	
• Inclusions	
• Structural Steel: 964 Tons of structural steel consisting of the following:	
• Columns	1 LS
• Beams	1 LS
• AESS V columns at Balcony and Drive Thru	1 LS
• Moment connections where shown on plans	1 LS
• Shear studs supply and installed	1 LS
• Deck edge angle and bent plate	1 LS
• Overhead door jamb tubes	1 LS
• Elevator guide rail support posts	1 LS
• Elevator divider beams	1 LS
• Elevator hoist beams	1 LS
• RTU support frames	1 LS
• Roof drain support frames	1 LS
• Beam lateral bracing	1 LS
• Column bracing angles	1 LS
• Deck support angles at column penetrations per 12/S405	1 LS
• Wind bracing	1 LS
• Drive Thru framing	1 LS
• Roof tie-off anchor framing per 7/S503 with Davits & Tiebacks for Window Washing	1 LS
• Hanging curtain support framing at Commissioners Court E2201 per 3/S410	1 LS
• Balcony Storefront support framing per 12/S410	1 LS
• Masonry hangar support framing per 3/S408 and similar	1 LS
• Areaway steel grating and embedded steel angle frames	1 LS
• Elevator sump pit steel grating and embedded steel angle frames	1 LS
• Embedded beam bearing assemblies Quantity of 12	1 LS
• Mockup material per A010 Quantity of 6	1 LS
• Dias wall steel support per B5/A424 Quantity of 4	1 LS
• Structural steel in the crawl space to be coated with Carboline "Carboguard 890" single coat epoxy primer. All other steel to be shop primed with the exception of steel that receives fireproofing	1 LS
• Fabricated Miscellaneous Steel: 28 tons of fabricated miscellaneous metals as follows:	
• Interior concrete pan stair E-1B	
• HSS 12x2 stringers	1 LS
• 56 total risers	1 LS
• DECORATIVE RAILING EXCLUDED	1 LS
• Primed	1 LS
• Interior concrete pan stair W-4	1 LS
• HSS 12x2 stringers	1 LS
• 56 total risers	1 LS
• 52 l.f. sloped steel 10-line rail (attached SS handrail by others)	1 LS
• 18 l.f. steel 10-line guardrail	1 LS
• SS wall rail by others	1 LS
• 12 l.f. steel cane detection rails	1 LS
• Primed	1 LS
• Interior concrete pan stair E-3	1 LS
• HSS 12x2 stringers	1 LS
• 56 total risers	1 LS
• 52 l.f. sloped steel 10-line rail (attached SS handrail by others)	1 LS
• 37 l.f. steel 10-line guardrail	1 LS
• SS wall rail by others	1 LS
• 12 l.f. steel cane detection rails	1 LS
• Primed	1 LS
• Interior Terrazzo tread Lobby stair	1 LS
• HSS 16x16 with ½" plate stringers	1 LS
• 28 total risers	1 LS
• SS RAILING by others	1 LS
• Primed	1 LS
• Steel elevator pit ladders – galvanized. Quantity of 3	1 LS
• Steel floor hatch access ladders – galvanized. Quantity of 2	1 LS
• Aluminum O'Keefe 523A roof hatch access ship's ladders – mill finish. Quantity of 2	1 LS
• Pair steel Dumpster enclosure gate frames – galvanized. Gate skins by others	1 LS
• Pair steel Chiller enclosure gate frames – galvanized. Gate skins by others	1 LS
• 35 l.f. steel 3-line guardrail at CIP stair South – galvanized	1 LS



- 14 l.f. steel 3-line guardrail at CIP stair West – galvanized 1 LS
- **Metal Deck: 1,933 Squares of metal deck and accessories as follows:** 1 LS
 - Type 3VLI, 20ga, G90 decking. Approx 484 sqs 1 LS
 - Type 3VLI, 20ga, G30 decking. Approx 853 sqs 1 LS
 - Type 1.5B, 22ga, G60 decking. Approx 504 sqs 1 LS
 - Type 3NL-32, 22ga, G60 decking. Approx 92 sqs 1 LS
- **Joists, Girders, and Bridging: 38 Tons of girders, joists and bridging as follows:** 1 LS
 - 176 total pieces 1 LS
 - Gray primer 1 LS
- **Standard Exclusions**
 - In addition to any items not specifically included in the "Inclusions" section, the following items are excluded, unless otherwise noted.
 - Cost of testing or inspection
 - Liquidated damages
 - Gaged metal
 - Non-ferrous metal fabrications
 - Fasteners for other trades
 - Standing seam roof decking and accessories
 - Gutter and downspout components
 - Any item not specifically included
 - Removal of decking from openings
 - Items bolted to concrete or masonry
 - Expansion joints and related components
 - All Stair Nosing Materials
 - Cost of permits
 - Taxes (UNO)
 - Installation of embedded items
 - Supply of and installation of grout
 - Supply of and application of touch up paint (Covered by Chasco)
 - Installation of wall mounted handrails
 - Reinforcing steel, wire mesh & accessories
 - Cleaning of steel (Covered by Chasco)
 - Furnishing copies of Insurance Policies
 - Field measurements or surveys (Covered by Chasco)
 - Safety Cables: furnish, maintenance, removal
 - Matting for cranes
 - Temporary shoring or bracing
 - Retained funds on materials
 - LEED Category MR-5
 - Permanent Horizontal Life Line Systems
 - Planters and Steel Edging
- **Project Specific Exclusions**
 - All Exclusions listed above in the Standard Exclusions where applicable for this project UNO in the Inclusions above
 - Installation of Wall Rails
 - Core Drilling of concrete for rail installation
 - Grout or Grouting
 - Any Light Gage Studs, Framing, Deck Installation Over, & Associated Hardware
 - All Unistrut Components, Hardware, and Installation
 - Any Aluminum, Stainless Steel, Brass, Bronze, Glass, or Cast Material & Associated Hardware
 - All Railing noted as being Decorative or Ornamental
 - All Chain Link and Gauge Metal Tube Steel Fencing, Posts, & Associated Hardware
 - Any Light Poles, Flag Poles, Signs, Signposts, & Associated Hardware
 - Bike Racks
 - Stud Rails
 - Powder Coating, Blackened, Bluing, etc. of steel unless specifically noted in the inclusions above
 - Demolition, Repair, Re-Installation, Removal, and Disposal of Existing Materials
- Cages for Exterior Roof Access Ladders – No Longer Required per Updated OSHA 1910.23 Standard
- Any Fall Arrest Systems for Ladders
- Taxes
- Ametco fencing at Chiller Pad
- Decorative railing
- Slotted channel framing
- Transverse loading of joist
- **Deduct for Shop Drawings in Bid Package 2A** (\$225,000)



Rough Carpentry - 06-0100

• Rough Carpentry	1 LS
• Bond	1 LS

Finish Carpentry & Cabinets - 06-2200

• See attached proposal	1 LS
• Forms+Surfaces Column Covers	16 LS
• Bond	1 LS



P.O. BOX 71
HUTTO, TX 78634
PH: (512) 759-1330 FAX (512) 759-1332

Bid Sheet for:

Chasco Constructors

DATE

7/24/2024

Project	BID- NEW WILLIAMSON COUNTY HEADQUARTERS FACILITY
Project Address	1848 Texas Trail Georgetown, Tx. 78626
Contact:	Scott Badgett
E-mail	scott@chasco.com
Phone #	512 244 0600

INCLUDED IN SCOPE

SHEET A111

ENLARGED PLAN D2/A402, ELEVATION A2/A408 & A3/A408 (DRIVE•THRU / CASHIER W1535):

- A&M 2.0 CONCEALED IN•WALL SUPPORT BRACKETS
- PL•1 BASE CABINETS WITH MELAMINE INTERIORS
- SSM1 SOLID SURFACE COUNTERTOP

SHEET A111

ENLARGED PLAN C3/A401, ELEVATION A2/A408 & A3/A408 & C3/A408 (TAX LOBBY COUNTERS W1501):

- A&M 2.0 CONCEALED IN•WALL SUPPORT BRACKETS
- PL•1 BASE CABINETS WITH MELAMINE INTERIORS
- SSM1 SOLID SURFACE COUNTERTOP
- WP•1 3FORM FRAMED DIVIDER PANELS
- (WC2 WALL COVERING BY OTHERS , KNEE WALLS BY OTHERS)

SHEET A112

ENLARGED PLAN A1/A401, ELEVATION A4/A405, B3/A405 & B4/A405 (COFFEE W1545):

- PL•3 BASE CABINETS WITH MELAMINE INTERIORS
- PL•3 FLOATING SHELVES
- PL•3 WHITE UPPER CABINETS WITH WHITE MELAMINE INTERIORS
- SSM2 SOLID SURFACE COUNTERTOP
- SHOP•FABRICATED BLACK P•LAM BOOTH FRAMES WITH UPH3 UPHOLSTERED SEAT BACKS, UPH2 UPHOLSTERED SEAT BOTTOMS
- SSM2 WALL CAP
- MP1 LASER•CUT METAL PANEL
- (KNEE WALL AT BOOTH SEATING BY OTHERS)

SHEET A112

ENLARGED PLAN C1/A401, ELEVATION B5/A407 (LACTATION W1522):

- PL•1 BASE CABINETS WITH MELAMINE INTERIORS
- PL•1 OPEN CABINETS WITH PL•1 INTERIORS
- SSM3 QUARTZ COUNTERTOP
- (TILE SPLASH BY OTHERS)

SHEET A112

ENLARGED PLAN C1/A401, ELEVATION C1/A405 & D1/A405 (STAFF RESTROOM W1520 & W1521):

- SSM3 QUARTZ COUNTERTOP
- SSM3 TOP TURN DOWN
- (TILE SPLASH BY OTHERS)
- 2X3 STEEL TUBE SUPPORT MOUNTED UNDER TOP ALONG LEADING EDGE, BOLTED TO END WALLS THROUGH FLANGE
- (IN•WALL BLOCKING BY OTHERS, COORDINATE WITH EURO•TEX FOR BLOCK LOCATION)

SHEET A112

ELEVATION D1/A408, D2/A408 & D3/A408 (CASH COUNT W1514):

- PL•1 UPPER AND LOWER CABINETS
- PL•1 TALL STORAGE CABINETS
- SSM1 SOLID SURFACE COUNTERTOPS)

SHEET A112

ENLARGED PLAN B2/A402, ELEVATION B1/A408, B2/A408 & B3/A408 (DEALER ADMIN W1510 & DEALER LOBBY W1102):

- PL•1 UPPER AND LOWER CABINETS
- PL•1 TALL STORAGE CABINETS
- SSM1 SOLID SURFACE COUNTERTOPS

SHEET A112

ELEVATION A1/A407, A2/A407 & A3/A407 (MAIL W1803):

- PL•1 LOWER CABINETS
- SSM1 SOLID SURFACE COUNTERTOPS

<p>SHEET A113 ELEVATION C5/A407 (RESEARCH LIBRARY E1301):</p> <ul style="list-style-type: none"> • PL•1 LOWER CABINETS • SSM1 SOLID SURFACE COUNTERTOPS
<p>SHEET A113 ELEVATION A5/A407 (PLATS WORK E1203):</p> <ul style="list-style-type: none"> • PL•1 UPPER & LOWER CABINETS WITH WHITE MELAMINE INTERIORS • SSM1 SOLID SURFACE COUNTERTOPS
<p>SHEET A113 ELEVATION C1/A406, C2/A406 & C3/A406 (VAULT E1232):</p> <ul style="list-style-type: none"> • PL•1 UPPER & LOWER CABINETS WITH WHITE MELAMINE INTERIORS • SSM1 SOLID SURFACE COUNTERTOPS
<p>SHEET A113 ENLARGED PLAN A5/A402, ELEVATION A1/A405 (COFFEE E1227):</p> <ul style="list-style-type: none"> • PL•3 UPPER AND LOWER CABINETS • SSM3 QUARTZ COUNTERTOPS
<p>SHEET A113 ENLARGED PLAN D1/A401, ELEVATION C1/A405 & D1/A405 (STAFF RESTROOM E1228 & E1229):</p> <ul style="list-style-type: none"> • SSM3 QUARTZ COUNTERTOP • SSM3 TOP TURN DOWN • (TILE SPLASH BY OTHERS) • 2X3 STEEL TUBE SUPPORT MOUNTED UNDER TOP ALONG LEADING EDGE, BOLTED TO END WALLS THROUGH FLANGE • (IN•WALL BLOCKING BY OTHERS, COORDINATE WITH EURO•TEX FOR BLOCK LOCATION)
<p>SHEET A113 ENLARGED PLAN D3/A402, ELEVATION A2/A409, B4/A409 & C4/A409 (MEN'S RR E1105, FAMILY RR E1006, WOMEN'S RR E1107):</p> <ul style="list-style-type: none"> • SSM3 QUARTZ COUNTERTOP • SSM3 TOP TURN DOWN • (TILE SPLASH BY OTHERS) • A&M 2.0 CONCEALED IN•WALL SUPPORT BRACKETS • 2X3 STEEL TUBE SUPPORT MOUNTED UNDER TOP ALONG LEADING EDGE, BOLTED TO END WALLS THROUGH FLANGE • (IN•WALL BLOCKING BY OTHERS, COORDINATE WITH EURO•TEX FOR BLOCK LOCATION)
<p>SHEET A114 ENLARGED PLAN A4/A402, ELEVATION B2/A406 & B4/A406 (WORKROOM E1221):</p> <ul style="list-style-type: none"> • PL•1 UPPER & LOWER CABINETS WITH WHITE MELAMINE INTERIORS • SSM1 SOLID SURFACE COUNTERTOPS
<p>SHEET A114 ELEVATION D1/A406 (VITAL WORK ROOM E1207):</p> <ul style="list-style-type: none"> • PL•1 UPPER & LOWER CABINETS WITH WHITE MELAMINE INTERIORS • SSM1 SOLID SURFACE COUNTERTOPS
<p>SHEET A114 ENLARGED PLAN B1/A424, ELEVATION A2/A424 & A3/A424, DETAIL D1/A424, D2/A424, D3/A424 (RECEPTION DESK):</p> <ul style="list-style-type: none"> • SHOP•FABRICATED RADII KNEE WALL WITH BLACK 1595•60 PLASTIC LAMINATED INTERIORS WITH REMOVABLE INTERIOR PANELS • A&M CONCEALED COUNTERTOP SUPPORT • SSM5 SOLID SURFACE THERMOFORMED CLADDING ON DESK EXTERIOR • SSM5 LOWER TOP, BACKSPLASH, AND TRANSACTION COUNTERTOP • TRB1 BASEBOARD BY OTHERS • STAINLESS STEEL LAMINATED INTERIOR BASE BY EUROTEx
<p>SHEET A114 ENLARGED PLAN D1/A618, ELEVATION D1/A620, D3/A620, D1/A621, D3/A621, D2/A622, DETAILS C/A424 (UNDER STAIRS BENCH):</p> <ul style="list-style-type: none"> • SHOP-FABRICATED PLYWOOD FRAMEWORK FOR UNDER THE STAIRS BENCH, BENCH CLAD IN SSM5 SOLID SURFACE
<p>SHEET A114 ENLARGED PLAN D1/A618, ELEVATION D1/A620, D3/A620, D1/A621, D3/A621, D2/A622, DETAILS C/A424 (AWP2 & AWP2A PANELS AT STAIR EXTERIOR):</p> <ul style="list-style-type: none"> • TERRAMAI WOOD WALL SLATS SCREWED DIRECTLY TO HAT TRACK AND BREAK METAL • SSM5 SOLID SURFACE RAILING CAP • (ALL BLOCKING, BREAK METAL, HAT TRACK, AND FRY REGLET SUPPLIED AND INSTALLED BY OTHERS)
<p>SHEET A114 ELEVATION B2/A407 (CCR LOBBY E1201):</p> <ul style="list-style-type: none"> • WP6: 4' X 8' FORBO BULLETIN BOARDS IN FRAMES. QTY: 4
<p>SHEET A113 & A114 ENLARGED PLAN B1/A402, ELEVATION B1/A604 & D2/A406, D3/A406, D4/A406, D5/A406 (CCR LOBBY COUNTERS E1501):</p> <ul style="list-style-type: none"> • A&M 2.0 CONCEALED IN•WALL SUPPORT BRACKETS • PL•1 BASE CABINETS WITH MELAMINE INTERIORS • SSM1 SOLID SURFACE COUNTERTOP • WP-1 3FORM FRAMED DIVIDER PANELS • (WC2 WALL COVERING BY OTHERS , KNEE WALLS BY OTHERS , CLEAR ACRYLIC SCREEN BY OTHERS)
<p>SHEET A122, A123, A124 DETAIL D1/A623 (AWP2 & AWP2A AT BALCONY RAILING):</p> <ul style="list-style-type: none"> • TERRAMAI WOOD WALL SLATS SCREWED DIRECTLY TO HAT TRACK AND BREAK METAL • SSM5 SOLID SURFACE RAILING CAP • (ALL BLOCKING, BREAK METAL, HAT TRACK, AND FRY REGLET SUPPLIED AND INSTALLED BY OTHERS)

SHEET A122**ENLARGED PLAN B3/A403, ELEVATION B1/A410 & B2/A410 (COFFEE W2405):**

- PL•3 BASE CABINETS WITH MELAMINE INTERIORS
- PL•3 FLOATING SHELVES
- PL•3 WHITE UPPER CABINETS WITH WHITE MELAMINE INTERIORS
- SSM2 QUARTZ COUNTERTOP
- SHOP-FABRICATED BLACK P-LAM BOOTH FRAMES WITH UPH3 UPHOLSTERED SEAT BACKS, UPH2 UPHOLSTERED SEAT BOTTOMS
- SSM1 WALL CAP
- MP1 LASER•CUT METAL PANEL
- (KNEE WALL AT BOOTH SEATING BY OTHERS)

SHEET A122**ENLARGED PLAN B3/A403, ELEVATION D5/A410 (COPY W2410):**

- PL•1 BASE CABINETS WITH MELAMINE INTERIORS
- PL•1 OPEN LAMINATED BASE CABINETS WITH LAMINATED INTERIORS
- SSM2 QUARTZ COUNTERTOP
- WP6: 4' X 8' FORBO BULLETIN BOARDS IN FRAMES

SHEET A122**ENLARGED PLAN D3/A403, ELEVATION B5/A407 (LACTATION W2414):**

- PL•1 BASE CABINETS WITH MELAMINE INTERIORS
- PL•1 OPEN CABINETS WITH PL•1 INTERIORS
- SSM3 QUARTZ COUNTERTOP
- (TILE SPLASH BY OTHERS)

SHEET A122**ENLARGED PLAN D3/A403, ELEVATION C1/A407 & D1/A407 (STAFF RESTROOM W2412 & W2413):**

- SSM3 QUARTZ COUNTERTOP
- SSM3 TOP TURN DOWN
- (TILE SPLASH BY OTHERS)
- 2X3 STEEL TUBE SUPPORT MOUNTED UNDER TOP ALONG LEADING EDGE, BOLTED TO END WALLS THROUGH FLANGE
- (IN-WALL BLOCKING BY OTHERS , COORDINATE WITH EURO-TEX FOR BLOCK LOCATION)

SHEET A123**ENLARGED PLAN D1/A403, ELEVATION A1/A410, A2/A410, A2/A409, D1/A409 & D3/A409 (MEN'S RR E2102, FAMILY RR E2103, WOMEN'S RR C2104):**

- SSM3 QUARTZ COUNTERTOP
- SSM3 TOP TURN DOWN
- (TILE SPLASH BY OTHERS)
- A&M 2.0 CONCEALED IN•WALL SUPPORT BRACKETS
- 2X3 STEEL TUBE SUPPORT MOUNTED UNDER TOP ALONG LEADING EDGE, BOLTED TO END WALLS THROUGH FLANGE
- (IN-WALL BLOCKING BY OTHERS , COORDINATE WITH EURO-TEX FOR BLOCK LOCATION)

SHEET A123**ELEVATION A3/A411 (STAFF/MEDIA E2202):**

- PL•2 LOWER CABINETS WITH WHITE MELAMINE INTERIORS
- SSM2 QUARTZ COUNTERTOP

SHEET A123**ENLARGED PLAN B1/A403, ELEVATION A4/A410, B4/A410, C1/A410, C3/A410, C4/A410 & D4/A410 (WILCO CAFÉ E2302):**

- PL•2 BASE CABINETS WITH MELAMINE INTERIORS
- PL•2 MICROWAVE STORAGE CABINETS WITH WHITE MELAMINE INTERIORS
- SSM4 QUARTZ COUNTERTOP
- (WT6 WALL COVERING AT ISLAND BY OTHERS)
- SHOP-FABRICATED BLACK P-LAM BOOTH FRAMES WITH UPH1 UPHOLSTERED SEAT BACKS, UPH1 UPHOLSTERED SEAT BOTTOMS
- ***FYI, "WELTING" WILL ONLY BE ON THE ENDS AT THE UPH1 SEAT BACKS AND NOT IN EACH CHANNEL. WE HAVE DONE IT BEFORE IN THE CHANNEL AND DID NOT GET A GOOD RESULT.***

SHEET A123**ELEVATION A1/A412 & A2/A412 (EXECUTIVE SESSION E2309):**

- CR1 CHAIR RAIL
- TWC MOLDING **PROFILE TBD**
- COLOR TO BE STAINED TO MATCH WD1

SHEET A123**ENLARGED PLAN D4/A403, ELEVATION A4/A412 & A5/A412 (COFFEE E2310, COPY E2313):**

- PL•1 BASE CABINETS WITH MELAMINE INTERIORS
- PL•1 OPEN LAMINATED BASE CABINETS WITH LAMINATED INTERIORS
- SSM2 QUARTZ COUNTERTOP
- (TILE SPLASH BY OTHERS)

SHEET A123**ELEVATION A4/A411 (DAIS BREAK E32205):**

- PL•2 LOWER CABINETS WITH WHITE MELAMINE INTERIORS
- SSM2 QUARTZ COUNTERTOP

SHEET A123**ELEVATION A1/A411 (CORRIDOR E2308 & E23B):**

- HR•1 HANDRAIL AT WALL CAPS
- (KNEE WALLS BY OTHERS)
- PL-1 TALL STORAGE WARDROBE CABINETS WITH WHITE MELAMINE INTERIORS

<p>SHEET A123 ENLARGED PLAN C1/A425, ELEVATION C1/A411, B2/A425, C2/A425 & CE/A425 (COMMISSIONERS COURT DAIS AREA):</p> <ul style="list-style-type: none"> • SHOP-FABRICATED DAIS WALL WITH CONCEALED IN-WALL SUPPORTS AND REMOVABLE BLACK LAMINATED INTERIORS • ½" BALLISTIC FIBERGLASS AND WD•1 WOOD VENEER EXTERIOR • SSM5 COUNTER AND SSM5 WALL CAPS • WB•1 BASEBOARD • 1 ¼" CLEAR BALLISTIC GLAZING LEVEL 3 BY OTHERS • ROUND BUTTON GLAZING PANEL STABILIZERS BY OTHERS
<p>SHEET A123 ELEVATION C1/A411, D1/A313, B3/A414 & SHEET A923: SEE AWP1 CALLOUTS (AWP1 TERRAMAI ACOUSTICAL PANELS):</p> <ul style="list-style-type: none"> • DIRECTLY SCREWED TO WALL • ACOUSTICAL WALL PANELS WITH PRE•FINISHED OILED FINISH FROM THE FACTORY
<p>SHEET A124 ENLARGED PLAN A1/A425, ELEVATION C1/A411, A2/A425 & A3/A425 (PRESENTER TABLE):</p> <ul style="list-style-type: none"> • SHOP-FABRICATED FURNITURE • CLAD IN WD-1 WOOD VENEER EXTERIOR • SURFACE MOUNTED WORKSURFACE SUPPORTS • SSM5 LOWER COUNTER AND SSM5 WALL CAPS • LOCKING CASTERS
<p>SHEET A124 ELEVATION D2/A410, DETAIL D4/A422 (TROPHY DISPLAY):</p> <ul style="list-style-type: none"> • PLASTIC LAMINATED DISPLAY STEPS, COLOR TBD • PLASTIC LAMINATED FLOATING SHELF, COLOR TBD • (SLIDING GLASS DOORS BY OTHERS)
<p>SHEET A124 ELEVATION B3/A406 (CLERK ENTRANCE ELEVATION):</p> <ul style="list-style-type: none"> • SSM5 WALL CAP • FRY REGLET SUPPLIED AND INSTALLED BY OTHERS
<p>SHEET A131 ELEVATION B1/A412 (JUDGE OPEN OFFICE AREA ,CJ FEATURE WALL)</p> <ul style="list-style-type: none"> • PLYWOOD GRID ATTACHED WITH PIN NAILS AND ADHESIVE TO SHEETROCK WALL • (PLYWOOD PAINTED AND CAULKED BY OTHERS)
<p>SHEET A132 ENLARGED PLAN B3/A403, ELEVATION B1/A410 & B2/A410 (COFFEE W3405):</p> <ul style="list-style-type: none"> • PL-3 BASE CABINETS WITH MELAMINE INTERIORS • PL-3 FLOATING SHELVES • PL-3 UPPER CABINETS WITH WHITE MELAMINE INTERIORS • SSM2 QUARTZ COUNTERTOP • SHOP-FABRICATED BLACK P-LAM BOOTH FRAMES WITH UPH3 UPHOLSTERED SEAT BACKS, UPH2 UPHOLSTERED SEAT BOTTOMS • SSM1 WALL CAP • MP1 LASER-CUT METAL PANEL • (KNEE WALL AT BOOTH SEATING BY OTHERS)
<p>SHEET A132 ENLARGED PLAN B3/A403, ELEVATION D5/A410 (COPY W3410):</p> <ul style="list-style-type: none"> • PL-1 BASE CABINETS WITH MELAMINE INTERIORS • PL-1 OPEN LAMINATED BASE CABINETS WITH LAMINATED INTERIORS • SSM2 QUARTZ COUNTERTOP • WP6: 4' X 8' FORBO BULLETIN BOARDS IN FRAMES
<p>SHEET A132 ENLARGED PLAN D3/A403, ELEVATION B5/A407 (LACTATION W3414):</p> <ul style="list-style-type: none"> • PL-1 BASE CABINETS WITH MELAMINE INTERIORS • PL-1 OPEN CABINETS WITH PL-1 INTERIORS • SSM3 QUARTZ COUNTERTOP • (TILE SPLASH BY OTHERS)
<p>SHEET A132 ENLARGED PLAN D3/A403, ELEVATION C1/A407 & D1/A407 (STAFF RESTROOM W3412 & W3413):</p> <ul style="list-style-type: none"> • SSM3 QUARTZ COUNTERTOP • SSM3 TOP TURN DOWN • (TILE SPLASH BY OTHERS) • 2X3 STEEL TUBE SUPPORT MOUNTED UNDER TOP ALONG LEADING EDGE, BOLTED TO END WALLS THROUGH FLANGE • (IN-WALL BLOCKING BY OTHERS , COORDINATE WITH EURO•TEX FOR BLOCK LOCATION)
<p>SHEET A132 ELEVATION D1/A412 (LOBBY E3101):</p> <ul style="list-style-type: none"> • SHOP-FABRICATED BLACK P-LAM BOOTH FRAMES WITH UPH6 UPHOLSTERED SEAT BACKS, UPH7 UPHOLSTERED SEAT BOTTOMS • AWP4 ACOUSTICAL WALL PANEL, TURF DESIGN, PEAK WALL PANELS, 10 TOPO GREEN
<p>SHEET A133 ELEVATION B2/A413 (COFFEE E3107):</p> <ul style="list-style-type: none"> • PL•2 LOWER CABINETS WITH WHITE MELAMINE INTERIORS • PL•2 UPPER CABINETS WITH WHITE MELAMINE INTERIORS • SSM2 QUARTZ COUNTERTOP

<p>SHEET A133 ENLARGED PLAN D1/A404, ELEVATION B1/A413 & A2/A413 (RESTROOM E3104 & E3103):</p> <ul style="list-style-type: none"> • SSM3 QUARTZ COUNTERTOP • SSM3 TOP TURN DOWN • (TILE SPLASH BY OTHERS) • 2X3 STEEL TUBE SUPPORT MOUNTED UNDER TOP ALONG LEADING EDGE, BOLTED TO END WALLS THROUGH FLANGE • (IN•WALL BLOCKING BY OTHERS , COORDINATE WITH EURO•TEX FOR BLOCK LOCATION)
<p>SHEET A134 ENLARGED PLAN D2/A404, ELEVATION B3/A413 (RESTROOM E3118):</p> <ul style="list-style-type: none"> • SSM3 QUARTZ COUNTERTOP • SSM3 TOP TURN DOWN • A&M 2.0 CONCEALED IN•WALL SUPPORT
<p>SHEET A134 ELEVATION B2/A412 & B3/A412 (SAN GABRIEL CONF E3116):</p> <ul style="list-style-type: none"> • CR1 CHAIR RAIL • TWC MOLDING PROFILE TBD • COLOR TO BE STAINED TO MATCH WD1
<p>SHEETS A923,A924,A931,A934 WB1 WOOD BASE BOARD MATCH WD1 PANELS</p> <ul style="list-style-type: none"> • BASE LOCATIONS: COMMISSIONER'S COURT DAIS AREA E2204, COMMISSIONERS COURT E2201, SAN GABRIEL CONF E3116, COUNTY JUDGE OFFICE E3117, COUNTY JUDGE OFFICE E311
<p>SHEET A524 DETAIL C3/A553, D3/A553 & D4/A553 (WDC1 COMMISSIONERS COURT ONLY) PRE•FINISHED OILED WOOD CEILINGS:</p> <ul style="list-style-type: none"> • TERRAMAI, ACOUSTIC PANELS LINER SLATS DIRECTLY SCREWED TO ARMSTRONG DROP CEILING GRID • (CEILING GRID SUPPLIED AND INSTALLED BY OTHERS)

CONSTRUCTION SPECIFICATIONS		
ITEM	DESCRIPTION	ADDITIONAL NOTES
CABINET PANEL CORE MATERIAL	MDF	NO PARTICLE BOARD ALLOWED
DOOR /DWR PANEL CORE	MDF	NO PARTICLE BOARD ALLOWED
CABINET INTERIORS	WHITE MELAMINE	
OPEN CABINET INTERIORS	DECORATIVE HPL	
EXTERIOR UPPER CAB BOTTOMS	WHITE MELAMINE	
CABINET BODY EDGE-BANDING	0.5 MM PVC MATCHING CASEGOOD EXTERIORS	
DOOR /DWR FRONT EDGE-BANDING	0.5 MM PVC MATCHING CASEGOOD EXTERIORS	
TOE KICK	P-LAM	
HARDWARE	DESCRIPTION	ADDITIONAL NOTES
CABINETS PULLS	96 MM CTC	U SHAPED WIRE PULL CHROME FINISH
HINGES	BLUM 110" + FULL OVERLAY CONCEALED HINGE, SELF CLOSING	
GROMMETS	2" DIA, BLACK ABS WITH CAP	
DRAWER SLIDES	100LB BALL BEARING	
SHELF CLIPS	5MM SPOON PIN	
LOCKS	CABINET CAM LOCKS KEYED ALIKE	
PULL OUT SHELF	225 LB HEAVY DUTY FULL EXTENSION BALL BEARING GUIDES	
TRASH PULL OUT	EURO-TEX STANDARD PULLOUT	
WALL SUPPORTS 1	A&M HARDWARE	CONCEALED AND EXTENDED CONCEALED
SLIDING CABINET DOOR HARDWARE	#2 ALUMINUM SLIDING DOOR TRACK KIT FOR 3/4" BY-PASSING WOOD DOORS SATIN CLEAR ANODIZED 5" EPCO 2-A-5	https://www.woodworkerexpress.com/-2-aluminum-sliding-door-track-kit-for-3-4-by-passing-wood-doors-satin-clear-anodized-5-epco-2-a-5.html?utm_source=google&utm_medium=product_search&utm_campaign=google_product_ads&source=googlebase&country=US&gad_source=1&gclid=CjwKCAjwhIS0Bh8qEiwADAUh5KkjmVx12HHmOR9K8WNFFf73vMX-gb9fJUyRRJIEalruYYXLchoCZagQAvD_BwE
FINISH LEGEND	PRODUCT REFERENCE /COLOR	ADDITIONAL NOTES
PL-1:	WILSONART: SMOKY VELVET ELM 15604-31	TRACELESS
PL-2:	WILSONART: WALNUT HEIGHTS; 7965	BREAKROOMS
PL-3:	WILSONART: NEW AGE OAK 7938-38	COFFEE BARS
WOOD	PRODUCT REFERENCE /COLOR	ADDITIONAL NOTES
WD1	BVC - BEST VENEER COMPANY : EURO OAK FUMED QTD	CLEAR FINISH , VERTICAL GRAIN
WDC1	TERRAMAI, ACOUSTIC PANELS; LINEAR SLAT,ORCHARD WALNUT	FINISH: ZERO-VOC CLEAR OIL OR LOW-VOC POLYURETHANE - TREATED WITH CLASS A FIRE RETARDANT ON BEST FACES. **NOTES: MATERIAL TREATED WITH A FIRE RETARDANT AND AN OIL TOP COAT MAY SHOW SIGNS OF DISCOLORATION AND CLOUDINESS, WHICH ARE GREATLY ACCENTUATED IF THE MATERIAL IS SUBJECTED TO MOISTURE.**
AWP1	DISCONTINUED: TERRAMAI, ACOUSTIC PANELS; SQUARE SLAT ,ORCHARD WALNUT DAVID ANDREWS WITH TERRAMAI DISCUSSED MATERIAL WITH ARCHTEC THE SQUARE SLAT IS NO LONGER AVALIBEL THIS PRICING IS FOR TerraMai Modular Panel - Mini Slat - Orchard Walnut - Oil - FR	FINISH: ZERO-VOC CLEAR OIL OR LOW-VOC POLYURETHANE - TREATED WITH CLASS A FIRE RETARDANT ON BEST FACES. **NOTES: MATERIAL TREATED WITH A FIRE RETARDANT AND AN OIL TOP COAT MAY SHOW SIGNS OF DISCOLORATION AND CLOUDINESS, WHICH ARE GREATLY ACCENTUATED IF THE MATERIAL IS SUBJECTED TO MOISTURE.**
AWP2 (FLEX PANELS)	DISCONTINUED: TERRAMAI, ACOUSTIC PANELS; FLEXPANEL SQUARE SLAT ,ORCHARD WALNUT DAVID ANDREWS WITH TERRAMAI DISCUSSED MATERIAL WITH ARCHTEC THE SQUARE SLAT IS NO LONGER AVALIBEL THIS PRICING IS FOR TerraMai Flex Panel - Linear Slat - Orchard Walnut - Oil - FR	FINISH: ZERO-VOC CLEAR OIL OR LOW-VOC POLYURETHANE - TREATED WITH CLASS A FIRE RETARDANT ON BEST FACES. **NOTES: MATERIAL TREATED WITH A FIRE RETARDANT AND AN OIL TOP COAT MAY SHOW SIGNS OF DISCOLORATION AND CLOUDINESS, WHICH ARE GREATLY ACCENTUATED IF THE MATERIAL IS SUBJECTED TO MOISTURE.**
AWP2A	DISCONTINUED : TERRAMAI, ACOUSTIC PANELS; MODULAR SQUARE SLAT ,ORCHARD WALNUT DAVID ANDREWS WITH TERRAMAI DISCUSSED MATERIAL WITH ARCHTEC THE SQUARE SLAT IS NO LONGER AVALIBEL THIS PRICING IS FOR TerraMai Modular Panel - Mini Slat - Orchard Walnut - Oil - FR	FINISH: ZERO-VOC CLEAR OIL OR LOW-VOC POLYURETHANE - TREATED WITH CLASS A FIRE RETARDANT ON BEST FACES. **NOTES: MATERIAL TREATED WITH A FIRE RETARDANT AND AN OIL TOP COAT MAY SHOW SIGNS OF DISCOLORATION AND CLOUDINESS, WHICH ARE GREATLY ACCENTUATED IF THE MATERIAL IS SUBJECTED TO MOISTURE.**
CR1	CHAIR RAIL : TWC MOLDING # TBD	WOOD BASE : TWC MOLDING #B752
HR1	HAND RAIL : TWC MOLDING # HR071	STAIN TO MATCH WD1
WB1	WOOD BASE : TWC MOLDING #B752	STAIN TO MATCH WD1
SOLID SURFACE	PRODUCT REFERENCE /COLOR	ADDITIONAL NOTES
SSM1	WILSONART : 9209 MOON GEYSERT	CLERK/TAX COUNTERS
SSM5	CORIAN : CARRARA CREMA	RECEPTION DESK / BENCH
SS-3:	LG Hi-Macs (Group A-B)	
SS-4:	LG Hi-Macs (Group A-B)	
SS-5:	LG Hi-Macs (Group A-B)	

STONE	PRODUCT REFERENCE /COLOR	ADDITIONAL NOTES
SSM2	WILSONART QUARTZ : FROZEN Q6023	COFFEE BAR
SSM3	WILSONART QUARTZ : TERLINGUA Q6024	RESTROOMS
SSM4	WILSONART QUARTZ : CALACATTA AQUILEA	BREAKROOM
WALL PANELS	PRODUCT REFERENCE /COLOR	ADDITIONAL NOTES
AWP3	ACOUSTICAL SOLUTIONS : SONEX TEC WEDGE ACOUSTIC FOAM; 2' X 4' X 3" THICK	BLACK , LOCATION :PAIO STUDIO
AWP4	TURF DESIGN, PEAK WALL PANELS	10 TOPO GREEN , LOCATION : 3RD FLOOR LANDING
MP1	METAL PANEL : MOZ METAL LASER CUT ALUMINUM DECO PATTERS:	WHITE SAND POWDER COAT . LOCATIONS : COFFEE BARS
WP1	3FORM : 200.52 FULLY FRAMED TOP SUPPORT PARTITION;2'-10" X 8'H., VARIA; 3/8", OZNER+CLEAR	THE OVERALL HEIGHT OF THE SYSTEM IS SLIGHTLY SMALLER THAN WHAT WAS SPECIFIED. WE'VE QUOTED OUR MAXIMUM SYSTEM HEIGHT USING A 96" STANDARD SHEET SIZE.
WP6	FORBO : BULLETIN BOARD PINBOARD LINOLEUM; FRAMED SOLUTION; 4' X 8'	2204 POPPY SEED
UPHOLSTERY	DESCRIPTION	ADDITIONAL NOTES
UPH1	ARC-COM : TAILORED AC-64098, MALLARD #9	LEVEL 2 AREA C SEAT BACKS, 2" VERTICAL CHANNELS (THIS LOCATION IS THE ONLY ONE WITH SEAT BACK 2" CHANNELING). ***WELTING* WILL ONLY BE ON THE ENDS...NOT EACH CHANNEL. WE HAVE TRIED THIS BEFORE AND DID NOT ACHIEVE A GOOD RESULT.**
UPH2	ARC-COM : DYNASTY, AC-60511,EMERALD #12	SEAT BOTTOMS
UPH3	MOMENTUM: PARACHUTE, BALI	SEAT BACKS
UPH6	MOMENTUM: PARACHUTE, BALI	SEAT BACKS
UPH7	ANZEA : 7219-01, JACK ELOPE	SEAT BOTTOMS
ADDITIONAL NOTES	DESCRIPTION	ADDITIONAL NOTES
SHOP DRAWINGS	Shop Drawings: Indicate materials, component profiles, fastening methods, jointing details, and accessories. 1. Scale of Drawings: 1-1/2 inch to 1 foot (125 mm to 1 m), minimum. 2. Complete details of materials and installation; combine with shop drawings of cabinets and casework and countertop materials specified herein or in other sections.	
CABINET MOCK UP REQUIRED	A) Provide mock-up of typical base cabinet, wall cabinet, and countertop , including hardware and finishes	Mock-up may remain as part of the work.

WILSONART: SMOKY VELVET ELM 15604-31			
PLASTIC LAMINATED CABINETS, WHITE MELAMINE CABINET INTERIORS			
BASE 2 DOOR	121.7	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER BASE CABINETS WITH WHITE MELAMINE INTERIORS.
OPEN BASE LAMINATED INTERIORS	55.9	<i>Ln.Ft.</i>	OPEN LOWER CABINET, PLASTIC LAMINATED INTERIOR
DRAWER BASE 2 DRAWER	46.2	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES AND FULL EXTENSION DRAWER GUIDES
DRAWER BASE 3 DRAWER	44.9	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES AND FULL EXTENSION DRAWER GUIDES
DRAWER BASE 4 DRAWER	21.7	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES AND FULL EXTENSION DRAWER GUIDES
ADA SINK BASE SLOPED PANEL	11.7	<i>Ln.Ft.</i>	PLASTIC LAMINATED ADA SINK CABINET WITH SLOPE PANEL AND PLYWOOD INTERIORS
TALL OPEN STORAGE PLAM INTERIOR	6.0	<i>Ln.Ft.</i>	OPEN STORAGE CABINET PLASTIC LAMINATE INTERIORS
LEG SUPPORT MILLWORK	8.0	<i>Ln.Ft.</i>	PLASTIC LAMINATED LEG SUPPORT
BASE CABINETS WITH BI-PASS SLIDING DOORS	51.0	<i>Ln.Ft.</i>	SHOP FABRICATED METAL IN-WALL SUPPORTS , PRIMED FOR PAINT
FINISHED END BASE CABINETS	127.0	<i>Ln.Ft.</i>	BASE CABINET FINISHED END PANEL
TALL CABINETS FINISHED END	8.0	<i>Ln.Ft.</i>	TALL CABINET FINISHED END PANEL
OPEN UPPERS LAMINATED INTERIORS 30"-36"	7.6	<i>Ln.Ft.</i>	OPEN UPPER CABINET ,PLASTIC LAMINATED INTERIORS
UPPER CABINETS 2 DOOR 30"-36" TALL	88.6	<i>Ln.Ft.</i>	PLASTIC LAMINATED UPPER CABINETS WITH WHITE MELAMINE INTERIORS
FLOATING SHELF, HIDDEN WALL SUPPORT	23.7	<i>Ln.Ft.</i>	FLOATING PLASTIC LAMINATED SHELF, HIDDEN WALL SUPPORTS
UPPER CABINET FINISHED END	5.0	<i>Ln.Ft.</i>	UPPER CABINET FINISHED END
TALL 2 DOOR WARDROBE	15.0	<i>Ln.Ft.</i>	EXTRA 8
LAMINATED TOE BASE	421.8	<i>Ln.Ft.</i>	PLASTIC LAMINATED TOE BASE
TROPHY CASE DISPLAY SHELVES/STEPS	24.1	<i>Ln.Ft.</i>	TROPHY CASE DISPLAY SHELVES/STEPS

WILSONART: WALNUT HEIGHTS; 7965			
PLASTIC LAMINATED CABINETS, WHITE MELAMINE CABINET INTERIORS			
BASE 1 DOOR	1.9	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER BASE CABINETS WITH WHITE MELAMINE INTERIORS.
BASE 2 DOOR	22.7	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER BASE CABINETS WITH WHITE MELAMINE INTERIORS.
BASE 2 DOORS 2 DRAWERS	18.4	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES AND FULL EXTENSION DRAWER GUIDES
DRAWER BASE 2 DRAWER	46.2	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES AND FULL EXTENSION DRAWER GUIDES
DRAWER BASE 4 DRAWER	6.9	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES AND FULL EXTENSION DRAWER GUIDES
DRAWER BASE MICROWAVE OPENING	7.6	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES, PLASTIC LAMINATED MICROWAVE OPENING
ADA SINK BASE SLOPED PANEL	12.0	<i>Ln.Ft.</i>	PLASTIC LAMINATED ADA SINK CABINET WITH SLOPE PANEL AND PLYWOOD INTERIORS
LEG SUPPORT MILLWORK	1.0	<i>QTY</i>	PLASTIC LAMINATED LEG SUPPORT
TALL LEG SUPPORT MILLWORK	1.0	<i>QTY</i>	TALL PLASTIC LAMINATED LEG SUPPORT
TALL 2 DOOR MICROWAVE STORAGE	7.5	<i>LN FT</i>	PLASTIC LAMINATED STORAGE CABINET WITH WHITE MELAMINE INTERIORS
FINISHED END BASE CABINETS	12.0	<i>QTY</i>	BASE CABINET FINISHED END PANEL
TALL CABINETS FINISHED END	2.0	<i>QTY</i>	TALL CABINET FINISHED END PANEL
UPPER CABINETS 2 DOOR 30"-36" TALL	4.9	<i>Ln.Ft.</i>	PLASTIC LAMINATED UPPER CABINETS WITH WHITE MELAMINE INTERIORS
UPPER CABINET FINISHED END	2.0	<i>QTY</i>	UPPER CABINET FINISHED END
LAMINATED TO BASE	73.3	<i>LN FT</i>	PLASTIC LAMINATED TOE BASE
WILSONART: NEW AGE OAK 7938-38			
PLASTIC LAMINATED CABINETS, WHITE MELAMINE CABINET INTERIORS			
BASE 1 DOOR	1.8	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER BASE CABINETS WITH WHITE MELAMINE INTERIORS.
BASE 2 DOOR	15.3	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER BASE CABINETS WITH WHITE MELAMINE INTERIORS.
DRAWER BASE 4 DRAWER	3.0	<i>Ln.Ft.</i>	PLASTIC LAMINATED LOWER CABINETS WITH 5/8" MELAMINE DRAWER BOXES AND FULL EXTENSION DRAWER GUIDES
ADA SINK BASE SLOPED PANEL	12.2	<i>Ln.Ft.</i>	PLASTIC LAMINATED ADA SINK CABINET WITH SLOPE PANEL AND PLYWOOD INTERIORS
LEG SUPPORT MILLWORK	4.0	<i>QTY</i>	PLASTIC LAMINATED LEG SUPPORT
FINISHED END BASE CABINETS	14.0	<i>QTY</i>	BASE CABINET FINISHED END PANEL
UPPER CABINETS 1 DOOR 30"-36" TALL	1.5	<i>Ln.Ft.</i>	PLASTIC LAMINATED UPPER CABINETS WITH WHITE MELAMINE INTERIORS
UPPER CABINETS 2 DOOR 30"-36" TALL	9.2	<i>Ln.Ft.</i>	PLASTIC LAMINATED UPPER CABINETS WITH WHITE MELAMINE INTERIORS
FLOATING SHELF, HIDDEN WALL SUPPORT	53.3	<i>Ln.Ft.</i>	FLOATING PLASTIC LAMINATED SHELF, HIDDEN WALL SUPPORTS
UPPER CABINET FINISHED END	7.0	<i>QTY</i>	UPPER CABINET FINISHED END
LAMINATED TOE BASE	43.8	<i>LN FT</i>	PLASTIC LAMINATED TOE BASE
WILSONART : 9209 MOON GEYSERT			
SOLID SURFACE 1			
SOLID SURFACE (TAX LOBBY DESK, CCR LOBBY DESK)	1219.2	<i>SQ. FT</i>	SOLID SURFACE (TAX LOBBY DESK, CCR LOBBY DESK)
SOLID SURFACE , 4" SPLASH	452.5	<i>SQ. FT</i>	SOLID SURFACE COUNTERTOP , 1-1/2" MITER EDGE, 4" BACK SPLASH AS REQUIRED
SOLID SURFACE WALL CAPS (TAX LOBBY DESK, CCR LOBBY DESK)	81.5	<i>SQ. FT</i>	SOLID SURFACE WALL CAPS (TAX LOBBY DESK, CCR LOBBY DESK)
SEAM KITS	43.8	<i>QTY</i>	SEAMING KITS
SHIPPING COST	1.0	<i>QTY.</i>	SHIPPING COST

CORIAN : CARRARA CREMA			
SOLID SURFACE 2			
SOLID SURFACE	419.4	<i>SQ. FT</i>	SOLID SURFACE COUNTERTOP , 1-1/2" MITER EDGE , SCRIBE AT WALLS
BALCONY WALL CAPS	146.8	<i>SQ. FT</i>	SOLID SURFACE WALL CAPS
THERMOFORMED AROUND RECEPTION DESK	177.6	<i>SQ. FT</i>	THERMOFORMED AROUND RECEPTION DESK
SEAM KITS	18.6	<i>QTY</i>	SEAMING KITS
SHIPPING COST	1.0	<i>QTY</i>	SHIPPING COST
LG Hi-Macs (Group A-B)			
SOLID SURFACE 3			
SSM2= 2CM WILSONART "FROZEN" #Q6023 POLISHED FINISH (SLAB SIZE: 61" X 126") SM3= 2CM WILSONART "TERLINGUA" #Q6024 POLISHED FINISH (SLAB SIZE: 61" X 126") SSM4= 2CM WILSONART "CALACATTA AQUILEA" #Q4056 POLISHED FINISH (SLAB SIZE: 65" X 130")			
SSM2: - COFFEE W1545 (QTY: 1) - COFFEE E1227 (QTY: 1) - COFFEE W2405 (QTY: 1) - COPY RM W2410 (QTY: 1) - STAFF MEDIA E2202 (QTY: 1) - COFFEE E2310 (QTY: 1) - EXEC COPY E2313 (QTY: 1) - DAIS BREAK RM E32205 (QTY: 1) - COFFEE W3405 (QTY: 1) - COPY RM W3410 (QTY: 1) - COFFEE E3107 (QTY: 1)	408.0	<i>SQ. FT</i>	SSM2= 2CM WILSONART "FROZEN" #Q6023 POLISHED FINISH (SLAB SIZE: 61" X 126") APPROX 408.00 SQ/FT CTOP (1-1/2" MITER SQUARE EASE EDGES
SSM3: - LACTATION W1522 (QTY: 1) - STAFF RR W1520 (QTY: 1) - STAFF RR W1521 (QTY: 1) - MENS RR E1105 (QTY: 1) - WOMENS RR E1107 (QTY: 1) - FAMILY RR E1106 (QTY: 1) - STAFF RR E1228 (QTY: 1) - STAFF RR E1229 (QTY: 1) - LACTATION W2414 (QTY: 1) - STAFF RR E2412 (QTY: 1) - STAFF RR E2413 (QTY: 1) - MENS RR E2102 (QTY: 2) - WOMENS RR C2104 (QTY: 2) - FAMILY RR E2103 (QTY: 1) - LACTATION W3414 (QTY: 1) - STAFF RR W3412 (QTY: 1) - STAFF RR W3413 (QTY: 1) - PUBLIC RR E3104 (QTY: 1) - PUBLIC RR E3103 (QTY: 1) - CJ RR E3118 (QTY: 1)	562.6	<i>SQ. FT</i>	SSM3= 2CM WILSONART "TERLINGUA" #Q6024 POLISHED FINISH (SLAB SIZE: 61" X 126") APPROX 562.6 SQ/FT CTOP (1-1/2" MITER SQUARE EASE EDGES
SSM4: -WILCO CAFÉ E2302 (QTY: 1) -WILCO CAFÉ ISLAND E2302 (QTY: 1)	179.1	<i>SQ. FT</i>	SSM4= 2CM WILSONART "CALACATTA AQUILEA" #Q4056 POLISHED FINISH (SLAB SIZE: 65" X 130") APPROX179.1 SQ/FT CTOP (1-1/2" MITER SQUARE EASE EDGES
TRIM			
CHAIR RAIL PROFIEL TBD (STAIN TO MATCH WD1)	55.6	<i>Ln.Ft.</i>	TWC ARCHITECTURAL , PROFILE TBD , STAINED TO MATCH WD1
HR1	66.9	<i>Ln.Ft.</i>	TWC ARCHITECTURAL , PROFILE HR071, STAINED TO MATCH WD1
WB1	811.7	<i>Ln.Ft.</i>	TWC ARCHITECTURAL , PROFILE B752; 3/4" X 3 1/2"H; CHAMFER, STAINED TO MATCH WD1
HARDWARE			
DRAWER LOCK	26.0	<i>QTY</i>	Disc Tumbler Keyed Cam Lock

WALL & CEILING PANELS			
AWP1	2089.7	SQ. FT	TERRAMAI, ACOUSTIC PANELS , SQUARE SLAT, ORHCARD WALNUT , COMMISSIONERS COURT DAVID ANDREWS WITH TERRAMAI DISCUSSED MATERIAL WITH ARCHTEC THE SQUARE SLAT IS NO LONGER AVAILABLE THIS PRICING IS FOR TerraMai Modular Panel - Mini Slat - Orchard Walnut - Oil - FR
AWP2 (FLEX PANELS)	557.2	SQ. FT	TERRAMAI, ACOUSTIC PANELS , FLEX PANEL; SQUARE SLAT, ORHCARD WALNUT DAVID ANDREWS WITH TERRAMAI DISCUSSED MATERIAL WITH ARCHTEC THE SQUARE SLAT IS NO LONGER AVAILABLE THIS PRICING IS FOR TerraMai Flex Panel - Linear Slat-Orchard Walnut - Oil - FR
AWP2A	1375.0	SQ. FT	TERRAMAI, ACOUSTIC PANELS , MODULAR SQUARE SLAT ; SQUARE SLAT, ORHCARD WALNUT DAVID ANDREWS WITH TERRAMAI DISCUSSED MATERIAL WITH ARCHTEC THE SQUARE SLAT IS NO LONGER AVAILABLE THIS PRICING IS FOR TerraMai Modular Panel - Mini Slat - Orchard Walnut - Oil - FR
AWP4	112.2	SQ. FT	ACOUSTIC PANELS , TURF DESIGN , PEAK WALL PANELS, 10 TOPO GREEN, 3RD FLOOR LANDING
MP1	5.0	QTY	METAL PANEL, MOZ METAL , LASER CUT ALUMINUM DECO PATTERNS , WHITE SAND POWDER COAT , COFFEE BARS
WDC1	3498.6	SQ. FT	TERRAMAI, ACOUSTIC PANELS , LINEAR SLAT, - Orchard Walnut - Oil - FR , COMMISSIONERS COURT
WD1 VENERED PANELS	336.0	SQ. FT	BVC - BEST VENEER COMPANY , EURO OAK FUMED QTD , CLEAR FINISH
WP1 3-FORM PANELS	26.0	QTY	3-FORM , 200.52 FULLY FRAMED TOP SUPPORT PARTITION; 2'-10" X 8'H , VARIA; 3/8"; OZNER+CLEAR
PAINT GRADE PLYWOOD GRID	245.3	SQ. FT	PAINT GRADE PLYWOOD GRID (PAINTED BY OTHERS)
WP6 FORBO	6.0	QTY	FORBO TACK WALL
1/2" BULLET PROOF FIBER GLASS PANEL	243.5	SQ. FT	1/2" BULLET PROOF FIBER GLASS PANEL
SHOP FABRICATED FRAMES AND KNEE WALLS			
PLYWOOD KNEE WALL ISLAND AT LEVEL 2 BREAKROOM	11.5	Ln.Ft.	PLYWOOD KNEE WALL ISLAND AT LEVEL 2 BREAKROOM
PLYWOOD KNEE WALL FRAME WORK FOR RECEPTION DESK	24.7	Ln.Ft.	PLYWOOD KNEE WALL FRAMEWORK FOR RECEPTION DESK
BENCH FRAME UNDER STAIRS	65.0	Ln.Ft.	BENCH FRAME UNDER STAIRS
STAFF DESK CUSTOM KNEEWALL	43.2	Ln.Ft.	STAFF DESK CUSTOM KNEEWALL
CUSTOM RADII KNEE WALL AT DIAS / PRESENTER TABLE	36.6	Ln.Ft.	CUSTOM RADII KNEE WALL AT DIAS / PRESENTER TABLE
CUSTOM STEEL WORK			
2x3 TUBE STEEL, HORIZONTAL SUPPORT	130.4	LN FT	2" X 3" STEEL HORIZONTAL SUPPORT AT LEADING EDGE OF COUNTERTOP
WALL SUPPORTS			
A&M 18 x 24 SURFACE MOUNTED SUPPORT	1.0	QTY	A&M 18 x 24 SURFACE MOUNTED SUPPORT
A&M 2.0" 24 x 24" Concealed Brackets	50.0	QTY	A&M 2.0" 24 x 24" Concealed Brackets
A&M 2.0" Extended Concealed Brackets	118.0	QTY	A&M 2.0" Extended Concealed Brackets
UPHOLSTERED BOOTH SEATING			
UPH 2 & 3 BLACK LAMINATED FRAME	12.7	LN FT	BLACK LAMINATED PLYWOOD FRAMEWORK
UPH 6 & 7 BLACK LAMINATED FRAME	16.0	LN FT	BLACK LAMINATED PLYWOOD FRAMEWORK
UPH1 BLACK LAMINATED FRAME	67.1	LN FT	BLACK LAMINATED PLYWOOD FRAMEWORK
UPH1 SEAT BACKS	30.0	LN FT	UPHOLSTERED SEAT BACKS WITH 2" CHANNELS
UPH1 SEAT BOTTOM	30.1	LN FT	UPHOLSTERED SMOOTH SEAT BOTTOMS
UPH2 SEAT BOTTOM	48.5	LN FT	UPHOLSTERED SMOOTH SEAT BOTTOMS
UPH3 SEAT BACKS	48.7	LN FT	UPHOLSTERED SMOOTH SEAT BACKS
UPH6 SEAT BACKS	16.0	LN FT	UPHOLSTERED SMOOTH SEAT BACKS
UPH7 SEAT BOTTOM	16.0	LN FT	UPHOLSTERED SMOOTH SEAT BOTTOMS
ADMINISTRATIVE WORK			
SHOP DRAWINGS	1.0	LOT	SHOP DRAWINGS

MILLWORK QUALIFICATIONS

CABINETS WILL BE BUILT "AWI : CUSTOM GRADE" FRAMELESS CONSTRUCTION
UNLESS NOTED OTHERWISE CABINET INTERIOR TO BE WHITE MELAMINE
TYPICALLY PVC EDGE BANDING IS MANUFACTURED BY A DIFFERENT COMPANY THAN THE PLASTIC LAMINATE. THEREFORE, SOME COLOR DISCREPANCIES MAY OCCUR.
THE FAILURE TO LIST SPECIFIC EXCLUSIONS DOES NOT IMPLY THAT SAID ITEMS, INCLUDING TRIM, ARE INCLUDED BY DEFAULT
ANY CHANGES IN MATERIAL AND/OR COLOR SELECTION AFTER BID DATE CAN AFFECT COST
ANY INSURANCE REQUIREMENT WHERE WE ARE CHARGED AN ADDITIONAL PREMIUM WILL BE CHARGED BACK TO CONTRACTOR
THIS PROPOSAL INCLUDES INSTALLATION OF MILLWORK
OUR PRICE INCLUDES SHOP DRAWINGS
VARIATION NOTE: DUE TO DEVIATIONS IN EXISTING BUILDINGS AND A LACK OF CLEAR PERFORMANCE STANDARDS FOR FRAMING AND DRYWALL, CAULKING OF GAPS BETWEEN CASEWORK AND BUILDING WALLS AND CEILINGS SHALL NOT BE THE RESPONSIBILITY OF THE MILLWORK INSTALLER.
A COPY OF THIS PROPOSAL MUST BE INCLUDED IN THE SUBCONTRACT DOCUMENTS BEFORE ANY WORK BEGINS
THIS PROPOSAL IS VALID FOR A PERIOD OF 30 DAYS.
A RESALE CERTIFICATE MUST BE PROVIDED BY GC FOR COMMERCIAL RENOVATION PROJECTS
BILLING WILL BEGIN UPON SUBMITTAL OF SHOP DRAWINGS

EXCLUSIONS

ANY ADDITIONAL INSURANCE OR BONDING
AWI CERTIFICATIONS AND/OR LABELS ARE EXCLUDED
WALL PANELS : WP2,WP3,WP4,WP5,WP12 , AWP3
WALL TILE : WT1,WT2,WT3,WT4,WT5,WT6,WT6A,WT7,WT7A
BASE : RB1,RB2,TB1,TB2,TB3,TRB1
WINDOW FILM: WF1
TEKNION: DWF,DWF1,DWL,DWM,DWP
NATURAL STONE : NS1
PAINT: PT1,PT2,PT3,PT4,PT5,PT6,PT7,PT8
METAL TRIM : FRY REGLET "F" REVEAL # DRMF-625-V50 WITH SNAP IN REVEAL BEYOND
METAL TRIM : HFRY REGLET MILLWORK CHANNEL #MW410050
METAL TRIM : HAT TRACK , BREAK METAL
METAL TRIM : T1 SCHLUTER , T2 SCHLUTER, T4 SCHLUTER, T5,T6,T7 TERRAZZO & MARBLE SUPPLY COMPANIES, T11 SCHLUTER
WALL COVERINGS : WC1,WC2,WC3,WC4,WC5,WC6,WC7,WC8,WC9,WC10,WC11,WC12,WC13,WC14,WC15,WC16,WC17,WC18
DRAPERY : DRP1
TOILET PARTITIONS: TP1
CEILINGS : ACM1,ACM2,ACM3,ACP1,ACT1,ACT2,EXC1,GYP1,WDC2,
TRASH/RECYCLING SIGNAGE
GLASS AND ACRYLIC : (DAIS WALL C5/A425) 1 1/4" CLEAR BALLISTIC GLAZING; LEVEL 3 PROTECTION ,
GLASS AND ACRYLIC : (CLRK COUNTERS B1/A406) CLEAR ACRYLIC SCREEN AND FRAME
GLASS AND ACRYLIC : (TROPHY DISPLAY D4/A422) SLIDING GLASS LOCKABLE GLASS DOORS
CEILING SUBSTRATES : CEILING GRID AT COMMISSIONERS COURT
KNEE WALLS @ : TAX LOBBY COUNTER , CCR LOBBY COUNTERS , COFFEE BARS AT BOOTH SEATING .
DOORS, FRAMES, HARDWARE AND GLAZING
ANY IN WALL BLOCKING :
Coordination Required areas with Euro-Tex
Staff Restroom W1520 & W1521
Staff Restroom E1228 & E1229
Men's RR E1105, Family RR E1006, Women's RR E1107
Staff Restroom W2412 & W2413
Staff Restroom W3412 & W3413
Restroom E3104 & E3103

SINKS
ANY ITEMS OR TASKS NOT LISTED IN THIS SCOPE.

SPECIAL QUALIFICATIONS**IN-WALL SUPPORT INSTALLATION**

PRE-INSTALLATION REQUIREMENT: IN-WALL SUPPORTS MUST BE INSTALLED BEFORE SHEETROCK, ELECTRICAL, OR PLUMBING WORK.
ADDITIONAL LABOR COST: IF EXTRA VISITS ARE NEEDED DUE TO UNMET INSTALLATION CRITERIA, A CHARGE OF \$75.00 PER MAN-HOUR WILL APPLY.

ACKNOWLEDGMENT**ADDENDUM #4****COMMERCIAL CONDITIONS AND
CLARIFICATIONS**

DUE TO DAILY CHANGES IN OUR WORKLOAD, AND AWAITING RESULTS FROM OUTSTANDING BIDS, WE CAN NOT COMMIT TO A SCHEDULE UNTIL PROJECT HAS BEEN AWARDED ,PROJECT IS SUBJECT TO CREW AND FACILITY CAPACITY AT THE TIME OF AWARD.

AFTER AWARDING THE PROJECT AND SHOP DRAWING SHAVE BEEN AUTHORIZED A SCHEDULE CAN BE PROVIDED. ALTERNATES SHOP DRAWING TYPICALLY TAKE 1-3 WEEKS DEPENDING ON SIZE AND COMPLEXITY OF PROJECT

BREAK-OUT PRICING IS BEING PROVIDED TO AID IN BID EVALUATION & PROGRESS BILLING. WE RESERVE THE RIGHT TO ADJUST

TOTAL NO TAX**\$ 1,968,478.84****BID ALTERNATE # 1 COLUMN COVERS****CC1 & CC2 : COLUMN COVERS,
FORMS+SURFACES, DELIVERY AND
INSTALLATION OF 16 COLUMN COVERS****TOTAL NO TAX****\$ 365,000.00****CONSTRUCTION, DELIVERY, AND INSTALLATION****Acceptance Of Bid Means Acceptance Of Terms**

Terms: Net 30 Days.

Over 30 Day: 1.5% Per Month (\$ 5.00 Min) 18% Per Year

Price is good for 30 days

Signature

Date

**Deck Pavers - 07-0270**

• Basis of Design (Hanover Gridloc Pedestal/Pavers System)	
• Hanover Gridloc Pedestal/Paver System (6"x18", 6"x24", 6"x36")	1 LS
• Gravel Layer	1 LS
• Bond	1 LS

Waterproof, Caulking and Flashing - 07-1000

• Section 071900 Water Repellents	1 LS
• Inclusions:	
• Water Repellents applied to Exterior Stone surfaces only. Includes pressure washing of substrate	1 LS
• Pressure washing stone prior to application of water repellents	1 LS
• Exclusions:	
• Cleaning, patching or repairing of substrates prior to application of water repellents.	
• Section 072100 Thermal Insulation (Rigid Insulation Behind Masonry Only)	1 LS
• Includes 2" Rigid – DuPont Thermax Ci per basis of Design	
• Includes Insulation Adhesive application on back of rigid insulation	
• Includes rigid insulation in wall cavity behind masonry veneer only	
• Includes installation of rigid insulation in horizontal high-hats prior to installation on wall for stone cladding	
• Add:	
• Section 072726 Fluid Applied Membrane Air Barrier	1 LS
• Inclusions:	
• 60 WFT Carlisle Barritech VP Fluid applied membrane air barrier applied to exterior backup walls behind Masonry and Metal Panels.	1 LS
• Includes flashing membrane associated with fluid applied air barrier at openings.	1 LS
• Exclusions:	1 LS
• Cleaning, patching or repairing of substrates, flashing not directly associated with air barrier, metal flashing and trim, flashing associated with roofing, high temperature flashings, foam	
• Add:	
• ABAA QAP Program listed under Section 072726, 1.6	1 LS
• Section 075556 Fluid Applied Protected Membrane Roofing	
• Basis of Design (American Hydrotech with 5" 60psi Dow HI60)	1 LS
• Inclusions:	
• *215 Mil Hot Fluid Applied Waterproofing, with 5" 60psi extruded polystyrene rigid insulation, iapplied to Level 2 and 3 Balconies.	1 LS
• 215 mil Hot Applied Waterproofing with Protection Board and Drainage Composite	1 LS
• 5" 60psi XPS Insulation	1 LS
• Metal Flashings associated with hot applied waterproofing (excludes break form metal at guardrail)	1 LS
• Includes one mobilization and 3 Electronic Leak Detections (assumed one ELD test per balcony)	1 LS
• Hanover Gridloc Pedestal/Paver System (6"x18", 6"x24", 6"x36")	1 LS
• Exclusions:	
• Hot applied waterproofing and pavers at all areas not mentioned above, additional mobilizations, additional ELD tests, galvanized or steel metal plate, break form metal, break form metal at guardrail, rock or ballast, gravel, sand, fabric, PMMA or PUMA Flashings, fire protection layer, delegated design, engineering calculations, cleaning, patching or repairing of substrates, crane for hoisting material, waterproofing at planters, pavers, geofoam, tapered insulation, mortar faced insulation, custom color pavers, expansion joints at decks and all other work not mentioned above.	
• Section 076200 Sheet Metal Flashing And Trim	1 LS
• Inclusions:	
• 26G Stainless Steel sheet metal through wall flashing, behind Masonry only, applied to:	
• Base of Wall	
• Window Heads, Jambs & under Cast Stone Sills	
• Door Heads & Jambs	
• Shelf Angles/Lintels	
• Under Cast Stone Caps per B4/A9	
• Under Door per D1/A212	
• Exclusions:	
• Flashing associated with Metal Panels, Roofing, Prefinished Flashing, subsills, metal extrusions, trim pieces or closure pieces, precast concrete splash pads, counterflashings, gutters, downspouts, cutting of reglets and all other sheet metal not mentioned above.	
• Add for 26G SS through wall metal flashing behind Metal Panels	1 LS
• Section 079100 Preformed Joint Seals	1 LS
• Section 079200 Joint Sealants	1 LS
• Inclusions:	1 LS
• Exterior Silicone Sealants applied to:	1 LS
• Masonry CJs (max ¾")	1 LS
• Masonry to Metal Panel Transitions (max ¾")	1 LS



• Masonry to Soffits (max 1/2")	1 LS
• Hollow Metal Door Frames to Masonry (max 3/8")	1 LS
• Masonry Returns at Jambs per D1/A211	1 LS
• Stone Caps control joints per B4/A009 (max 3/8"; excludes raking back mortar)	1 LS
• Site Polyurethane Sealants applied to:	1 LS
• Site concrete paving CJ and EJ,	1 LS
• Sidewalk EJ,	1 LS
• Sidewalk -to- concrete curb EJ,	1 LS
• Site concrete -to- base of building EJ,	1 LS
• Exclusions:	
• Sealants and caulking associated with interior, roofing, aluminum windows, aluminum storefront systems, aluminum curtainwall, drywall, metal panel CJs, all stone to stone joints, retaining wall joints, asphalt paving, curb to curb EJ, joint sealants or caulking at joints larger than sizes stated in Inclusions, removal of joint filler materials which interfere with installation of joint sealant, and removal of zips strips, wood filler or foreign substances from joint substrates, and all other joint sealants and caulking not specifically listed in Inclusions.	
• Section 079200 Acoustic Joint Sealants	
• Joints	1 LS
• Penetrations	1 LS
• Inclusions:	
• Acoustic Sealant at bottom of interior non-rated drywall partitions (assuming maximum joint size of 1/2") only.	1 LS
• Acoustic Spray at head of interior non-rated drywall partitions (assuming maximum joint size of 1" measured from top of gypsum to bottom of metal deck) only.	1 LS
• Acoustical sealant at control joints of interior non-rated CMU partitions (assuming max joint size of 1" measured from top of CMU wall to bottom of metal deck) only.	1 LS
• Acoustical sealant at the following new penetrations through interior non-rated drywall/CMU partitions (assuming maximum 1/2" annular space):	1 LS
• HVAC chilled and hot water pipe,	1 LS
• HVAC ducts which do not have dampers,	1 LS
• Domestic hot and cold water pipe,	1 LS
• Soil, Waste, and Vent piping, Gas piping,	1 LS
• Fire Protection Piping (sprinklers),	1 LS
• Electrical, Communication, Telecommunication, Security and Fire alarm rigid conduit.	1 LS
• Exclusions:	
• Acoustical sealant/spray associated with joint sizes or annular space exceeding those stated above, at all other conditions not specifically mentioned above, penetrations above ceiling grid on non-rated walls that do not go to deck, putty pads and/or sealant for outlet junction boxes, cleaning or patching of substrates and all other work not specified above.	
• Bond	1 LS
Spray Foam Insulation - 07-2129	
• Section 072129 Sprayed Insulation	1 LS
• Inclusions:	
• Apply R-30 closed cell spray foam insulation with 15 minute intumescent ignition barrier to underside of entire level 1 composite floor deck only as indicated in drawings.	1 LS
• Apply closed cell spray foam to top and bottom of roof deck at exterior wall perimeter to seal deck flutes as shown in detail B2, D1, D2, D4/A710. Intumescent thermal barrier included at interior side only.	
• Includes costs for 3 man crew confined space application at crawl space.	1 LS
• Includes 2 mobilizations.	1 LS
• Add to include sides and bottoms of steel beams at crawlspace:	1 LS
• Exclusions:	
• Any areas not indicated above or shown in shop drawings. Testing, trimming, patching of insulation damaged by others, protection of floor-stocked materials, electrical power for our application, temperature and humidity control of building, additional mobilizations, spray foam in miscellaneous voids, protection of floor stocked materials, protection of MEP installed out of sequence.	
• Safety Equipment for job site personnel other than Alpha Insulation & Waterproofing Employees and Safety Standards that exceed OSHA or Alpha Insulation & Waterproofing Inc. requirements are also excluded.	
• Bond	1 LS

**Metal Wall Panels and Soffits - 07-4213**

• Metal Soffit Panels & Column Covers	1 LS
• Column Covers (05 58 13)	1 LS
• Column covers to be a Metalbond 300 series by Byrne Metals.	1 LS
• Column covers to be 1/8" aluminum having a single custom finish.	1 LS
• Includes secondary framing off columns.	1 LS
• Excludes the interior column covers.	1 LS
• Metal Soffit Panels (07 42 13)	1 LS
• Linear aluminum soffit panels to be a Metalbond 600 series by Byrne Metals.	1 LS
• Panels to have a manufactures standard southern pecan finish.	1 LS
• Includes associated furring, flashing, and sealant.	1 LS
• Soffits will need to be hard framed.	1 LS
• We exclude hanger wires and pre-engineered suspension systems.	1 LS
• We exclude formed aluminum soffit panels.	1 LS
• Bond	1 LS
• Dri Design Metal Panel System:	1 SF
• Dri-Design wall panels,	21,800 SF
• Monarch thermal break z-clips, and Thermax Xarmor 2" (R-13) insulation installed per the manufacturer's recommendations, including all Dri-Design Fasteners/Tracks/Planks/CFMF at our system only.	1 LS
• 11% Material Price Increase Allowance for September per Supplier	1 LS
• Bond	1 LS

Roofing - 07-5400

• Thermoplastic Membrane Roofing	1 LS
• Install a (GAF, Versico, MuleHide) 60 mil PVC fully adhered, over 1/2" cover board, over R-30 (2 layers of 2.6") polyiso roof insulation mechanically fastened and fully adhered to the deck	1 LS
• Includes wall, flashing boots, curb, termination bar, penetration flashings, and edge metal.	1 LS
• Includes two (3'- 8" X 5' – 4") roof hatches with safety railing.	1 LS
• 20-year No Dollar Limit warranty and 2-year workmanship warranty for building and drive-thru.	1 LS
• Walkpads included	1 LS
• Sheet Metal Flashing and Trim	1 LS
• Prefinished metal coping and roof edge trim, fascia trim over white edge metal	1 LS
• Exclusions:	
• Wood blocking, weather barrier, skylight oculus glass dome, fluid applied membrane roofing,	
• 11% Material Price Increase Allowance for September per Supplier	1 LS
• Bond	1 LS

Applied Fire Protection (Fireproofing) - 07-8100

• Inclusions:	1 LS
• Spray apply GCP Z-106/HY cementitious fireproofing to structural steel to achieve 1 hour and 4 hour ratings per R101 and R102 Overall Fireproofing Plans as shown in drawings.	1 LS
• Steel building structure considered thermally unrestrained.	1 LS
• Includes cost for mock up.	1 LS
• Includes 1 mobilization.	1 LS
• Exclusions:	1 LS
• Toweling or squaring of edges. Power, water, weather protection, sandblasting, grinding and other metal working preparation or priming of steel. Patching of fireproofing damaged by others. Testing, tamping and/or troweling of material, dumpster costs, additional mobilizations, and overtime due to no fault of our own. Canopies, crowns, and any steel outside the main building envelope not considered structural.	1 LS
• Bond	1 LS

Firestopping - 07-8400

• 078400 Firestopping (Penetrations)	1 LS
• Firestop at the following new penetrations through interior fire rated floor, drywall/CMU partitions (assuming maximum ½" annular space):	1 LS
• Inclusions:	
• HVAC chilled and hot water pipe,	1 LS
• HVAC ducts which do not have dampers,	1 LS
• Domestic hot and cold-water pipe,	1 LS
• Soil, Waste, and Vent piping, Gas piping,	1 LS
• Fire Protection Piping (sprinklers),	1 LS
• Electrical, Communication, Telecommunication, Security and	1 LS
• Fire alarm rigid conduit.	1 LS
• Exclusions:	
• Firestop associated with annular space exceeding those stated above, Identification/Labeling of rated penetrations, W-Rated Firestop Systems, F=T Firestop Systems, non-metallic piping (contact Alpha for additional costs), cable pathway devices, aluminum rigid conduit, putty pads and/or sealant for outlet/junction boxes, cleaning or patching of substrates and all other work not specified above.	
• 078400 Firestopping (Joints)	
• CMU	1 LS
• Gypsum	1 LS
• Perimeter Fire Containment	1 LS
• Inclusions:	
• Firestop Sealant at bottom of interior fire-rated drywall partitions (assuming maximum joint size of 1/2") only.	1 LS
• Firestop Spray at head of interior fire-rated drywall partitions (assuming maximum joint size of 1" measured from top of gypsum to bottom of metal deck) only.	1 LS
• Firestop Sealant at vertical joints of interior fire-rated drywall partitions at concrete/CMU wall or column (assuming maximum joint size of 1/2") only.	1 LS
• Firestop Spray at head of interior fire rated CMU partitions (assuming maximum joint size of 1" measured from top of CMU wall to bottom of metal deck) only.	1 LS
• Firestop Sealant at control joints of interior fire rated CMU partitions (assuming max joint size of 1/2") only.	1 LS
• Firestop Spray at pockets around Steel Beams and/or Bar Joists penetrating rated Partitions (assuming opening framed with steel cold rolled framing by others) with a maximum 1" space beyond beam/bar joist flanges.	1 LS
• Perimeter Fire Containment (Metal-Stud Wall) bypassing rated slab edge. Install unfaced safing and acrylic based firestop at joint between slab and sheathing. Reference D3/A718 with maximum 8" joint width.	1 LS
• Perimeter Fire Containment (Metal-Stud Wall) sitting on slab edge. Install unfaced safing and acrylic based firestop within metal track. Reference D4/A708 with maximum 8" joint width.	1 LS
• Exclusions:	
• Vertical joint at intersection of interior partition(s) to exterior wall, formaldehyde free mineral wool, dead load anchor protection, Firestop associated with joint sizes exceeding those stated above, Identification/Labeling or Stenciling of fire rated walls, perimeter fire containment, putty pads and/or sealant for outlet/junction boxes, cleaning or patching of substrates and all other work not specified above.	
• Bond	1 LS

Doors, Frames and Hardware - 08-0100

• SECTIONS:	1 LS
• 081113 Hollow Metal Doors and Frames	1 LS
• Doors - Hollow Metal	48 EA
• Doors - Hollow Metal STC 55	2 EA
• Doors - Hollow Metal STC 56	2 EA
• Frames - Hollow Metal 3 Sided STC 52	9 EA
• Frame - Hollow Metal 3 Sided STC 55	1 EA
• Frame - Hollow Metal 3 Sided STC 56	1 EA
• Frames - Hollow Metal 3 Sided	118 EA
• 081416 Flush Wood Doors	1 LS
• Doors - Wood STC 52 Quarter Sliced Euro Oak Fumed (BVC)	9 EA
• Doors - Wood - 1 3/4 SC Quarter Sliced Euro Oak Fumed (BVC)	89 EA
• 087100 Door Hardware	1 LS
• Hardware	1 LS
• Sound Control Door Assemblies (No Spec)	1 LS
• Bond	1 LS
• Hollow Metal Doors and Frames	
• Leadtimes after Approval and Answers to all Questions:	



- Hollow Metal Doors 16-18 Weeks
- Hollow Metal Frames Please call us to discuss
- **Exclusions:**
 - Prefinishing
 - Glass
 - Field Measuring
- **Inclusions:**
 - One door shipment
- **Qualifications:**
 - Lite kits for hollow metal doors will be shipped loose to be field installed by others.
- **Flush Wood Doors**
 - Leadtimes after Approvals and Answers to all Questions:
 - 11-13 Weeks
 - **Exclusions:**
 - Glass/glazing
 - **Inclusions:**
 - Prefinishing (1 stain color only) based on the manufacturer's standard finishing system
 - 1 approval/shipment for the entire project
 - **Qualifications:**
 - Our price is based on supplying the wood doors with manufacturer's standard stock Grade "A," book and running matched, quarter sawn, Euro Oak Fumed face veneers.
 - Modifications of some lite sizes may be required in order to maintain the warranty.
- **Door Hardware**
 - Leadtimes after Approvals and Answers to all Questions
 - Hardware: 7-8 Weeks
 - Please note that lead times are subject to change due to fluctuating availability
 - **Exclusions**
 - Aluminum Storefront Door Hardware
 - Demountable Wall System Door Hardware
 - Vault Door Hardware
 - Overhead Door Hardware
 - Installation of automatic door operators
 - Card Readers
 - Door Contacts
 - Power Supplies
 - **Inclusions**
 - Automatic door operators to the extent shown.
- **Sound Control Door Assemblies**
 - Leadtimes after Approval and Answers to all Questions:
 - STC Doors and Frames 23-25 Weeks
 - **Exclusions:**
 - Prefinishing
 - Field Measuring
 - **Inclusions:**
 - One shipment
 - **Qualifications:**
 - Due to manufacturer restriction the maximum acoustic rating is STC 55 at a paired fire rated steel door unit, Opening W1703A
 - Please note, the estimated leadtime quoted above is based on the manufacturer's current leadtimes for the products as bid and qualified herein. With the seasonal fluctuations in the availability of materials and labor, the leadtime is an anticipated estimate only and is not a guarantee of the actual leadtime at time of full approval.

**Glass & Glazing & Storefronts - 08-0400**

• Base Bid	1	LS
• Supply of specified hardware sets per section 087100	1	LS
<ul style="list-style-type: none"> • Hardware sets: #103A (4x), 403A (1x), 501A (13x), 501AC (1x), 501 AW (1x), 505AW (1x), 507A (1x), 701AC (1x), 714AM (1x), 715A (1x), A710ACM (1x), A710ACM-1 (3x), AC714AM (2x), C201 R (1x), C2051W (1x), C710ACM (1x), C714AM (1x), C715A (2x; door operators included). • Electrical integration, door contact, card reader, power supply by others. 		
• Joint Firestopping and Thermal Curtain Wall Insulation	1	LS
<ul style="list-style-type: none"> • Perimeter Fire Containment (Glass-Curtain Wall) at rated slab edge. Install 3"FSK faced mineral wool insulation mechanically fastened within mullions. Install unfaced sating and acrylic based fire stop at joint between slab and curtainwall insulation. Install 3FSK faced mineral wool insulation within mullions at non-fire rated spandrel panels with perimeter taped to frame. 		
• Aluminum Entrance and Storefronts		
• Curtain Wall	27,408	SF
<ul style="list-style-type: none"> • 2 ½" x 7 ½" Charcoal Painted Finish, Steel Reinforcing, T/F anchors, steel anchors, horizontal SSG mullions. • 2-year Manufacturer warranty, 20- year Finish Warranty. • CW Frames: W1E (1x), W2E (1x), W3E (1x), W4E (1x), W6E (10x), W5E (1x), W7E (1x), W8E (1x), W11E (2x), W12E (1x), W13E (4x), W14E (14x), W16E (1x), W15E (1x), W17E (1x), W18E (1x), W19E (3x), W20E (2x), W21E(2x), W22E (1x), W23E (1x), W24E (3x), W25E (3x), W26E (2x), W27E (10x), W28E (1x), W29E (1x), W30E (1x),W31E (1x), W32E (1x), 2x mockups D3/A010. • Note. D1 & D2 /A213, D2/A214, D1/A215, D1/A718 custom extrusion 'aluminum curtainwall trim' in Charcoal painted finish included. 		
• Interior Storefront (3146SQFT)	3,146	SF
<ul style="list-style-type: none"> • 2" x 4 ½", Center-set, Charcoal painted Finish • SF Frames: W1 I (1x), W2I (1x), W3I (1x), W4I (1x), W6I (3x), W7I (1x), W8I (1x), W10I (1x), W12I (2x), W14I (1x), W15I (1x), W16I (1x), W17I (2x), W30I (1x), W20I (1x), W21I (1x), W22I (2x), W23I (1x), W24I (1x), W25I (1x), W26I (1x), W27I (1x), W28I (1x), W29I (1x). 2-year Manufacturer warranty, 20-year Finish Warranty. 		
• Aluminum Storefront Doors	46	Leafs
<ul style="list-style-type: none"> • Thermal Wide Stile Entrances@ Exterior, Non-thermal Wide Stile Entrances@ Interior, 10" Bottom rail, Charcoal painted finish, open for 1" infill @ exterior, ¼" infill @ interior. 2-year Manufacturer warranty, 20-year Finish Warranty. • 9x pairs, 28 singles. • Per PB 19 Response, all entrances bid Wide stile to accommodate for specified hardware. 		
• Door Hardware		
<ul style="list-style-type: none"> • Installation of Hardware sets: #103A (4x), 403A (1x), 501A (13x), 501AC (1x), 501 AW (1x), 505AW (1x), 507A (1x), 701AC (1x), 714AM (1x), 715A (1x), A710ACM (1x), A710ACM-1 (3x), AC714AM (2x), C201R (1x), C2051W (1x), C710ACM (1x), C714AM (1x), C715A (2x). 		
• Sliding/Folding Glazed Doors		
<ul style="list-style-type: none"> • SI 3000 Aluminum Folding Glass Wall, Sx panels, 188 ¼" x 93 ¾", 05LR configuration, 1" IG: Solarban 90 Clear/Clear Tempered with Argon, 2-coat custom painted finish to match 'Charcoal'; including semi-concealed hinges, door catch, unkeyed 2-point lock, single rail, extruded hinge pull. D#E2201C. 		
• Brake Metal (1560LNFT.)	1,560	LF
<ul style="list-style-type: none"> • 24GA prefinished Charcoal Grey Berridge Galvalume Steel flashing@ curtain wall sill conditions D1/A213, D2/A213, D4/A213, D2/A214, D4/A214. • Note. All other flashing/break metal terminating other structural elements and preceding glazing scope excluded. (ref. exclusions) 		
• Brake Metal		
<ul style="list-style-type: none"> • .125" brake metal corners in charcoal grey painted finish @C2/A215, D2/A215, C4/A215, D4/A215, B1/A212, B3/A212. • Rockwool Comfortbatt R-15 insulation included. 		
• Sunshade Devices		
<ul style="list-style-type: none"> • Per RFI PB 26 Response, Kawneer custom die 18" profile accepted- 2 coat painted finish. @ curtainwall W16E. 		
• Display Cases		
<ul style="list-style-type: none"> • Display Sliding XX Glass doors with¼" clear tempered glass, track assembly, jamb trim, Adams rite lock and cylinders, Adams rite recessed pull, Clear Anodized Finish. Ref. D2/A410 . 		
• Acrylic Clerk Windows		
<ul style="list-style-type: none"> • ½" Acrylic, 1" u-channel, L-brackets. Ref. B1.A406, D1/A406, D2/A406, D4/A206 		
• Glass		
• Exterior Glass GL-1	14,656	SF
<ul style="list-style-type: none"> • 1" IG Low-e: ¼" Solarban 90 Clear Tempered #2 + ½" A.S. +¼" Clear Tempered 		
• Exterior Glass GL-1 OVERSIZED	2,750	SF
<ul style="list-style-type: none"> • 1" IG Low-e *OVERSIZED*:Â¼" Solarban 90 Clear Tempered #2 + Â½" A.S. +Â¼"Clear Tempered 		
• Exterior Glass GL-2	6,706	SF
<ul style="list-style-type: none"> • 1" IG: ¼" Solarban 90 Clear Tern pered #2 + ½".A.S. + ¼" Clear Tempered with Black Opacity. 		



• Exterior Glass GL-4	2,231 SF
• 1" IG: ¼" Solarban 90 Clear Tempered #2 + ½" A.S. + ¼" Clear Tempered with Opacity White Custom.	
• Monolithic Glass GL-5	2,533 SF
• 1/4" Clear Tempered	
• Fire Rated Glazing	
• 5/16" FireLite Plus 45 min, Door type NN (4x door lites)	1 LS
• Decorative Film WFI	
• Level Standard Repeat Window Film: LSWF006-40 Lindsey Linear (167 SF) located @ Interior Storefront W10I.	167 LF
• Ballistic Clear Glazing	
• Installation of (6x) 48" x 30" butt glazed rated UL 752 Level 3: 1-¼" LP 1250 ballistic rated (laminated acrylic polycarbonate) with stainless steel standoffs and stainless steel u-channel on top.	1 LS
• Fire Rated Assemblies	
• 60 min rated 'Aluminum Series' (Steel) assemblies glazed with 60 min rated Pyrostop, Powder coat Standard Finish. Frames: W9I (3x), W5I (1x), W11I (2x), W18I (2x)	1 LS
• 60 min rated doors: 8 singles: W1103B, W1208, E1206, E1205, W2103B, W3103B, E2101A, E2101B along with compatible hardware in compliance of fire testing: cylinder, Von-duprin CVR/RIM exit devices, LCN closer, smoke seal, EPT 10, removable mullion, welded pivot hinge, auto-operator, electrified hinge, center pin. Note. Per Technical Glass product, all must be fire tested to withstand designated rating. Section 08 71 00 specifies hardware for Hollow Metal doors. TGP match them to fit their system.	1 LS
• Exclusions: actuator, harness, position switch, card reader, power supply and electrical integration.	
• Sealant	
• Perimeter Sealant	19,398
• Exterior Perimeter Sealant, Interior Perimeter Sealant, Backer Rod.	1 LS
• 3 beads at curtainwalls and SSG Horizontals	1 LS
• Labor	1 LS
• Administration	
• Engineering	1 LS
• Shop- drawings	1 LS
• Miscellaneous	
• Equipment Rental	1 LS
• Exclusions: seamless joints, stainless steel 316, reinstallation of base shoes with waterproofing, embeds, temporary railing/protection, coring, fire watch, texture, any supporting structural steel, bond, OCIP, CAD drawings, embeds, bent glass, structural steel tolerances, union labor, any railing scope beyond listed above	
• Bond	1 LS

Glass & SS Rails - 08-0550

• System 1: SHOE Glass Railing	
• (424 LF): 2 ¾" x 4" aluminum base shoe, ¾" clear laminated tempered glass with u-cap top rail in Satin finish, 20GA standard 4 brushed aluminum cladding. Note, mounting shown on details 84/A773 & 04/A 77 7 would not work. Steel angle is needed to top mount the base shoe. Steel substructure/angle [provided and installed by others]. 84/A773 & 04/A 77 7 details will be adjusted to reflect bent steel angle overlapping capstone and base shoe will be top mounted on its surfaces. The sequence of work to be coordinated. All railing bid at 42" A.F.F.	424 LF
• System 2: Blade Multi-line Railing	171 LF
• 2" double flat post, Blade multi panel infill, 1-½" top/assist/wall rail in SS304 Satin #6 Finish, FSR 1-½" diameter tube and FSR 1-½" top rail, (Note. quote assumes posts will be mount on steel substructure as shown on detail B3-C4/A617- to be provided & installed by others).	
• System 3: Shoe Glass Railing	
• 6' O" x 3' 6" Mock-up per B3/A.010: 2 panel infills with ¾" clear laminated tempered glass, 2 ¾" x 4" aluminum base shoe, top rail S.S. 304 Satin #6 Finish and 20 GA standard 4in Satin S.S. cladding. Total 6LF. as well as 4' x 3' 6" Mock up (SYSTEM 2) per spec 05 7311-1.8.	6 LF
• System 4: FSR.	
• 1-½" Post diameter tube SS 304 Satin #6 with FSR top rail - IRAIL linear LED Lighted. Total 50 LF..	50 LF
• System 5: Wall Rail:	
• 1-½" SS Rail 304 Satin #6. Ref. to A611, A618. Total 122 LF.	122 LF
• System 6: Hand-Rail:	
• 1-½" assist/wall rail in SS 304 Satin #6 Finish; along with FSR post/top rail. Total 328 LF. Note, Steel post guardrail need to be pre-drilled and pre-fabricated to install VIVA post brackets.	328 LF
• 5x mobilizations, shop drawings. 2-revisions and Performance and Payment Bond included	

**OH Doors & Grilles - 08-3323**

• 12-0 x 12-0, Mark W1703C, W1804C	2 EA
• Cornell Iron Works Model ESD20, motor operated, face of wall mount, interior coil weathered Thermiser, insulated, 24 gauge, powder coated galvanized steel curtain, single guide weathering, lintel brush seal, electric sensing edge, best cylinder with removable key core	
• 4-0 x 4-0, Mark W1102	1 EA
• Cornell Iron Works Model ESC10 push-up, between jambs, interior coil counter shutter, 18 gauge, powder coated aluminum curtain, best cylinder with removable key core	

Sealed Concrete - 09-0650

• Sealed Concrete: CON-1	15,619 SF
• Inclusions:	
• Normal Working Hours.	1 LS
• Supervision	1 LS
• Liability and Workers Compensation	1 LS
• Minor Patching	1 LS
• Temp Floor Protection	1 LS
• Exclusions:	
• Electrical Power	
• Lighting	
• Dumpster	
• Floor Protection	
• Floor Leveling	
• After Hours Work	
• Parking	
• Mechanical Pad Coatings	

Drywall - 09-2000

• BIM for interior walls	1 LS
• ACT - 1 and 2	1 LS
• ACM - 1, 2, 3	1 LS
• AWP- 3 and 4	1 LS
• ACP - 1	1 LS
• WDC - 2	1 LS
• Provide and install WP 5	1 LS
• Access Panels and floor access hatches allowance	1 LS
• Install Wall Rails	1 LS
• Bond	1 LS
• Excludes:	
• Rigid Insulation	
• Spray Foam Insulation	
• Z Furring	
• Curtain Wall insulation	
• Column covers	
• Dais floor framing	
• Bullet proof panels	
• AWP - 1	
• AWP - 2	
• WDC - 1	
• WP -1 thru 4	

**Ceramic & Stone - 09-3000**

• Bond		
• FT1 Floor Tile @ Rr's	4,230	SF
• Includes Crack Water Proofing Membrane; Thinset; Urethane Grout		
• Crossville Ceramics ® Bone- Ups		
• Alaska - 12" X 24"		
• FT2 Floor Tile @ 2ND Floor Lobby	6,295	SF
• Includes Crack Isolation Membrane; Thinset; Cementitious Grout / Sealer		
• Crossville Ceramics ® Bone - Ups		
• Alaska - 24" X48"		
• FT3 Floor Tile @ Breakroom	871	SF
• Includes Crack Isolation Membrane; Thinset; Cementitious Grout / Sealer		
• Dal-tile Artic White		
• Keystone 2X2 Mosaics / D617		
• FT4 Floor Tile @ Breakroom	110	SF
• Includes Crack Isolation Membrane; Thinset; Cementitious Grout / Sealer		
• Dal-tile Black / Ebony		
• Keystone 2X2 Mosaics /D311		
• FT5 Floor Tile @ 2ND & 3RD Floor Lobby	89	SF
• Includes Crack Water Proofing Membrane; Thinset; Trucolor Urethane Grout		
• Crossville Ceramics ® Alaska / Bone - Ups		
• Alaska - 2X2 Mosaic		
• WT1 Wall Tile @ Rr's	2,952	SF
• Includes Thinset; Trucolor Urethane Grout		
• Crossville Ceramics ® ravertine Sand		
• Accent Point 12 X 24 Ups		
• WT2 Wall Tile at Breakroom	161	SF
• Includes Thinset; Trucolor Urethane Grout		
• Lili Tile Mia 4 White 100		
• Mia Tile 8" X 8" Navy Blue 4012		
• WT3 Wall Tile at Coffee Bars	113	SF
• Includes Thinset; Trucolor Urethane Grout		
• Dal-tile		
113.00		
• Miramo Linear Mosaic 1" X 6"		
/ MR47		
• WT4 Wall Tile @ RR's - Vanities	1,259	SF
• Includes Thinset; Trucolor Urethane Grout		
• Crossville Ceramics ®		
Handwritten 3"x12"		
• WT5 Wall Tile @ Commissioner's Area		
• Includes Thinset; Trucolor Urethane Grout		
• Concept Surfaces		
• Salerno Dimensional 1X1 Mosaic (12X12 Mesh)		
• WT6 Wall Tile at Breakroom Bar		
• Includes Thinset; Trucolor Urethane Grout		
• Dal-tile		
• Miramo Picket Undulated 2 X 5		
• WT6A Wall Tile @ Breakroom Bar		
• Includes Thinset; Trucolor Urethane Grout		
• Dal-tile		
• Miramo - Jolly 1/2" X12"		
• WT7 & WT7A Wall Tile @ Breakroom Booth		
• Includes Thinset; Trucolor Urethane Grout		
• Dal-tile		
• Color Wheel Classic 3" X 6"		
/ 0190		
• TB1 Base @ Rr's	1,114	EA
• Includes Crack Water Proofing Membrane; Thinset; Trucolor Urethane Grout		
• Crossville Ceramics ®		
Alaska - 6X12 Cove Base		
• TB2 Base		
• Includes Crack Water Proofing Membrane; Thinset; Trucolor Urethane Grout		
• Crossville Ceramics ®		
Alaska - 4X24 Bullnose		
• TB3 Base @ Breakroom	176	EA
• Includes Crack Water Proofing Membrane; Thinset; Trucolor Urethane Grout		
• Dal-tile		
• Keystones - MB5A Built up Base 2" X 2", Flat Top		



• T1 Metal Wall Tile Transitions		142 EA
• Schluter® Systems	Satin Anodized	
• Schiene AE100	Aluminum	
• T2 Metal Floor Tile Transitions to Carpet		23 EA
• Schluter® Systems		
• Dark Anthracite Schiene Trendline A100 TSDA		
• T4 Metal Floor Tile Transitions to Concrete		5 EA
• Colors Not Available		
• Schluter® Systems	Satin Anodized	
• Reno - V Aevt 100 B30	Aluminum	
• T11 Metal Floor Tile Transitions to Laf		1 EA
• Colors Not Available		
• Schluter® Systems	Satin Anodized	
• Reno - V Aevt 100 B30	Aluminum	
• Sealant as Required Per Section 079200 (tile to Tile)		110 EA
• Hydroment		
• Siliconized Acrylic Latex Caulk (sanded)		
• Attic Stock Supply Material Only		1 LS
• 1% of Each Tile Used		
• Flooring Solutions Inc. Tile		
• Floor Prep		250 EA
• Temp Floor protection as needed		1 LS
• Bond		1 LS
• Attic Stock		1 LS

Terrazzo Flooring - 09-5100

• Terrazzo Floor per finish plans	10,705 SF
• Precast Base	1 LS
• 1 Stair	1 LS
• Floor Protection	1 LS
• 2 Elevator Floors	1 LS
• 100% ISO Crack Membrane	1 LS
• Moisture Mitigation Membrane	1 LS
• Mockup	1 LS
• Bond	1 LS
• Extra mob for elevator floor install	1 LS

**Resilient Flooring and Carpet - 09-5200**

• CPT-1 Carpet Supplied and Installed	5,663 SY
• Patcraft Commercial Carpets	
• Skill	
• Color Name/Number	
• Moxie	
• CPT-2 Carpet Supplied and Installed	359 SY
• Interface Flor	
• Play the Angle 25CMX1M	
• CPT-3 Carpet Supplied and Installed	625 SY
• Shaw Commercial Carpets	
• Process Tile	
• CPT-4 Carpet Supplied and Installed	54 SY
• Interface Flor	
• Past Forward Collection- Decades	
• CPT-5 Carpet Supplied and Installed	275 SY
• Interface Flor	
• Open Air 418	
• CPT-6 Carpet Supplied and Installed	65 SY
• Shaw Commercial Carpets	
• Cross Weave	
• EF-1 Entrance Flooring Supplied and Installed	59 SY
• Shaw Commercial Carpets	
• Divvy Tile	
• Adhesive Materials Supplied Only	43 EA
• Patcraft Commercial Carpets	
• 500Op Carpet Tile Adhesive	
• ESD Tile 1 Supplied and Installed	1,120 SF
• Roppe® Corporation	
• Esd Vinyl Flooring Static Dissapative 24"X24"	
• Adhesive Materials Supplied Only	4 EA
• Roppe® Corporation	
• Adhesive - ASD-800 (esd Adhesive)	
• LVT-1 Vinyl Tile Supplied and Installed	1,991 SF
• Interface Flor	
• Drawn Lines	
• Adhesive Materials Supplied Only	7 EA
• Interface Flor	
• Adhesive - XL 2000 Plus	
• Stair Treads Supplied and Installed	140 EA
• Roppe® Corporation	
• Stair Tread - Rubber #96 Raised Circular Vantage	
• Designw/rsr-sn 66"	
• Stair Nose Epoxy Caulk	27 EA
• Roppe® Corporation	
• Adhesive - 610 Epoxy Nose Filler	
• Rub-1 Rubber Tile Supplied and Installed	2,021 SF
• Stair Landings	
• Roppe® Corporation	
• Rubber Tile - #992 Low Profile Raised Circular	
• Design 50CMX50CMX1/8"	
• Rub-2 Rubber Tile Supplied and Installed	344 SF
• Roppe® Corporation	
• Rubber Tile - #970 Smooth 50 CM X 50 CM X 1/8"	
• Adhesive Materials Supplied Only	8 EA
• Roppe® Corporation	
• Adhesive - Aw 510 Rubber Tile & Tread 4 Gal	
• Rb-1 Wall Base Supplied and Installed	12,240 LF
• Roppe® Corporation	
• Wall Base - Pinnacle -COVE-4" Roll	
• RB-2 Wall Base Supplied and Installed	120 LF
• Roppe® Corporation	
• Wall Base - Pinnacle -COVE-4" Roll	
• Transitions	10 EA
• Schluter® Systems	
• Scheine AE-80 Satin Anodized Aluminum	
• Transitions	10 EA
• Roppe® Corporation	



• Reducer- Vinyl- #169 1/4" Glue Down Reducer	
• Transitions	1 EA
• Roppe® Corporation	
• Reducer- Rubber- #22 1/8" X 1" Reducer Strip- 9' Lgth	
• Floor Prep Estimate	250 EA
• Flooring Solutions Inc.	
• Labor	
• Temp Floor protection as needed	1 LS
• Addition 250 Bags of Floor Prep	250
• Attic Stock	
• CPT-1 Attic Stock	267 SY
• Patcraft Commercial Carpets	
• Skill	
• CPT-2 Attic Stock	18 SY
• Interface Flor	
• Play the Angle 25CMX1M	
• CPT-3 Attic Stock	30 SY
• Shaw Commercial Carpets	
• Process Tile	
• CPT-4 Attic Stock	6 SY
• Interface Flor	
• Past Forward Collection- Decades	
• CPT-5 Attic Stock	18 SY
• Interface Flor	
• Open Air 418	
• CPT-6 Attic Stock	5 SY
• Shaw Commercial Carpets	
• Cross Weave	
• EF-1 Attic Stock	5 SY
• Shaw Commercial Carpets	
• Divvy Tile	
• ESD Tile 1 Attic Stock	80 SF
• Roppe® Corporation	
• Esd Vinyl Flooring Static Dissapative 24"X24"	
• LVT-1 Attic Stock	108 SF
• Interface Flor	
• Drawn Lines	
• Rub-1 Attic Stock	86 SF
• Stair Landings	
• Roppe® Corporation	
• Rubber Tile - #992 Low Profile Raised Circular	
• Design 50CMX50CMX1/8"	
• Rub-2 Attic Stock	43 SF
• Roppe® Corporation	
• Rubber Tile - #970 Smooth 50 CM X 50 CM X 1/8"	
• Rb-1 Attic Stock	120 LF
• Roppe® Corporation	
• Wall Base - Pinnacle -COVE-4" Roll	
• Bond	1 LS

Epoxy Flooring - 09-6723

• Resinous Flooring LAF-1	6,324 SF
• Inclusions:	
• Normal Working Hours.	1 LS
• Supervision	1 LS
• Liability and Workers Compensation	1 LS
• Minor Patching	1 LS
• Floor Protection	6,324
• Exclusions:	
• Electrical Power	
• Lighting	
• Dumpster	
• Floor Protection	
• Floor Leveling	
• After Hours Work	
• Parking	
• Mechanical Pad Coatings	

**Paint and Wallcovering - 09-9100**

• Tape, Bed and Paint Walls	1 LS
• Accent Colors per Plans	1 LS
• Painting of Exposed Deck per RCP	1 LS
• Staining of Wood Base	1 LS
• Furnish and Install Wallcovering per Finish Plan	1 LS
• Painting of Hollow Metal Doors and Frames	1 LS
• Painting of Pre-primed Ferrous Steel at Stair Systems	1 LS
• Tape & Float Level 2 Shell Space	1 LS
• Texture at Walls	1 LS
• Paint Plywood Squares with level 5 wall finish	1 LS
• Bond	1 LS

Fire Extinguishers & Cabinets - 10-0950

• Fire Extinguisher Cabinets	31 EA
• Fire Extinguishers	35 EA

Misc Office Equipment - 10-1133

• Cabinets	4 EA
• Cash Boxes	32 EA
• Literature Racks	4 EA
• Wire Shelving	4 EA
• Markerboards	17 EA
• Tackboards	32 EA

Toilet Room Partitions & Accessories - 10-2113

• Provide and Install the following	1 LS
• Toilet Compartments	34 EA
• Urinal Screens	5 EA
• Baby Changing Stations	6 EA
• Grab Bars	38 EA
• Mirrors	39 EA
• Mop Holders	5 EA
• AED Cabinets	7 EA
• AED Device	7 EA
• Knox Box (Not shown on Plans)	2 EA
• Bond	1 LS

Demountable Partitions - 10-2219

• See attached proposal	1 LS
• Bond	1 LS

Curtain & Curtain Track - 10-2123

• Deviations and Omissions: Discussion of curtain machine, power, and switch placement ongoing. Proposed with 2 curtains in the dais area.	2 EA
• Quote assumes building structure is sufficient to support all loads.	
• All powder coated items shall be RAL colors in 100% Gloss sheen. Other color/sheen combinations will require additional time and cost if applicable.	
• Power for RFI is covered in Electrical Scope	
• PE stamp on record drawings is not included.	
• Fabrication: 12-16 weeks	
• Installation: 2 mobilizations. 5-6 working days. Curtains install after site is verified dust free.	

Wall Protection - 10-2600

• Temporary walll protection	1 LS
------------------------------	------



PROPOSAL TO:
CHASCO CONSTRUCTORS LTD
PROJECT: WILLIAMSON COUNTY NEW HEADQUARTERS
GEORGETOWN TX

CONTACT:
Raquel S Daniel
214.908.3235

RFP / BUDGET SUBMITTAL
DATE: 6.27.2024

AREA	DESCRIPTION	LINEAR FEET	UNIT PER LF	EXT TOTAL
Teknion ALTOS Wall System - 10'-0"H				
Glass Type: Framed glass fascias in 6mm Clear Tempered, Single Glazed, 4" Profile STC: 31				
Metal Finish: Teknion Paint Anthracite				
Floor Tolerance: +1-3/4" Expansion & -1/4" Compression				
LEVEL 01				
DM01 STOREFRONT WALL TYPE	36" Laminate, 80"Framed Glass, 4" Ceiling Fascia, Power per Elec Plan; Monolithic Tech Panel 8"W Door Type: Framed Glass Pivot Door with 10" ADA Kickplate, Cal-Royal Pioneer SL00 Entrance/Office Lock OR SL30 Passage Set (as scheduled)	300	\$ 498	\$ 149,445.00
DM02 Office Demising Walls	36" Laminate, 48"Fabric Gr2, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	80	\$ 351	\$ 28,080.00
DM03 MB Wall-2 Sides	36" Laminate, 48"Markerboard, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	0	\$ 421	-
DM04 MB Wall 1-Side	36" Laminate, 48"Markerboard, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	50	\$ 405	\$ 20,250.00
DM05 Offie Accent Wall	36" Laminate, 48"Fabric Gr 2, 32"Clerestory 4" Ceiling Fascia Back - 84"Fabric, 32" Clerestory; Power per Electrical Plans	12	\$ 359	\$ 4,309.20
DM06	36" Laminate, 48"Fabric Gr 2, 32"Clerestory 4" Ceiling Fascia Back - 84"Fabric, 32" Clerestory; Power per Electrical Plans	92	\$ 356	\$ 32,788.80
DM07	84"Fabric Gr 2, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	330	\$ 358	\$ 118,057.50
DM10 Cutable @ Window Wall	12-0"H Altos Wall, Monolithic Laminate To be field cut on site	28	\$ 351	\$ 9,828.00
LEVEL 01 - SUBTOTAL (ALL WALLS)		892		\$362,758.50
LEVEL 02				
DM01 STOREFRONT WALL TYPE	36" Laminate, 80"Framed Glass, 4" Ceiling Fascia, Power per Elec Plan; Monolithic Tech Panel 8"W - Door	290	\$ 498	\$ 144,463.50
DM02 Office Demising Walls	36" Laminate, 48"Fabric Gr2, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	65	\$ 351	\$ 22,815.00
DM03 MB Wall-2 Sides	36" Laminate, 48"Markerboard, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	12	\$ 421	\$ 5,054.40
DM04 MB Wall 1-Side	36" Laminate, 48"Markerboard, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	92	\$ 405	\$ 37,260.00
DM05 Offie Accent Wall	36" Laminate, 48"Fabric Gr 2, 32"Clerestory 4" Ceiling Fascia Back - 84"Fabric, 32" Clerestory; Power per Electrical Plans	112	\$ 359	\$ 40,219.20
DM06	36" Laminate, 48"Fabric Gr 2, 32"Clerestory 4" Ceiling Fascia Back - 84"Fabric, 32" Clerestory; Power per Electrical Plans	190	\$ 356	\$ 67,716.00
DM07	84"Fabric Gr 2, 32"Clerestory 4" Ceiling Fascia Double Sided; Power per Electrical Plans	48	\$ 358	\$ 17,172.00
DM10 Cutable @ Window Wall	12-0"H Altos Wall, Monolithic Laminate To be field cut on site	18	\$ 351	\$ 6,318.00
LEVEL 02 - SUBTOTAL (ALL WALLS)		827		\$341,018.10